# **ELECTRONIC SUBMISSION**

TECHNICAL PROPOSAL | VOLUME I

I-81 WIDENING MM 136.6 TO MM 141.8 ROANOKE COUNTY AND CITY OF SALEM, VIRGINIA

State Project No.: 0081-080-946, P101, R201, C501, B677, B678, B681, B682, B683, B684, B685, B686, B687, B688 Federal Project No.: NHPP-0812 (330) Contract ID Number: C00116203DB108





in association with Lead Designer





MARCH 3, 2021



die

d

March 3, 2021



– Joint Venture –

in conjunction with Lead Designer

Bryan Stevenson, PE, DBIA Alternative Project Delivery Division Virginia Department of Transportation 1401 East Broad Street, Annex Building, 5th Floor Richmond, VA 23219

#### RE: Technical Proposal | I-81 Widening MM 136.6 to MM 141.8, Roanoke County and City of Salem, VA State Project No.: 0081-080-946, P101, R201, C501, B677, B678, B681, B682, B683, B684, B685, B686, B687, B688 | Federal Project No.: NHPP-0812(330) | Contract ID Number: C00116203DB108

Dear Mr. Stevenson,

Partnership will be fundamental to the success of the I-81 Widening MM 136.6 to MM 141.8 Design-Build (D-B) Project (the I-81 Project, or the Project). This complex endeavor demands a D-B team that seamlessly collaborates internally and with the Virginia Department of Transportation (VDOT). The **Branch-Orders Joint Venture** (Branch-Orders), as the Offeror, has thoughtfully assembled a Team that includes firms with extensive experience working on similar projects in the I-81 corridor. Branch-Orders will work with Lead Designer, **Whitman, Requardt** & Associates, LLP (WRA), to furnish a product that meets or exceeds design and construction expectations. The Branch-Orders Team (also called the Team) offers the following information as required by Section 4.1 of the Request for Proposals (RFP):

**4.1.1 Offeror's Official Information:** Branch-Orders, based at 442 Rutherford Ave, NE, Roanoke, VA 24016, is the Offeror and will be the overall authority on the project as well as the Lead Contractor.

**4.1.2 Declaration of Intent:** It is our team's intent to enter into a contract with VDOT for the I-81 Project in accordance with the terms of the RFP.

**4.1.3 120-Day Declaration:** The offer represented by the technical and price proposals will remain in full force and effect for 120 days after the price proposal is submitted.

**4.1.4 Point of Contact:** Donald E. Bryson, Jr., Pursuit Manager 442 Rutherford Avenue NE, Roanoke, VA 24016 Phone: 704.572.1684 | Fax: 540.982.4216 Email: donald.bryson@branchcivil.com **4.1.5 Principal Officer of the Offeror:** Jason Hoyle, Vice President 442 Rutherford Avenue NE, Roanoke, VA 24016 Phone: 540.982.1678 | Fax: 540.982.4216 Email: jason.hoyle@branchcivil.com

4.1.6 Final Completion Date: Our Team commits to a timely Final Completion Date of January 15, 2026.

4.1.7 Unique Milestone Dates: Our team does not propose unique milestone dates for this Project.

**4.1.8 Proposal Payment Agreement or Waiver of Proposal Payment:** An executed Proposal Payment Agreement is included in Appendix 9.3.1 of this document.

**4.1.9 Certification Regarding Debarment Forms:** Signed Primary and Lower Tier Debarment Forms are provided in Appendix 11.8.6 of this document.

**4.1.10 Disadvantaged Business Enterprise (DBE) Commitment:** Our team supports the DBE program and is committed to achieving or exceeding the 9% DBE participation goal for the entire value of the Contract.

Our Team acknowledges receipt of Addendum No. 1 dated December 16, 2020, Addendum No. 2 dated January 7, 2021, Addendum No. 3 dated January 27, 2021, and Addendum No. 4 dated February 12, 2021. We've included the signed Acknowledgment of RFP, Revision and/or Addenda Form (Attachment 3.7) in Appendix 3.7 of our Technical Proposal. We appreciate the opportunity to present our proposal to VDOT and are 100% committed to delivering a successful, quality Project on-time and on-budget.

Respectfully Submitted,

The Branch-Orders Joint Venture

Donald E. Bryson, Jr. Pursuit Manager | Branch Civil, Inc.

# **SECTION 4.2** Offeror's Qualifications



# **4.2 OFFEROR'S QUALIFICATIONS**

THE BRANCH-ORDERS TEAM WILL PARTNER WITH VDOT TO DELIVER CONSISTENT, QUALITY OPERATIONS. BASED ON OUR TEAM'S D-B LESSONS LEARNED AND EXPERIENCE IN THE I-81 CORRIDOR, WE HAVE INCORPORATED VALUE-ADDED PERSONNEL TO MAXIMIZE WORKERS' SAFETY AND THE TRAVELING PUBLIC AND MINIMIZE RISKS TO THE SCHEDULE AND BUDGET.

The Branch-Orders Team is comprised of leading roadway and bridge designers and design-build (D-B) contractors who understand the project's challenges and complexities, as well as VDOT's procedures and expectations. Our Team members have solved similar challenges on past projects and understand the importance of minimizing disruptions to local communities and the traveling public, with an emphasis on safety and the value of every dollar invested.

# **4.2.1 Confirmation Statemen**

Branch-Orders, as the Offeror, confirms that the information provided in our Statement of Qualifications (SOQ) dated July 8, 2020, remains true and accurate in accordance with the Request for Proposal (RFP) Section 4.2.1 requirements except for the following changes to our named Team members.

### SURVEYING/SUBSURFACE UTILITY ENGINEERING

According to the Department's letter dated December 3, 2020, we understand that H&B Surveying and Mapping, LLC has a potential conflict of interest with the I-81 Project. We have added **Precision Measurements, Inc.** (PMI) as a replacement



Team member to address this. PMI is a full-service land surveying firm with four offices in Virginia and others throughout the Southeast. With over 20 years of experience working for VDOT, PMI has performed surveying and SUE on seven VDOT D-B projects throughout the state.

PMI provides a full range of surveying services, including mapping, boundary surveys, verification surveys, platting, topographic surveys, 3-D scanning, route surveys, Global Positioning System (GPS) surveys, construction stakeout services, ALTA/ACSM land title surveys, and Geographic Information Systems (GIS), among others. PMI is certified by VDOT as a Disadvantaged Business Enterprise (DBE) and by the Commonwealth of Virginia Minority Business Enterprise as a Small Woman and Minority (SWaM) business.

# LANDSCAPE DESIGN

In recognition of the Department's addition of landscape design services in the RFP, we have added Land Planning



and Design Associates, Inc. (LPDA) to our Team. LPDA has a wide range of experience in landscape architecture and planning services for roadways, interchanges, park-and-ride lots, pedestrian and bicycle facilities, and transportation-related design and improvement projects.

LPDA has an organized understanding and expertise in resolving land use issues that may arise. LPDA plays a crucial role in the public participation process and examines the impacts of design and improvements. LPDA serves Virginia and the Mid-Atlantic region with offices in Charlottesville and Sterling, Virginia, and is a certified SWaM and MICRO business.

A copy of VDOT's approval of these changes, received on **February 16, 2021**, is included in this submittal's Appendices.

# 4.2.2 Organizational Chart

Under the leadership of Design-Build Project Manager (DBPM), M. Jeff Humphreys, Jr., DBIA, our Team is structured to effectively manage and deliver the design and construction of the I-81 Project. Our fusion of local, regional, and national expertise enables identifying and addressing challenges early, increasing delivery certainty. We provide a dynamic, expert group of design and construction professionals with local, recent, and relevant D-B experience in the I-81 corridor.

The functional relationships between positions and roles described in our SOQ narrative remain unchanged, true, and accurate. Our Organizational Chart, provided in **EXHIBIT 4.2-1** on page 3, indicates personnel changes in yellow highlights.



# **SECTION 4.2 | OFFEROR'S QUALIFICATIONS**

Technical Proposal, Volume I | I-81 Widening MM 136.6 to MM 141.8 Design-Build





	Third Party Stakeholders
lic Relations Manager wen Peery, PE <sup>RK&amp;K</sup>	Roanoke County City of Salem Roanoke County Parks Utility Companies Roanoke City First Responders/State Police Local Hospitals American Trucking Associations Roanoke Chamber of Commerce Local Businesses
Safety Manager	
Danny Minnix BRANCH	
	Quality Control
	Austin Williams NAL
Deputy Construction	Lead OC Roadway
Maliaga Source BRANCH	NXL Staff
vienssa Sowers	Lead OC Bridges
• • • • • • • •	NXL Staff
Dject Controls Manager	QC Inspections
Wilchael Vass	NXL Staff
on. Compliance Manager	QC Testing/Lab
Tyler Racey BRANCH	ECS Staff
E Compliance Manager Ericka Sullivan <sup>BRANCH</sup>	
contractor Work Force	
C Qualified Subcontractors, ling local firms, DBEs, and SWAM firms	LEGEND Combined Resources Design
MEMBERS	Construction
e. tion Company rdt & Associates, LLP er & Kahl, LLP	Quality Assurance (QA) Quality Control (QC)
rements, Inc. ( <i>DBE/SWaM</i> )	Volue Added Staff
of Century Engineering	value-Added Staff     Direct Lines of Reporting
	stranger and stranger and
ic, LLC	Lines of Communication
c, LLC onsulting, LLC ( <i>SWaM</i> ) e Services, Inc.	Lines of Communication Org Chart Changes Since

# SECTION 4.3 Design Concept

----



# **4.3 DESIGN CONCEPT**

**SIMPLER IS SAFER.** OUR CONCEPTUAL DESIGN PROVIDES EFFICIENCY AND SIGNIFICANTLY REDUCES TRAFFIC SHIFTS IN THE WORK ZONE. THIS ALLOWS FOR SAFE CONSTRUCTION OPERATIONS AND ENSURES THE NEEDS OF VDOT, STAKEHOLDERS, RESIDENTS, AND BUSINESSES ARE NOT OVERLOOKED.

The Branch-Orders Team has highly effective communication protocols that ensure efficient development, approval, and ultimate implementation of a high-quality design. We have recent and relevant experience in the I-81 corridor that will allow rapid deployment and Project start-up. Our Team has delivered similarly challenging projects for VDOT within budget and schedule and will successfully deliver the final completion of the I-81 Project on **January 15, 2026**.

Our Conceptual Design for the I-81 Project, located behind "TAB 1" in Volume II, builds upon our overall D-B and I-81 corridor experience to deliver VDOT and other stakeholders' best value. Key aspects and enhancements are highlighted below in **EXHIBIT 4.3-1** and described throughout this section.

# 4.3.1.1 Conceptual Roadway Plans

Our Team has reviewed the preliminary plans and details presented in the RFP documents. We have developed a Conceptual Design that will enhance safety, operations, schedule, construction, public acceptance, cost savings, and long-term sustainability benefits for end-users. Our Conceptual Design meets or exceeds the design requirements. Also, all criteria of the RFP and Addenda are met or exceeded. Our Conceptual and Final Designs will address all of the RFP objectives, including a more efficient design,

**EXHIBIT 4.3-1** Branch-Orders Team Project Features and Enhancements

ENHANCEMENT	BENEFITS	SAFETY	OPERATIONS	SCHEDULE	CONSTRUCTABILITY	PUBLIC ACCEPTANCE	LONG-TERM LOW MAINT	COST SAVINGS
Modifications to	• Significantly reduces the grade change on I-81 to simplify maintenance of traffic (MOT).	0	0	0	0	0		0
the I-81 Baselines over Route 112 to	• Significantly reduces construction time and driver exposure to construction operations.	0	0	0	0	0		0
Bridges	• Eliminates the RFP Design for 12' tangent lane shift (STA 543+50 to STA 554+50) by offsetting the PGL within a fully superelevated section.	0	0		0	0		0
I-81 Baseline Modifications North of the Route 112 Bridges	<ul><li>Eliminates the 1,500' Median Shoulder Design Exception.</li><li>Improves the consistency of lane configurations during construction.</li></ul>	00	000	0	0	00		0
Loop Ramp D Safety Improvements	<ul> <li>Modifies the departure curve radius from 250' to 320'.</li> <li>Modifies the grading between SB I-81, Loop Ramp D, and Ramp D to be 6:1 or flatter, exceeding the RFP 4:1 requirement.</li> </ul>	00	00			00	00	
	• Reduces bridge and construction phases, thus reducing construction time, improving worker safety and increasing driver consistency.	0	0	0	0	0		0
Modifications to the Route 112, Route 635, and Route 619 Bridge	<ul> <li>Eliminates long temporary alignments and lane shifts during construction.</li> <li>Streamlines traffic operations during construction, which minimizes opportunity for traffic disruptions and driver exposure to construction and congestion.</li> </ul>	0	0	0	0	0		0
Driuges	• Minimizes impacts/widening to the outside shoulder and preserves existing trees.	0		0	0	0	0	0
	• Eliminates the need for retaining wall or box culvert extension at STA 618+00.	0		0	0		0	0





#### **EXHIBIT 4.3-1** | Branch-Orders Team Project Features and Enhancements (*continued*) ONG-TERM LOW MAINT **PUBLIC ACCEPTANCE CONSTRUCTABILITY** COST SAVINGS **OPERATIONS** SCHEDULE SAFETY **ENHANCEMENT** BENEFITS The I-81 SB North • Reduces construction time. 0 0 0 0 0 0 of Route 705 (Red • Reduces driver exposure to construction and delays. 0 0 0 0 0 0 Lane) Baseline is Reduces footprint by keeping the outside edge of pavement on or within 0 0 0 0 Modified to Shift the existing outside edge of pavement. **Proposed Lanes** 0 0 0 toward the Median • Maintains a 12' outside shoulder below the existing Route 705 Bridge. The I-81 NB **Baseline** at the Allows traffic to flow parallel to the existing bridge. 0 0 0 **Bridge over Route** 0 0 0 0 0 • Avoids conflicts during construction. 630 (Kessler Mill 0 0 Avoids unexpected lane arrangements. 0 0 Road) is Modified • Avoids the need to rework pavement in the median. 0 0 0 0 0 0 0 to Match the I-81 **As-built Plans** Cut Slope 0 0 0 0 Minimizes the Project footprint. 0 **Optimizations** 0 Minimizes impacts to existing stable slopes. 0 0 0 0 to Minimize Cut Õ Õ 0 0 0 **Slopes (Where No** Minimizes impacts to existing rock slopes and associated traffic impacts 0 0 Widening is Taking due to rock blasting. Place, the Existing • Minimizes construction impacts to traffic for hauling materials. 0 0 0 0 0 0 0 Side Slopes will be Minimizes the potential for ROW impacts. 0 0 0 0 0 0 Maintained) **Retaining Wall** 0 0 0 0 0 Minimizes the Project footprint. Panels As Noise 0 0 0 0 Minimizes the potential for ROW impacts. 0 Walls **Minimizations to** 0 0 • Minimizes the Project footprint. 0 0 0 **ROW Impacts** 0 Minimizes VDOT costs for additional ROW acquisitions. 0 0 0 throughout the 0 0 0 0 · Reduces public concerns about ROW takes. Project 0 0 • Exceeds the minimum clear roadway width at all bridges during 0 0 0 **Modifications to** construction. **Structure Phasing** Eliminates a phase of construction at all bridges. 0 0 0 0 0 0 0 0 **MOT Optimizations** • Increases the Phase 3 bridge construction clear roadway width. 0 0 • Minimizes the Project footprint. 0 0 0 0 0 **Modifications to** 0 0 0 0 0 Minimizes the potential for ROW impacts. 0 **Retaining Wall** 0 0 · Minimizes impacts to wetlands. 0 0 0 Locations in Fill 0 0 0 0 0 • Reduces earthwork, which minimizes construction/hauling traffic. 0 0 Sections 0 0 0 0 0 • Reduces the height of multiple retaining walls.

improved constructability, and an approach that limits risks to the Department, Project, public, and stakeholders. Final plans will be prepared using MicroStation and OpenRoads Designer. Electronic submissions of plans, reports, and calculations will follow VDOT's process, including an associated quality assurance and quality control (QA/QC) documentation, including VDOT's LD-436 QC checklist. Our Team will provide plans in .dgn and .pdf formats and as paper copies at the milestones outlined in the RFP. Each submission will undergo an internal quality review process before submission. Upon final completion, we will provide As-Built plans documenting all design changes incorporated during construction.





#### **EXHIBIT 4.3-2** | Geometric Features

LOCATION	FUNCTIONAL CLASSIFICATION/ GEOMETRIC DESIGN STANDARD	DESIGN POSTED SPEED (MPH)	NUMBER/ WIDTH OF LANE(S)	
I-81	GS-INT	65 MPH	Three (per direction)/12'	
Route 112 Ramp A Route 112 Ramp B Route 311 Ramp A Route 311 Ramp B	GS-R	45 MPH	One/16'	
Route 112 Ramp D	GS-R	40 MPH	One/16'	
Route 311 Ramp D	GS-R	35 MPH	One/18'	
Route 419 Ramp B Route 419 Ramp D	GS-R	35 MPH	One/16'	
Route 112 Loop D	GS-R	30 MPH	One/16'	
Route 311 Loop D Route 419 Loop B Route 419 Loop D	GS-R	25 MPH	One/18'	
Route 112 Loop D Spur	GS-R	20 MPH	One/18'	
Route 112 (Wildwood Road)	GS-5	35 MPH	N/A	
Route 635 (Goodwin Avenue)	GS-7	35 MPH (Roanoke County) 30 MPH (City of Salem)	One (per direction)/11'	
Route 619 (Wildwood Road)	GS-7	35 MPH (Roanoke County) 30 MPH (City of Salem)	N/A	

## (A) GENERAL GEOMETRY, INCLUDING HORIZONTAL CURVE DATA AND ASSOCIATED DESIGN SPEEDS

Our Conceptual Design, provided behind "TAB 1-A" in Volume II, provides a six-lane facility with a median barrier throughout most of the project limits, providing three mainline lanes in each direction. This design meets or exceeds RFP requirements, the Design Criteria Table Attachment 2.2, and the RFP Design intent. Our Conceptual Design includes information detailing horizontal curve data, the number and width of lanes and shoulders, and improved cross slope or rollover differential in accordance with the RFP.

**EXHIBIT 4.3-2** above summarizes pertinent geometric features for the major roadway components and matches the Design Criteria provided in the RFP.

# **(B) HORIZONTAL ALIGNMENTS**

The proposed horizontal alignment provides three thru-lanes in each direction. However, we provided optimizations to accelerate construction and reduce construction-related delays and potential impacts to the traveling public. Our Conceptual Design achieves this by performing most of the northbound (NB) widening toward the Project's median, while providing most southbound (SB) widening to the outside of the existing travel way. This alignment will maintain, at a minimum, the required overall clear roadway and shoulder width of 34' throughout construction. It also allows all median construction, median drainage, and widened roadways and bridges to take place simultaneously for both the NB and SB directions. Doing so provides the opportunity to combine ingress and egress points in many locations, thereby **minimizing traffic impacts**. Our Team has modified the RFP alignment in many places to **reduce impacts**, **improve constructability and safety during construction, and maximize existing pavement reuse**.

Our Team modified the RFP baselines from 1,000' south to 1,200' north of the Route 112 Bridge. As shown in EXHIBIT 4.3-3 on the next page, horizontal curves allow the bridges over Route 112 to be superelevated, which:

- Allows the design to achieve the minimum clearance of the bridges over Route 112 more efficiently than the RFP Design. This reduces the height of mainline grade change in the RFP Design up to 2.75'.
- Accelerates construction by reducing the amount of build-up by up to 2.75'. This reduces driver exposure to construction operations and improves safety.
- Allows the construction of bridges over Route 112 to be performed in two phases instead of the three shown in the RFP Design, accelerating construction and improving safety.

### **EXHIBIT 4.3-3** | Exit 137 - Route 112 Design Enhancements





# 





**EXHIBIT 4.3-4** | I-81 SB over Route 635 Alignment Revision



- Eliminates the RFP Design's 12' lane shift (STA 543+50 to STA 554+50) by offsetting the PGL within a fully superelevated section. This elimination also accelerates construction and improves safety.
- Eliminates the need for the planned Design Exception for reduced median shoulders between STA 137+00 and STA 152+00, improving long-term emergency operations and safety.

Our Team modified the RFP baseline at the Route 635 and Route 619 bridges by shifting the baseline toward the median. As demonstrated above in EXHIBIT 4.3-4, these modifications to the alignment:

- Shifts more construction toward the median of the roadway.
- Allows for the roadway and the Route 635 and Route 619 bridges to be constructed in two primary phases instead of the three in the RFP Design.
- Reduces tree clearing by 101,000 SF.
- Eliminates the need for a retaining wall or box culvert extension at STA 618+00.
- Accelerates construction, reduces driver exposure to construction operations, and improves safety.

Our Team modified the RFP Design's SB baseline north of Route 705 by shifting the baseline and proposed lanes toward the median. This modification to the alignment:

- Provides a more consistent alignment and travel way, which is safer concerning driver expectancy and easier to construct.
- Accelerates construction, reduces driver exposure to construction operations, and improves safety.
- Eliminates the sliver cut, which reduces the overall Project footprint.
- Reduces the length and height of the retaining wall at STA 661+00.

Our Team modified the I-81 NB Baseline at the bridge over Route 630 (Kessler Mill Road) to match the I-81 As-Built plans. This modification to the alignment:

- Allows the baseline to be parallel to the bridge parapets over Route 630.
- Roadway approaches to the bridge will better line up with the existing bridge.



#### Our design of the Route 112 Loop D is in accordance with Attachment 2.2, the Design Criteria Chart, of

the RFP. This provides safety improvements at the intersection of Route 112 and Loop D intersection, and includes the following enhancements:

- Modifies the departure curve radius from 250' to 320'.
- A minimum 70' storage length for the left turn from Route 112 Loop D to Route 112.
- Re-striping to match the Pavement Marking Concept provided in the RFP Information Package. This action offers a free-flow condition for right-turning traffic from Route 112 Loop Ramp D to Route 112.
- Accommodation of WB-67s at all intersection turning movements.
- Providing grading out to the "clearing line" shown on the RFP Design along the Route 112 Loop D Exit Ramp.
- The area between the SB I-81 mainline, Route 112 Loop D Exit Ramp, and Route 112 Ramp D SB Entrance Ramp is re-graded to 6:1 or flatter. This action exceeds the 4:1 minimum requirement to enhance safety for vehicles departing the roadway.

# (C) MAXIMUM GRADE FOR ALL SEGMENTS AND CONNECTORS

As demonstrated in **EXHIBIT 4.3-5**, our Conceptual Design meets the RFP requirements as defined in Part 2 of the RFP and the Design Criteria Table Attachment 2.2. Additionally, our vertical alignments:

- Reduce the vertical grade change on I-81 at Route 112 by up to 2.75', which will accelerate construction and improve safety.
- Correct the RFP Design's Route 635 profile to provide vertical clearance for future I-81 widening.

### (D) TYPICAL SECTIONS OF ROADWAY SEGMENTS (RAMPS, RETAINING WALLS, AND BRIDGE STRUCTURES)

### Roadway Sections

Our Team's typical sections, provided in our Conceptual Design behind "TAB 1-A" of Volume II, graphically depict the proposed roadway design intent and fully comply with Part 2 of the RFP. Our Conceptual Design attempts to utilize the existing roadway as much as possible and practical. Much of our Conceptual Design has a median width of less than 15'. We will provide a median treatment that eliminates mowing and regular maintenance whenever the median is less than 15' (shoulder-to-shoulder). All median areas greater than 15' will be grass.

Our Conceptual Design will maintain the existing roadway cross slope where slope correction is not

### **EXHIBIT 4.3-5** | Maximum Grade Comparison

LOCATION	BRANCH- ORDERS MAXIMUM GRADE	ALLOWABLE MAXIMUM GRADE
I-81	3.5%	4%
Route 112 Ramp A	4.7%	3-5%
Route 112 Ramp B	3.6%	3-5%
Route 112 Ramp D	4.0%	4-6%
Route 112 Loop D	1.5%	5-7%
Route 112 Loop D Spur	3.0%	6-8%
Route 112 (Wildwood Rd.)	N/A	N/A
Route 311 Ramp A	3.6%	3-5%
Route 311 Ramp B	1.3%	3-5%
Route 311 Ramp D	2.9%	4-6%
Route 311 Loop D	3.7%	5-7%
Route 419 Ramp B	2.3%	4-6%
Route 419 Ramp D	3.7%	4-6%
Route 419 Loop B	2.8%	5-7%
Route 419 Loop D	3.2%	5-7%
Route 635 (Goodwin Ave.)	7.0%	10%
Route 619 (Wildwood Rd.)	N/A	N/A

needed. Our Team will apply VDOT standards in locations where:

- Existing cross slopes in areas of normal crown that are less than 1%.
- An existing or proposed rollover break between travel lanes exceeds 6%.
- The average superelevation within a horizontal curve is below VDOT's standard by more than 1%.
- All new full-width pavement sections.
- Vertical alignment increases of more than 3" as measured in accordance with the RFP.
- Horizontal alignment shifts of more than 12' from the existing.

Our Conceptual Design utilizes guardrail or concrete barrier where required by Appendix J of the *VDOT Road Design Manual* or AASHTO standards. The Conceptual Design also includes pier protection, where required. Roadside grading will be in accordance with VDOT Standards CS-4 as required in Part 2 of the RFP and the Design Criteria Table Attachment 2.2 and includes clearing of clear zones not protected by a barrier. In locations where no widening to the outside is occurring, our Team





will utilize existing side slopes. The Conceptual Design includes retaining walls outside of the clear zone. These are generally in the same locations as the RFP Design, with the following notable exceptions, where wall heights are reduced by up to 6':

- STA 660+67.20 to STA 664+43.55
- STA 669+01.72 to STA 669+94.90
- STA 713+85.01 to STA 714+60.62

Our Team will protect noise barrier locations within the clear zone with a constant slope barrier per the RFP. Also, our Conceptual Design utilizes retaining panels to minimize grading impacts and proposed ROW. **These activities are a direct benefit to the environment, VDOT, and the Public.** We developed typical sections to reduce impacts to existing trees and plants to minimize construction runoff and reduce stormwater management (SWM) requirements.

Our Team will develop a Landscape Plan to denote proposed areas that will be planted and reforested. The plan will meet all requirements of Part 2 of the RFP (Section 2.8) and will be developed by a landscape architect licensed in the Commonwealth of Virginia. The most common typical roadway section our Team will utilize on this Project is provided above in **EXHIBIT 4.3-6**.

#### Bridge Structures

The typical sections of bridges, located in our Conceptual Design behind "**TAB 1-B**" of Volume II, conform to *VDOT Structure and Bridge Manual, Volume V, Part* 2, *Chapter 6*, and Part 2 of the RFP. Bridges will be designed in close coordination with the roadway plans and MOT requirements specific to each location.

# (E) CONCEPTUAL HYDRAULIC AND STORMWATER MANAGEMENT DESIGN

Our SWM approach emphasizes feasibility and constructability to provide a solution that satisfies VDOT and Virginia Department of Environmental Quality's (DEQ) requirements. We understand how to navigate the multiple layers of the DEQ's Virginia Stormwater Management Program (VSMP) regulations while engineering a proposed solution that minimizes costs and long-term maintenance requirements. Critical for the I-81 Project is the ability to understand and meet the Project's SWM needs within the ROW constraints while satisfying the design guidance of the RFP. We optimized and streamlined the SWM design while following VSMP regulations and guidance and meeting VDOT's Design Criteria. The following narrative provides examples of our approach to optimizing the RFP Design.

#### Consolidation of Drainage Outfalls

Our Team's initial analysis of the RFP showed that some of the existing outfalls along I-81 have insufficient space for a stormwater management facility and

Our Team has significant experience with interstate designs, including the I-64 Widening MM 200-205 in Richmond District (WRA), I-81 Exit 14 Interchange Improvements in the Bristol District (RK&K), I-64 and Route 623 Interchange Improvements in Richmond District (RK&K), and Route 3 and I-95 Interchange in Fredericksburg District (WRA). This experience provides our Team the knowledge and understanding needed to meet the stormwater challenges on this Project.



**EXHIBIT 4.3-7** | Decreased BMP Footprint and Reduced ROW at Stormwater Basin #4



are inadequate to convey the post-construction project peak discharges. We will mitigate this condition by diverting runoff away from the outfall through the storm drain to areas where the runoff can be sufficiently detained and treated by a BMP facility. **This approach protects VDOT from potential liability from downstream flooding impacts while also providing the necessary on-site project water quality treatment**. Another advantage of outfall consolidation is that it can reduce the number of pipes that need to be jackand-bored under I-81, minimizing construction risk, cost, and long-term maintenance for VDOT. Example locations where our Team proposes this approach is:

- Abandoning the existing I-81 SB culvert under SB STA 516+75 and conveying the runoff with storm drain to the proposed BMP left of SB STA 529+00.
- Diverting runoff from the inadequate outfall at STA 172+50 NB to the proposed BMP left of SB STA 575+00.

#### Strategic BMP Type Selection and Grading

Because much of the I-81 corridor has steep topography, a BMP with a small footprint can require substantial grading and ROW/easement acquisition to chase slopes in some areas. Our Team has accounted for this by carefully selecting BMP types, locations, and grading footprints to minimize the ROW needed for this Project, **ultimately reducing long-term maintenance costs**. Examples include:

- Maximizing nutrient credit purchase to satisfy up to 25% of the required project water quality treatment.
- Proposing BMPs within existing VDOT ROW areas, such as within the Route 112/Wildwood Road loop interchange.
- As shown above in **EXHIBIT 4.3-7**, refining the grading of the proposed BMP facility left of I-81 SB STA 575+00 significantly reduces the area of proposed ROW shown in the RFP Design.
- Eliminating over 1,000 LF of the linear swale BMP depicted in the RFP Design from I-81 SB STA 582+00 to 593+50, reducing grading and ROW impacts.

#### Providing BMP Access from Local Roads for Safety

We understand that providing access to BMPs from local roadways during and after construction will be safer. For this reason, we have strategically located and graded the following proposed BMP facilities to facilitate access from local roads:

- The proposed BMP facility left of I-81 SB STA 529+00 will be accessed from the Wildwood Road eastbound lane.
- The proposed BMP facility right of I-81 NB STA 149+00 will be accessed from Burma Road.







- The proposed BMP facility right of I-81 NB STA 163+00 will be accessed from Starview Drive.
- The proposed BMP facility left of I-81 SB STA 600+00 will be accessed from Route 635/ Goodwin Avenue.

#### Robust E&SC and Temporary Drainage Design

Our Team understands that DÉQ has made recent inquiries on a statewide basis about ensuring the protection of outfalls with sediment traps and basins per DEQ Minimum Standard 6 (MS-6). Our approach to a safe work zone and protecting downstream outfalls from sediment during construction includes:

- Utilizing all proposed BMP facilities as sediment traps and basins.
- Providing sediment traps within the I-81 median at key locations where the drainage area does not exceed 3 acres. In general, this equates to one sediment trap for every 2,000 LF of roadway on the I-81 Project.
- Developing proposed median storm drain inlet spacing so that runoff spread is contained within the shoulders, including during phased MOT when the shoulder areas are temporarily reduced in width.

# (F) PROPOSED RIGHT OF WAY LIMITS

Understanding how ROW can affect the Project's schedule and how to mitigate its effects was a priority in the development of our Conceptual Design. The result is a design that reduces the Project footprint, minimizes the amount of acquisition, and reduces the number of parcels impacted.

**EXHIBIT 4.3-8** above presents a representative example of how we provide ROW reductions. Additionally, **EXHIBIT 4.3-9** below demonstrates our overall reduction in ROW on this Project. We will also prioritize the ROW acquisitions for this Project to align with our schedule.

<b>EXHIBIT 4.3-9</b>   Reductions in ROW versus R	FP
---	----

	# OF PARCELS	ROW (SF)	EASEMENTS (SF)
RFP Design	56	474,425	40,397
Team Design	36	389,583	31,137
Proposed Reductions	20	84,842	9,260



UTILITY DESCRIPTION	APPROXIMATE LOCATION	POTENTIAL IMPACT	MITIGATION STRATEGIES
Citizen's Telephone Fiber Optic Line	Throughout the entire Project.	Multiple conflicts with roadway widening and bridge construction.	Relocate lines to outside of the shoulders of I-81.
VDOT	Throughout the entire Project.	Multiple conflicts with roadway widening and bridge construction.	Relocate lines to outside of the shoulders of I-81.
Comcast Cable Television	Along Route 112 at I-81 bridge.	Conflict with proposed bridge substructure.	Relocate cable to the edge of Route 112.
Verizon Phone/Cable	Along Route 112 at I-81 bridge.	Conflict with proposed bridge substructure.	Relocate cable to the edge of Route 112.
Roanoke Gas 4" Line	Along Route 112 south of I-81.	Possible conflict with replacement storm pipes.	Raise or lower existing line to avoid conflicts.
City of Salem 12" Water	Along Route 112 south of I-81.	Possible conflict with replacement storm pipes.	Raise or lower existing line to avoid conflicts.
WVWS 10" Sewer	Along Route 112 south of I-81.	Possible conflict with replacement storm pipes.	Raise or lower existing line to avoid conflicts.
Citizen's Telephone Fiber Optic Line	Along Route 112 at I-81 NB on-ramp.	Possible conflict with replacement storm pipes.	Raise or lower existing line to avoid conflicts.
Verizon Fiber Optic Ducts	Crossing I-81 near STA 559+50.	Possible conflict with storm pipe.	Raise or lower existing line to avoid conflicts.
City of Salem 6" Water	Along Route 635 south of I-81.	Possible conflict with replacement storm pipes.	Raise or lower existing line to avoid conflicts.
City of Salem 8" Water	Crossing I-81 at STA 642+35.	Possible conflict with storm pipe.	Raise or lower existing line to avoid conflicts.
City of Salem 8" Water	Crossing I-81 at STA 643+75.	Possible conflict with storm pipe.	Raise or lower existing line to avoid conflicts.
City of Salem Electric	Along Route 635 at Basin 7	Conflict with paved access area to basin.	Relocate pole out of paved area.

#### **EXHIBIT 4.3-10** | Utility Conflicts and Potential Mitigation Strategies

# (G) PROPOSED UTILITY IMPACTS

There are multiple utility impacts between the proposed construction and the existing utility facilities within the Project area. The most significant of these are existing fiber optic lines from Citizen's Telephone Cooperative and VDOT within the I-81 median throughout the Project's length. There are also conflicts between the proposed bridge abutments and existing communications lines at the Route 112 bridge. Additional potential conflicts also exist at several locations within the Project between proposed storm drain pipes and water, sewer, gas, electric, and communications lines. Our Team assessed potential impacts and has a strategy to address each, as summarized above in **EXHIBIT 4.3-10**. Further discussion is provided in Section 4.4.2, and a detailed Utility Matrix is available behind "TAB 2" in Volume II.

### (H) NOISE BARRIERS

Per the RFP, our Team will conduct a Final Design Noise Analysis during the detailed design phase, based on the Department's Preliminary Noise Analysis. If the results of the Final Design Noise Analysis dictate that noise abatement is required, we will provide permanent noise mitigation in compliance with the policies, guidance, and manuals specified in the RFP. The design of any noise barriers will be in accordance with VDOT policies. Our Conceptual Design utilizes small retaining panels at select noise barrier locations to eliminate sliver fill sections. This will accelerate the construction of the Project, minimize tree clearing, reduce grading and SWM requirements associated with the disturbed area, and reduce ROW impacts.

### (I) OTHER KEY PROJECT FEATURES

#### ■ ITS/CCTV/DMS/Communication Infrastructure

Major intelligent transportation system (ITS) components will consist of closed-circuit television (CCTV) cameras, equipment cabinets, fiber optic cable system, and network hardware components. Four CCTV sites currently exist within the Project limits. We also propose a new CCTV site at MM 139, on the north side of the Red Lane overpass. We will also provide three

VDOT

portable CCTVs during construction to monitor traffic along I-81 or other roadways within the regional network following our MOT Plan's approval. Our Team will coordinate this with the VDOT Southwest Regional Transportation Operations Center (TOC) Manager. The fiber optic cable system will include a new 96-count fiber optic backbone along one side of I-81 throughout the I-81 Project limits. Additionally, our Team has included 24-count fiber optic drop cables connecting all existing and proposed ITS devices to the backbone, as defined in the RFP.

Our Team will install the fiber optic cable system in an underground conduit and junction box system, separate from any conduits and junction boxes containing electrical power. The fiber optic cable system will replace existing VDOT and shared resource fiber optic cables impacted by the I-81 Project's construction and provide critical connections to VDOT's TOC and existing fiber optic lines north and south of the Project limits.

We will provide managed field ethernet switches. Our Team will reconfigure existing switches to provide communications through the proposed fiber optic cable system and re-establish communications outside of the project limits. Our Team will coordinate all network hardware configuration requirements with VDOT's networking staff to ensure seamless operation. The inspection, integration, and testing of ITS components will follow a three-tiered sequential process consisting of stand-alone, system operation, and acceptance testing approved by VDOT before starting; this activity will be witnessed by VDOT and the Quality Assurance Manager (QAM) per the RFP requirements.

The ITS will be designed and constructed following *VDOT's Guidelines and Information Instructions*, 2020 Road and Bridge Specifications, and 2016 Road and Bridge Standards to ensure a system that meets or exceeds the RFP requirements and is maintainable by VDOT. The construction of the proposed ITS components, including fiber optic cable system, will be sequenced with the roadway and bridge construction to minimize disruption to the existing network and system operation. Alternative methods of communications or power for ITS will be provided when disruptions exceed the durations permitted by VDOT.

#### Lighting

Our Team will provide roadway lighting at Exit 137, Exit 140, and Exit 141 interchanges per the RFP and Addenda. Following the RFP interchange lighting concepts, the interchange lighting will light all merge and diverge points from mainline I-81 and the entirety of all on- and off-ramps to tie-in with existing lighting at the ramp terminal intersections. Additionally, we will provide lighting along Route 112 (Exit 137) and Route 311 (Exit 140) to connect with existing lighting along the roadways. The light poles will be standard VDOT LP-1 or LP-2 poles with a maximum mounting height of 45' (our Team will use no high mast lighting) to minimize adverse impacts on nearby residences and areas outside the VDOT ROW.

Our Team will perform photometric and voltage drop calculations to maximize the lighting design's efficiency. We will coordinate with the local utility company to identify locations and construction service drops for the lighting system. The lighting will be designed and constructed following *IES RP-8* and the *VDOT Traffic Engineering Design Manual, Guidelines and Information Instructions, 2020 Road and Bridge Specifications, 2016 Road and Bridge Standards*, and the NEC. This will ensure a lighting system that meets or exceeds the RFP requirements and is maintainable by VDOT.

#### Landscaping

Our specialized subconsultant Land Planning and Design Associates (LPDA) is well versed in delivering efficient landscaping plans for VDOT, including many D-B projects. Per Section 2.8 of the RFP, all landscaping will follow the *Memo for Guidance for Planting in the Clear Zone and Landscaping for VDOT Projects, Guidelines for Context Sensitive Solutions FHWA 23 CFR 752, Landscaping and Roadside Development.* Planting Sizes and Replacement Plans will be in strict accordance with Section 2.8 of the RFP.

#### Signage

Our Team will upgrade, replace, or relocate impacted signage within the project limits in accordance with the RFP. As part of our initial submittal, an existing signing inventory and recommended actions for all existing signs will be provided. Overhead advance guide signage, meeting MUTCD and the Virginia Supplement to the MUTCD requirements for an "intermediate" interchange, will be provided at approximately onemile and half-mile increments. Our Team will also provide overhead exit direction signage.

Overhead sign structures will be located outside the clear zone or protected by guardrail throughout the project limits. Supplemental guide signs, Integrated Directional Signing Program (IDSP) signage and regulatory/warning signage will be ground-mounted on appropriate VDOT standard sign structures as per the RFP requirements. The proposed signing plan will provide motorists with clear guidance and notice of regulatory and advisory conditions within the project area. Our Team will design pavement markings to satisfy the VDOT PM standards. All permanent markings will be Type B,



Class VI to conform with VDOT requirements for limited access facilities. Plastic Inlaid Markers (PIMs) will be included in the Pavement Markings/Signage Plans per the appropriate VDOT standards.

# **4.3.1.2 Conceptual Structural Plans**

Our Team's approach to the I-81 Project provides a solution that meets or exceeds the RFP requirements. The use of reliable and durable materials will result in safe operations, reduced long-term maintenance, increased long-term asset performance, improved constructability, and public acceptance.

# **BRIDGE STRUCTURES**

### General Bridge Design

Our Team has extensive experience designing, detailing, and constructing bridges that meet or exceed VDOT's commitment to safe, high-quality, long-term, low-maintenance structures. We understand the importance of incorporating constructability into designs and providing a final design that exceeds VDOT's expectations and requirements.

We are confident that our Team's design and construction abilities will give the Department complete confidence in the I-81 Project's long-term asset performance. Our Team is committed to keeping this confidence throughout the Project through communication, design, detailing, and installation. All materials used on the Project will be in strict accordance with the Department's design guidelines, specifications, and approved materials lists. We will not use any details that increase inspection frequency or require additional inspection effort beyond routine bridge safety inspections.

Besides providing safe, long-term, low-maintenance structures, **our Team's overall approach and proposed bridge designs will minimize the public's impacts and allow construction in a safe and timely manner**. Our Team will design the proposed bridge structure replacements, modifications, and repairs per the AASHTO LRFD Bridge Design Specifications, 8th Edition, 2017, including Errata and VDOT Modifications, the RFP requirements, and Instructional and Informational Memoranda and the Manual of the Structure and Bridge Division. Bridges will be rated following IIM-S&B-86 and the RFP requirements.

### Constructability through Design

Our Team collaborated to extensively evaluate the constructability of the bridge replacements/modification/repairs from a Project corridor perspective. We reviewed As-Built drawings, survey data, and various alternative roadway alignments to determine this Project's most efficient construction schemes. Our Team has an established history of working together. Recent examples of how our partnership has successfully produced safe, high quality, longterm, low-maintenance structures for VDOT include the following projects:

- Route 636 PPTA | Augusta County, Virginia: Working with Branch as the Lead Contractor, WRA was the Lead Designer for the Route 636 Extension PPTA. This project included a semiintegral bridge over Norfolk Southern Railway tracks and is very similar to the bridges for this project.
- I-81 (NB and SB) over Route 808 (Halls Bottom Road) Bridge Replacement D-B | Washington County, Virginia: Working with Orders as the Lead Contractor, WRA was the Lead Designer for the bridge replacement project. This project replaced the existing structures in staged construction with new structural steel bridges supported by semiintegral abutments in MSE fill and is very similar to the bridges for this project.

We are confident that our proposed sequence **minimizes impacts on the traveling public and provides for each structure's shortest construction duration**. It is of notable mention that for improved motorist safety, our sequence of construction balances construction access with maintaining a minimum of 2' wide shoulders at the bridges at all times, exceeding the minimum RFP requirement of 1' shoulders.

An example of our consideration of constructability is the **use of semi-integral abutments to mitigate risks related to subsurface conditions at each site**. We used knowledge of the area and its geology to determine that the use of integral abutments for the bridge replacements would represent a risk not only to construction cost and schedule but the long-term performance of the abutments. A discussion for each structure for additional information follows in this section.

### General Superstructure Elements

Our Team evaluated the use of weathering steel girders and prestressed concrete beams and determined that weathering steel offers the best long-term, low-maintenance solutions for each bridge. The weathering steel plate girders also **allow for optimized superstructure depths to provide the required vertical clearances and minimize changes to profile grades throughout the Project corridor.** Smaller cranes with smaller footprints can be used to set the steel girders, which will reduce impacts to the schedule and the traveling





Our Team has an established history of bridge and structure design experience. This experience includes the I-81 Bridge Replacement over the Norfolk Southern Railway, Route 11, and South Fork Holston D-B, on which WRA was the Lead Designer and Orders the Lead Contractor. On this project, WRA worked with Orders to design a bridge that minimized impacts to the traveling public. The above photo shows steel erection during Phase II bridge construction of this D-B project.

public. The ASTM A709 Grade 50W girders will be designed, detailed, and fabricated following VDOT requirements for infinite fatigue life. To complement the durable and low maintenance bridge girders proposed for this project, the reinforced cast-in-place (CIP) concrete deck slabs will be constructed with Low Shrinkage Class A4 Modified concrete and will contain corrosion-resistant reinforcing (CRR) steel as required by VDOT and the technical requirements. Branch-Orders will build the deck to strict adherence to VDOT concrete cover requirements. The resulting deck provides a very durable long-term low maintenance deck with a high-quality ride surface for the traveling public.

#### Jointless Superstructure for Bridge Replacements

Our Team evaluated VDOT design criteria, including span length, skew, geotechnical requirements, and available geotechnical information. Findings indicate that semi-integral abutments in mechanically stabilized earth (MSE) fills are the best jointless bridge alternative for the new bridges over Route 112, Route 635, and Route 619. After considering subsurface conditions, we determined that achieving the pile arrangement required for fully integral abutments represents an appreciable risk concerning long-term performance, cost, and schedule. Proper long-term performance of fully integral abutments depends on the flexibility of the pile supports. Accordingly, Volume V Part 2, File No. 17.01 of the *VDOT Bridge Design Manual* requires that subsurface conditions allow piles to be driven to meet pile bent tolerances. Semi-integral abutments mitigate pile location and impediment risks associated with fully integral abutments. They also provide an excellent jointless solution following VDOT design criteria. In accordance with the VDOT Bridge Design Manual and relevant experience, we have determined that semi-integral abutments are the appropriate solution. Notably, the bridges will be designed and built to facilitate future jacking operations to replace the elastomeric bearing pads, if necessary, in the distant future.

#### Accommodations for Future Widening

Based on experience, our Team has learned that the proposed semi-integral abutments and multi-column piers for the structure replacements are well suited for future widening. The proposed substructure modification on structures carrying I-81 over Route 311 will also not preclude future widening. We evaluated the MSE fill walls proposed for all structure replacements; all walls will be designed and detailed to allow for



#### future widening of I-81 to accommodate a future four thru-lane configuration. Our Team has designed and constructed many bridge widening projects and understands how to accommodate future widening.

Our Team will facilitate future pile installation by installing pile sleeves/cans in the MSE fill below the waterproof geomembrane protecting the MSE fill. Pile sleeves/cans will be filled with approved granular fill material that can readily be removed in the future to install the proposed piles. The location of the sleeves/ cans will be clearly marked in construction/As-Built drawings. Additionally, the MSE panels will be designed to take the additional loads induced by future widening and live load surcharge. Contract drawings will clearly document this load allowance for future reference.

#### Aesthetics

Our Team will meet all aesthetic requirements of the RFP and the *VDOT Structure & Bridge Manual Part 2, Chapter 5, and Part 3.* For all bridge replacements, the width of proposed parapets accounts for up to 2" relief of drystack architectural treatment on the parapet's exterior faces when not adjacent to a sound barrier while maintaining proper section capacity and reinforcing steel cover for the barrier per VDOT standards. All MSE wall panels and abutment faces at Route 112, Route 635, and Route 619 will receive drystack treatment. Retaining walls and noise barriers will receive architectural treatment in accordance with the RFP.

We will match the current abutment architectural treatment at the abutments on Route 311; details are discussed in greater detail later in this section. All bridge architectural treatments, existing or proposed, will receive a concrete color surface coat. The color of the coating will be coordinated with and ultimately approved by the Department before application. Our Team finds that the proposed weathering steel superstructures combined with the concrete architectural treatments and good clean craftsmanship will visually appeal to the traveling public throughout the extent of the Project.

#### Commitment to Quality

Our Team is committed to producing a high-quality and cost-effective final product that will provide long-term, low-maintenance structures for the Department. This process began in the RFP phase through collaborative evaluation of many aspects of the structures, including small details that we know have been problematic for the Department and resulted in preventable maintenance issues. For example, we evaluated the approach slab/sleeper pad interaction with the median barrier and its impact on joint performance and joint maintenance. We will provide proper joint opening and installation to provide a long service life. An outline of the design aspects broken down by bridge crossing follows in this section.

#### I-81 OVER ROUTE 112

#### STRUCTURE LAYOUT

After careful consideration of site conditions, our Team determined replacing the existing four-span structures with two-span structures in two bridge construction phases to be the best option at this location. We evaluated a single-span bridge over the structure obstruction zone, but the required minimum bridge depth to meet VDOT criteria could not provide sufficient vertical clearance without appreciable modifications to I-81 or Route 112 profiles. As shown in **EXHIBIT 4.3-11** on page 18, the proposed bridge offers more than the required 16' - 6" minimum vertical clearance and allows for a minimum 16'- 6" vertical clearance for a future widening for a four thru-lane configuration with the same girder depth.

#### CONSTRUCTABILITY THROUGH DESIGN

We evaluated the As-Built drawings and survey data to verify that an entire construction phase can be eliminated compared to the RFP plans, which reduces construction duration and associated traffic impacts. A brief explanation of bridge construction activities is provided below. *Section 4.5.1* contains a more detailed writeup and additional information is located in "TAB 1-B" in Volume II.

- **Phase 2:** Temporarily shift traffic to the outside to safely maintain traffic in two 11' thru-lanes with 2' shoulders at only the bridge following the RFP.
  - » The exit ramp will be maintained.
  - » The interior portions of the existing NB and SB bridges can be removed. The remaining structure portions will safely support traffic with no reduction in the structure's current load capacity.
  - » This layout works well for deck removal limits relative to the existing beam lines and substructure removal limits relative to existing beams supporting traffic.
- **Phase 3:** Temporarily shift traffic to the newly constructed portion of the structure and maintain two 12' lanes with 2' shoulders at only the bridge following the RFP.
  - » The exit ramp will be maintained.
  - » This configuration provides an appreciable work area in the median of I-81 that achieves separation from the traveling public and facilitates efficient construction. Additionally, this configuration does not require the exit ramp to be maintained on a separate structure from the mainline traffic, as indicated in the RFP Design.

#### **SECTION 4.3 | DESIGN CONCEPT**

Technical Proposal, Volume I | I-81 Widening MM 136.6 to MM 141.8 Design-Build



# **I-81 OVER ROUTE 112**



The existing four-span structures will be replaced with two-span structures in two phases and remain outside of the Limit of SOZ. The structural steel superstructures will be founded on multi-column piers and semi-integral abutments. The multi-column pier footing is designed to minimize conflicts with existing pier footings; in no case will any portion of the existing footing be reused. The proposed opening will provide greater than a 16' - 6" minimum vertical clearance and allow for a 16' - 6" minimum vertical clearance in the future widening.

# **I-81 OVER ROUTE 619**



The existing three-span structures will be replaced with single-span structures in two phases and remain outside of the Limit of SOZ. The structural steel superstructures will be founded on semi-integral abutments. The proposed opening will provide greater than a 15' - 8" minimum vertical clearance and will allow for a 15' - 8" minimum vertical clearance in the future widening. This opening will primarily be achieved by lowering the grade of Route 635.



The existing three-span structures will be replaced with single-span structures in two phases and remain outside of the Limit of SOZ. The structural steel superstructures will be founded on semi-integral abutments. The proposed opening will provide greater than a 16' - 6" minimum vertical clearance and allow for a 16' - 6" minimum vertical clearance in the future widening.



The existing single-span bridges will be widened in two primary phases of construction. The structural steel superstructures will be widened with structural steel beams. Portions of the remaining deck will receive a latex overlay. The existing median of the abutments will be reconstructed to accommodate the bridge widening. The SB abutments will be widened to the outside to provide the required roadway width. The proposed opening will provide greater than a 16' - 6" minimum vertical clearance and will allow for a 16' - 6" minimum vertical clearance in the future widening.





# I-81 OVER ROUTE 635



#### SUBSTRUCTURE

Semi-integral abutments will be located behind MSE walls running parallel to Route 112. All portions of the structure will be located outside the structure obstruction zone (SOZ), as indicated in the RFP. MSE wall footers will be located below grade following RFP criteria to facilitate future improvements along Route 112. The proposed pier line will need to be placed where the existing pier is currently located.

Our Team has determined that all proposed multicolumn pier footings can be constructed between the existing pier footings in the earlier phase of construction and all but one footing location in the later phase of construction. We do not propose incorporating any portions of the existing foundations into the new structure. Where the proposed footing conflicts with the existing footing, our Team will remove the conflicting portion of the existing abandoned footing and cut existing piles off below the bottom of the proposed footing.

We propose the use of micropiles in this location to significantly reduce impacts to the traveling public along Route 112. Equipment required to install micropiles is more compact than the cranes and boom lengths necessary to drive piles in the median of Route 112. Using micropiles significantly improves constructability when working in the median of I-81. We will also install new piles adjacent to existing abandoned piles where proposed pier footings conflict with existing footings.

#### I-81 OVER ROUTE 635 AND I-81 OVER ROUTE 619

#### STRUCTURE LAYOUT

After reviewing the site conditions and planned roadway geometry, our Team selected replacing the existing three-span structures with jointless singlespan structures spanning the SOZ, as previously shown on page 18 in **EXHIBIT 4.3-11**. We will perform the bridge replacements in two phases of bridge construction versus the three-phase construction in the RFP Design.

At I-81 over Route 619, the steel plate girder depth and spacing is optimized to provide the most cost-effective structure for this location. At Route 635, the steel plate girders are optimized to meet the AASHTO and VDOT minimum span to depth ratio to improve the existing substandard vertical clearances. Improving the vertical clearance from 13' - 4" to 15' - 8" at I-81 over Route 635 is a stated goal in the RFP for this location. Notably, a Design Waver has been obtained to allow the 15' - 8" vertical clearance. Based on our review of the existing information, including the As-Built bridge plans and the proposed roadway geometry at this location, we have determined that Route 635 can be lowered in phased construction. Our approach to improving the vertical clearance includes:

- Adjust the existing Route 635 roadway to lower the vertical profile at the bridge location to include an allowance for future widening. Based on our review of the bridge As-Built drawings, excavating the existing roadway to this depth will not negatively impact the existing bridge. Our Team will construct temporary drainage and final roadway pavement, except for the finish course of asphalt. This effort will be accomplished during the allowable 60-day closure of Route 635, while school is not in session.
- Our Team will construct the bridge replacements utilizing two-phase construction. We will demolish the existing bridge piers during the bridge replacement to not damage the previously constructed Route 635 roadway. We will perform finish grading and construct surface course pavement and lane striping utilizing a flagger operation to maintain traffic.
- Jointless superstructures will be supported on semi-integral abutments located behind MSE walls running roughly parallel to the roadway alignment of the routes being crossed. All portions of the structure will be located outside of SOZs, as per the RFP. MSE wall footings will be embedded following the RFP criteria to facilitate future improvements along Route 635 and Route 619.

#### CONSTRUCTABILITY THROUGH DESIGN

As an improvement to the RFP Design, our Conceptual Design replaces the existing bridges in two phases of construction at each location versus the three phases shown in the RFP Design as follows; additional information is located behind "TAB 1-B" in Volume II. *Section 4.5.1* contains a more detailed writeup.

- **Phase 2:** Traffic will be temporarily shifted to the outside (away from the median) of the existing bridges and will be accommodated in two 11' lanes with 2' shoulders. The bridge's NB and SB interior portions will be demolished and reconstructed on their new alignments with sufficient width to provide two 12' lanes with 2' shoulders in each direction at Route 635 and two 11' lanes with 2' shoulders in each direction at Route 619.
- **Phase 3:** Traffic will be shifted to the newly constructed inside portion of the NB and SB bridges. When traffic is shifted, the remaining outside portion of the NB and SB bridges will be constructed, and the bridges will be fully opened to traffic.



This construction sequence works well for deck removal limits relative to the existing beam lines and substructure removal limits relative to existing beams in conjunction with our proposed roadway alignments. The existing structures can be partially demolished and still safely support traffic on the remaining portion of the existing structure with no reduction in its current load capacity.

This configuration also provides an appreciable work area in the median of I-81 that achieves a safe separation from the traveling public and facilitates efficient construction while reducing the number of construction phases and meeting all RFP requirements.

#### ROUTE 705 OVER I-81 AND ROUTE 419 OVER I-81

In accordance with the RFP, these structures will receive concrete substructure repairs, which shall include installing anodes in the repair areas according to the Specifications. All repairs will be in accordance with the RFP and *Volume V, Part II, Chapter 32*. Pier neatwork repairs will be waterproofed following the *VDOT Special Provision Copy Note for Waterproofing Coating* and the Specifications.

Existing piers will be protected by pier protection designed and installed following VDOT requirements. Additionally, our Team will repair the concrete slope protection at Route 419 by removing damaged portions, restoring fill, and restoring in-kind. All work will be performed in coordination with the roadway sequencing to reduce impacts to the traveling public.

#### I-81 OVER ROUTE 311

#### STRUCTURE LAYOUT

As previously shown in **EXHIBIT 4.3-11** on page 18, the existing structures will be widened to the inside and outside with structural steel beams supported on reconstructed or extended portions of the abutments. Proposed locations of widening and sequence of construction are in-keeping with RFP Design. The proposed widening can be achieved with steel beams that meet VDOT required minimum span to depth ratio based on all available information.

The steep grade of Route 311 would preclude maintaining 16' - 6" in a four thru-lane configuration on the SB structure if the same girder depth were used. If necessary, our Team will install all substructure modifications with sufficient depth to facilitate lowering Route 311 in the future. It is noted that a Design Waiver to reduce the girder depth could be used for the future four thru-lane configuration instead of lowering the Route 311 roadway profile.

### CONSTRUCTABILITY THROUGH DESIGN

Similar to RFP Design, our Team evaluated As-Built drawings and survey data to verify that traffic can temporarily be shifted to the outside to safely maintain traffic while providing 2' shoulders within the existing bridge footprint per the RFP. The interior parapet and deck overhangs of the NB and SB bridges will be removed, and the bridges will be widened to the interior on reconstructed abutments.

After construction in the median, traffic will temporarily be shifted to the inside to safely maintain traffic. The exterior parapet and deck overhangs of the NB and SB bridges will be removed, and the bridges will be widened to the exteriors. The SB bridge will be widened on new girders supported by abutment extensions. The NB structure will not require added girders for the widening to the outside. The bridge widening will be supported on existing bridge girders with an extended deck overhang meeting the design waiver for overhang length at this location. Additional information is located behind "TAB 1-B" of Volume II.

#### SUPERSTRUCTURE

Upon reviewing As-Built drawings, our Team noted that the existing bridge deck has precast stay-in-place panels. We considered these forms' presence when evaluating the RFP Design and constructability of the proposed widening.

To adequately address the stay-in-place panel's presence to remain in the finished condition, our Team will replace the existing overhang on the east face of the NB bridge as shown in the RFP Design; we will also replace the full deck in the exterior bay. This method will allow our Team to eliminate the risk of removing a portion of the deck over the precast panels that would have to remain. It will also enable the ability to fully develop the proposed parapet reinforcement in accordance with the standards. Our Conceptual Design sets the limits of removal and reconstruction to be located over the existing girders. In no case will partial portions of the precast panels remain in the structure.

In addition to widening the bridge, bridge joints will be eliminated to provide a jointless bridge deck. This structure has approach slabs supported by the back wall. Therefore, the approach slab will be replaced with a buried approach slab supported on a modified backwall to allow for the installation of deck slab extensions. The deck slab extensions will eliminate the joints following the VDOT Structure and Bridge Manual for existing portions of the bridge to remain in widened portions. The new approach slabs and the deck slab extensions will provide a long-term, low-maintenance jointless superstructure.



Proposed girders are designed to prevent any increase in loading to the existing exterior beam and ensure that the existing beam will provide a similar service life to an existing interior beam. Additionally, all widened portions of the structure will provide a relative overall structure stiffness that works well with the remaining portion of the bridge and ensure that the final superstructure shares applied loads well. Doing so will prevent such issues as unanticipated diaphragm or deck stress at the construction joints.

The deck will receive a mill and overlay over all portions of the existing deck that remain. Traffic will be shifted to minimize the number of construction joints in the overlay. All construction joints will be prepared and installed according to VDOT requirements to ensure the overlay provides the required service life. Our Team will replace the existing bearings. As the proposed elastomeric bearings are much shallower than the existing bearings, we will install seat extensions to raise the existing beam seats.

#### SUBSTRUCTURE

In accordance with the RFP, the existing abutment piles cannot be used to support widening to the median unless the pile condition and capacity are verified. The existing front piles are battered and cannot be re-struck from in front of the abutment. Re-striking will require the median's excavation to expose the heel and removal of a large portion of the heel to expose three piles. We will replace the entire median portion of the abutment and anticipate driving new piles as the entire area will already be exposed. Existing SB abutments will be extended to the west with a seat extension and u-back wingwall supported on H-piles. The existing wingwall will be removed to a minimum of 3' below grade. The small widening to the east of the NB bridge will be accommodated by modifying the top portion of the wingwall; a moment slab will be installed above the portion of the existing wingwall to remain.

#### APPROACH SETTLEMENT

As outlined in the RFP and as documented in the most recent *Bridge Safety Inspection Report*, the drainage apron in the outside shoulder of the SB I-81 just north of the abutment has settled 5 <sup>1</sup>/<sub>2</sub>" and is undermined by approximately 4' x 2' x 3' deep. This drainage apron and existing approach slabs will be replaced with new approach slabs. When the drainage apron is removed, the fill will be evaluated to determine that the settlement is isolated to the existing drainage apron area. Any unsuitable material will be removed, and our Team will install select approach backfill material according to VDOT requirements before installing the proposed approach slabs.

### Temporary Shoring

Phased construction will require the use of temporary walls to facilitate construction. Temporary support of the excavation will be required to enable excavation adjacent to the existing travel way. Additionally, the first phase of MSE wall will incorporate temporary wire walls parallel to I-81 to temporarily support the first phase of bridge construction until it is ultimately abandoned in the final MSE fill.

#### Retaining Walls

Retaining walls are required at various locations throughout the project to minimize ROW impacts. All retaining walls on the project will be in accordance with the RFP and *Volume V, Part 11, Chapter 10*. Retaining walls will have HR-1 railings where required by the RFP. Where relatively small amounts of soil retention are required at noise barrier, soil retaining panels will be utilized to eliminate the need to construct or maintain separate retaining walls. Our Team will analyze any existing earth retaining structures for any increase in soil loading.

#### Major Drainage Structures

Our Team will evaluate all major drainage structures for any increase in applied loading due to the roadway widening. We have determined that the existing box culvert structures at SB STA 549+10 (6' x 4' cell) and 560+20 (4' x 6' cell) will be modified. Culvert extensions will be designed and detailed in accordance with VDOT standards to match existing hydraulic openings. Construction joints between existing box culverts and proposed extensions will be detailed, executed, and waterproofed to provide a long-term, low-maintenance extension. Headwall and wingwall modifications will be made where culvert extensions can be eliminated. These will be designed and detailed in accordance with VDOT practices. Drainage structures will be repaired in accordance with the RFP.



# **SECTION 4.4** Project Approach

140,0

B

0



# **4.4 PROJECT APPROACH**

WE OFFER A TEAM CENTERED AROUND PARTNERSHIP, AND ARE READY TO ACTIVELY ENGAGE WITH VDOT TO DELIVER THIS D-B PROJECT. SUCCESS REQUIRES TRUST AND INTEGRATION BETWEEN AN EXPERIENCED TEAM, VDOT, AND MULTIPLE STAKEHOLDERS. WE WILL MAKE COMMUNICATION A PRIORITY AND SUPPLY THE RIGHT TECHNICAL RESOURCES AT THE RIGHT TIME.

The Branch-Orders Team is committed to being a true partner, knows how to manage complex projects, and can manage risk through best practices and lessons learned from similar large-scale major roadway and bridge improvement projects. Members of our Team have applied the systems, tools, processes, and procedures described in this section on previous D-B projects, including the I-95 Southern Terminus Extension (STE) D-B, I-64 Widening Exits 200 to 205 D-B, and I-81 Halls Bottom Bridge Replacement D-B.

# **Project Management Approach**

Our Team will leverage its proven history of managing complex D-B projects, public relations, and coordinating with multiple stakeholders to implement best practices throughout the delivery of the I-81 Project. By partnering with VDOT and other stakeholders, we will effectively manage all aspects of design and construction to limit impacts throughout the Project's life. Elements our project management approach are highlighted in **EXHIBIT 4.4-1**.

# **OVERALL PROJECT MANAGEMENT**

**M. Jeff Humphreys, Jr., DBIA**, will serve as the D-B Project Manager (DBPM) and will have ultimate responsibility for the Project's delivery. Mr. Humphreys has **more than 40 years of experience** and serves as a knowledgeable and conscientious project manager with a knack for public interaction and exceeding the expectations of project owners. As an added value, we have included **Pat Jones** as the Deputy DBPM. With **more than 20 years of construction experience**, Mr. Jones will support the project management role and assist Mr. Humphreys with leading the Team.

# **EXECUTIVE COMMITTEE**

Providing VDOT with an additional accountability level is our Team's Executive Committee, a best practice learned from previous major D-B projects. The Executive Committee will work with the DBPM to fulfill project objectives and commitments to VDOT and critical stakeholders. The Executive Committee comprises **senior leadership from all major Team member organizations** and provides ultimate authority to manage resources and mitigate risk, providing delivery certainty.



EXHIBIT 4.4-1 | Project Management Approach

Integration of safety and constructability into the design.

Consideration of schedule and cost implications.





Improved coordination with VDOT and all relevant stakeholders in the I-81 Project corridor.

Improved efficiency and elimination of surprises.





Attention to all design alternatives, access, equipment, and material resources.

Reduced field design changes during construction of the I-81 Project.





The members of the Executive Committee include:

- Jason Hoyle (Vice President Branch)
- Nate Orders, PE (President Orders)
- John Maddox, PE (Senior Vice President WRA)
- Owen Peery, PE (Director, Transportation RK&K)

With extensive experience and knowledge of D-B processes, these individuals will track and review project



bonus from VDOT. Client accolades received from VDOT are shown below.



#### **TEAM MEMBER HIGHLIGHT: Design-Build Project Manager**

Mr. Humphreys has more than 40 years of project management experience and has worked as DBPM on many highway and bridge projects. He excels in bringing a variety of D-B and transportation projects to completion on time and within budget. He served as the DBPM on I-64 Widening Exit 200 to 205 D-B Project in New Kent and Henrico Counties. Very similar to the I-81 Project, this challenging interstate widening project widened the roadway from four to six lanes, widened two existing bridges over the Chickahominy River, and rehabilitated existing structures to accommodate additional lanes. The project faced extreme weather conditions, including heavy flooding that impacted bridge construction. Despite these challenges, Mr. Humphreys led the team to an early completion, earning the maximum incentive

M. Jeff Humphreys, Jr., DBIA Branch Civil, Inc.

"Despite higher than normal river levels, which affected your substructure work on the bridge, pushing the project weeks behind the baseline schedule and the addition of soundwall square footage, Branch kept focused on completing the project within the original schedule. You led the project toward safety and quality while actively partnering with the Department. I appreciate your commitment to the project and look forward to working with you on future projects."

Shane Mann, PE District Construction Engineer VDOT Richmond District

performance with the Management Team to ensure necessary resources, including design and construction personnel, equipment, and materials, are allocated to safely and efficiently complete the project. They will also review and provide direction to the Team on how to best address issues regarding safety, quality, and the environment, should they occur.

### PUBLIC RELATIONS MANAGER

Clear communication and effective outreach with the VDOT Salem District is critical to engaging the public. Our Team will partner with VDOT to develop comprehensive public communication and community engagement program to achieve this goal. The DBPM will lead all design and construction-related public communications and will be assisted by our Team's Public Relations Manager, **Owen Peery, PE**.

Mr. Peery has **extensive experience working as an outreach manager in Virginia** and is familiar with VDOT's public relations processes and VDOT's Policy Manual for Public Participation in Transportation Projects. Mr. Peery and the DBPM will work with VDOT's Salem District Communications Team and the VDOT Southwest Regional Transportation Operations Center (TOC) to notify the traveling public of project impacts, including lane shifts and closures. Detailed information about our plan to keep the traveling public aware of this critical Project's construction is provided in Section 4.5.2 Transportation Management Plan.

### PARTNERING APPROACH

Our Team will implement a detailed partnering approach with VDOT from the beginning of the I-81 Project. Elements of this approach include:

- Keeping the public and stakeholders well-informed and safe at all times. The Team's approach identifies critical safety concerns during the design phase, which will help eliminate hazards during construction.
- Holding detailed partnering meetings, which include, but are not limited to, quarterly partnering meetings, over-the-shoulder reviews, task meetings, traffic management task force (TMTF), and quality assurance and quality control (QA/QC)meetings.
- Creating an environment where stakeholders can provide input to the design and construction process, maintaining the Project's integrity, and all parties' interests are represented. The public will have the opportunity to discuss key concerns throughout the I-81 Project's duration.

### **COORDINATION MEETINGS**

Continuous communication on all levels is the foundation of our integration. Our Team will implement a series of coordination meetings, which are presented in EXHIBIT 4.4-2 on page 24.

# **4.4.1 Environmental Management**

Our comprehensive **Environmental Management Plan** (EMP) outlines environmental goals, ensures the satisfaction of permit requirements, and addresses schedule requirements for permitting and environmental compliance. It institutes robust compliance, monitoring, reporting, and continuous improvement of our Team's processes. The EMP focuses on avoiding and reducing environmental impacts during design and construction by establishing proven procedures to address environmental issues, provide mitigations, and minimize risk.

#### **EXHIBIT 4.4-2** | Coordination Meetings

MEETING (FREQUENCY)	DETAILS/PURPOSE
Task Forces (Weekly during Design)	<ul> <li>Streamlines decision-making and design development process through discipline-specific, face-to-face collaboration.</li> <li>Explores opportunities to mitigate risk and minimize impacts to the public through design innovations.</li> <li>Evaluates safety, quality, design updates, environmental and sustainability opportunities, constructability, schedule, utilities, and ROW.</li> </ul>
<b>TMTF Meetings</b> (Monthly)	<ul> <li>Reviews current and upcoming MOT plans and activities to help coordinate operations with the Team, VDOT, stakeholders, the adjacent projects, and the public.</li> <li>Evaluates safety and schedule to minimize impacts.</li> </ul>
Progress and Health, Safety and Environmental (HSE) Meeting (Monthly)	<ul> <li>Facilitated by the DBPM.</li> <li>Team reviews action items and updates of all aspects of the project ranging from safety, design, environmental compliance, construction, schedule, public relations, utilities, and ROW coordination.</li> </ul>
<b>Preparatory Meeting</b> (Prior to Each Operation)	<ul> <li>Held before the start of every major work activity.</li> <li>Reviews the plan for construction of the work so that the team is clear on scope, safety, quality, and environmental compliance.</li> </ul>
QA/QC Meeting (Weekly)	<ul> <li>Reviews safety, quality, environmental compliance, QA/QC, schedules, upcoming activities, and required communication.</li> <li>Effectively keeps all parties informed of the Project's status and actively engaged.</li> </ul>
Safety Meeting (Weekly)	<ul> <li>Communicates safety trends and related messages from Corporate to the operations team.</li> <li>Provides job-specific update to the operations team.</li> </ul>
<b>Safety Meeting</b> (Daily)	• Reviews that day's tasks and associated safety risk assessments between superintendents and their crews.
<b>Design Integration</b> <b>Meeting</b> (Bi-Weekly)	• A focused meeting of key stakeholders and experts to discuss the design.
<b>Constructability</b> <b>Review Meeting</b> (Bi-Weekly)	<ul> <li>These meetings will occur during the pre-construction phase.</li> <li>Will be attended by design and construction personnel to review project constructability and provide input on the design.</li> </ul>
<b>Stakeholder Meetings</b> (As Needed)	• These meetings make certain that constant engagement of stakeholders.
Public Meetings (As Needed)	• The meetings achieve engagement with the public and that their concerns and issues are addressed throughout the project life cycle. This includes "pardon our dust" meetings.

# APPROACH TO ENVIRONMENTAL PERMITTING DURING DESIGN AND CONSTRUCTION

#### Design Approach

Identifying recognized environmental conditions/areas of concern early in the design process facilitates the timely issuance of environmental permits. Additionally, consistent communication within our Team and resource agencies helps mitigate risk to the I-81 Project Schedule.

Our approach during design includes the following elements. Upon receipt of a Notice to Proceed (NTP), our Team will refine environmental resource locations in the I-81 Project corridor based on the Conceptual Design. We will conduct fieldwork and technical services as necessary. They may include wetland delineation reconfirmation, stream assessments, threatened and endangered (T&E) species reviews, environmentally sensitive areas (ESAs), asbestos inspections on structures, and a final noise analysis that will be utilized for permitting and environmental compliance monitoring. If our refinement identifies unanticipated or unknown resources, the Conceptual Design will be modified to support avoidance and/or minimization opportunities. Our Team will coordinate with the appropriate resource agency(ies) to ensure resource protection if any new resources are identified. We will also review the environmental commitments included in the RFP, the Categorical Exclusion (CE), and other documentation and incorporate each into the Final Design.

**ADHERING TO CULTURAL RESOURCE COMMITMENTS** Because our Conceptual Design is entirely within the RFP Design's footprint, the previously concluded Section 106 effect determination of No Effect, determined on July 28, 2020, should remain valid. Per the RFP, our Team will consider the three identified historic properties along the project limits to be design constraints and will avoid impacting them beyond what is included in the RFP Design. These properties include the Virginia Baptist Children's Home/Hope Tree, Hanging Rock





WRA's Environmental Team

WRA's environmental staff have worked on several projects in the I-81 Project corridor and are familiar with its needs and issues. Their experience will enable the Team team to develop solutions that minimize impacts to ESAs in the area. It will also assist in identifying and securing the permits and environmental commitments required to ensure success on the I-81 Project.

Battlefield, and Freeman Cemetery. We will avoid any other Project-related activities on or within the viewshed of the three historic properties identified in the RFP, including but not limited to staging, borrow/disposal, and any temporary or permanent easements. We understand that any changes beyond the RFP Design may require additional cultural resources studies or coordination with the Virginia State Historic Preservation Office (SHPO).

#### **PROTECTION OF T&E SPECIES**

Our Team has reviewed the T&E species studies and coordination conducted by VDOT. The preliminary T&E Species Clearance Form dated August 21, 2020, identified two species that the Project would have no effect: the Roanoke logperch and orangefin madtom. This Form stated that the proposed Project may affect, but is not likely to adversely affect, the Indiana bat and northern long-eared bat. However, VDOT's June 2020 acoustic survey for T&E bats did not detect the presence of Indiana bat or northern long-eared bat. Additionally, the survey report concluded that a time-of-year restriction for tree cutting will not be required for the Project as long as all tree cutting occurs during the five-year time frame the survey is valid.

Per the RFP, no bridge bat inventories will be required within the five-year time frame the acoustic survey is valid. Upon receipt of an NTP, our Team will continue coordination with natural resource and regulatory agencies to ensure compliance with species protections.



#### SECURE WATER QUALITY PERMITS

Our Team refined the RFP Design to avoid and minimize impacts to streams. The RFP Design resulted in impacts to 0.31 acres (AC) of wetlands and 1,120 LF feet of streams. **Our Conceptual Design was refined to avoid impacts to 25 LF of streams through headwall modification.** This modification also eliminates floodplain impacts for the Project. As the design advances following the receipt of an NTP, we will look for additional ways to improve our Conceptual Design to avoid and further reduce impacts.

The Project will require authorization under a Virginia Water Protection General Permit 3 (up to 1,500 LF and 2 acres of wetlands) and an Individual Permit from the US Army Corps of Engineers (USACE). If impacts can be reduced to less than 0.5 acres of wetlands and 1,000 LF of streams, the Project would be authorized under a Nationwide Permit 23 for approved Categorical Exclusions. The Project will cross four named streams: Horners Branch, Dry Creek, Gish Branch, and Mason Creek. Mason Creek has a drainage area greater than 5 square miles; therefore, a Virginia Marine Resources Commission (VMRC) permit will be necessary.

If required, impacts to wetlands and streams will be mitigated through the purchase of wetland and stream credits from approved mitigation banks. During construction, if permit modifications are required, we will avoid increasing wetland and stream impacts and impacts to the



Project's schedule to the maximum extent practicable. The Project will not encroach into and will not impact the 100-year floodplain. During the development of the Final Design, the Team will conduct a hydrologic and hydraulic analysis. This analysis will ensure the adequate design of the hydraulic openings of culverts and bridges, allowing proper conveyance of floodwaters to minimize potential impacts on floodplain and floodplain hazards. The Final Design will ensure that no substantial increase in downstream flooding occurs and document the need for any Letters of Map Revision (LOMR) or Conditional Letters of Map Revision (CLOMR. It will also ensure that all encroachments conform with all applicable state and local floodplain protection standards.

#### Communication Methods

Consistent communication, both within the Team and with resource agencies, is crucial for maintaining the Project Schedule. Our Team will use the following communication methods throughout the design and construction of the I-81 Project.

#### CREATING AN ENVIRONMENTAL CONSTRAINTS MAP

Upon receipt of an NTP, our Team will create an Environmental Constraints Map that depicts any environmental constraints' locations. This living document will be distributed to all Team members so that we can design and construct around areas of environmental concern.

#### **REGULAR COORDINATION MEETINGS**

We will set up regular coordination meetings between design and construction personnel. These meetings will provide an opportunity to discuss and understand environmental constraints and ensure all disciplines address them. We will also discuss opportunities to discuss anticipated permit requirements and facilitate avoidance and minimization efforts during meetings. In addition to formal coordination meetings, the Team's environmental staff will work closely with design engineers to ensure environmental constraints are recognized throughout the design process and construction means and methods are understood in the permitting process. This communication eliminates rework during later stages of design and avoids potential permit modifications.

# REGULATORY AGENCY PRE-APPLICATION COORDINATION

Our Team will coordinate to review impact limits with the appropriate regulatory agencies before submitting permit applications to ensure their completion. This approach expedites the permitting process by allowing each agency the opportunity to review, comment, and provide recommendations on the impacts before permit application submittal.

### Environmental Approach during Construction

Our Team understands the importance of worktogether to maintain compliance ing with environmental permits, complete construction monitoring efficiently, and keep up-to-date documentation throughout all construction phases. WRA's permitting staff have experience with all aspects of environmental compliance and currently has qualified staff assisting with environmental compliance for various VDOT construction projects in Virginia.

We understand the importance of maintaining compliance with all environmental permits, including erosion and sediment control (E&SC), Virginia Pollutant Discharge Elimination System (VPDES) stormwater, and wetlands permits. E&SC devices will be inspected and maintained daily by our dedicated erosion control crew to minimize the potential for sediment loss from the Project. These inspections will cover all aspects of the Project, including staging areas, waste areas, and haul routes. Additionally, we will have a QA inspector dedicated to performing and documenting the required environmental inspections and corrective work. This dedicated QA inspector will also be responsible for maintaining the up-todate record set of E&S drawings that are part of the Stormwater Pollution Prevention Plan (SWPPP).

Before and immediately following storm events, our erosion control crew will utilize an **All Hands on Deck approach** to the inspection and maintenance of E&SC devices. Additionally, we will establish a chain of responsibility for the Team's and subcontractor's operations to ensure the E&SC Plan and SWPPP are implemented and maintained over the life of the contract. As part of the Preparatory Meeting, Construction Manager, **Bob Cross**, and Environmental/ Permits Lead, **Taylor Sprenkle**, **PWD**, will lead environmental compliance meetings before beginning work in ESAs to ensure permit requirements are followed. Also, VDOT and other appropriate agencies will be invited to review permit details and remind everyone of the permit's limitations.

As a critical part of permit compliance and before construction begins, our Team will locate authorized impact areas and subsequently delineate wetlands and streams to be avoided with orange safety fencing and signage to prevent accidental encroachment into these ESAs. Proper construction methodology and processes when working within ESAs are critical to Project success. The Team understands that working within ESAs has the highest likelihood of producing environmental violations. Authorized work within the ESAs, including both temporary and permanent impacts, will be carefully planned to provide avoidance and



**minimization to the greatest extent practical.** As examples, tree clearing will be limited to the amount necessary to perform the work, temporary work within wetlands will be performed on mats, and non-erodible material will be used for temporary stream crossings. All temporary impacts to ESAs will be restored to pre-existing contours, stabilized, and seeded with the appropriate wetland mix before leaving the construction area. Where authorized permanent impacts intersect with non-impacted wetlands and streams, identification and strict adherence to the proper use of E&SC will occur. The following narrative outlines elements of our Team's approach to achieving environmental protection and compliance.

#### CONSTRUCTION ENVIRONMENTAL MANAGER

We will take a proactive approach to environmental compliance to **identify and mitigate potential problems before they become violations**. The Construction Team includes an Environmental Compliance Manager (ECM) who reports directly to the DBPM and has the authority to stop work. Once construction begins, the ECM will collaborate with and support the construction staff to meet environmental commitments. The ECM will also advise the field construction staff of any issues or construction activities that may impact environmental permits.

#### PRE-CONSTRUCTION COORDINATION

Before construction, we will use the Environmental Constraints Map as a tool for confirming and avoiding areas of concern. Our Team will clearly demarcate all Waters of the US (WOUS) to **make certain that boundaries are easily identifiable by construction staff**. Non-impacted wetlands and WOUS will be protected by a silt fence and orange safety fence to avoid non-permitted areas. Additionally we will conduct environmental compliance training to educate construction staff on the project's ESAs and methods to prevent and minimize impacts to ESAs.

#### **E&SC INSTALLATION, MAINTENANCE, AND INSPECTION**

Following the issuance of the Construction General Permit (CGP), but before beginning land-disturbing activities, E&SC measures will be installed and inspected. The ECM will lead compliance and inspection of all E&SC measures before and throughout construction. The QAM's staff will perform and document the official C-107 reviews twice per week as required. C-107 reviews will be completed twice a week. We will provide prompt updates to VDOT regarding the status of any items identified during inspections, and we will implement corrective actions promptly. Furthermore, we will conduct internal reviews to ensure all documentation is updated and maintained.



The Geotechnical Data Report (GDR) provided in the RFP identified the presence of low-sulfur (<0.2%), Category 2 Acid Producing Material (APM) within the project limits. Our Team understands that the key to mitigating APM is locating and assessing it before it is exposed. Our Team will perform a design-level geotechnical exploration that will include APM field exploration, laboratory testing, and Acid Based Accounting (ABA) analysis to identify, locate, and assess any additional APM within the Project limits.

the I-81 Bridge Replacements in Atkins, VA.

Our Team will develop avoidance measures, design features, and mitigation measures to ensure that any acidic drainage is controlled, mitigated, and treated to ensure no long-term performance issues related to the vegetation and surface water runoff from the Project. These findings and mitigation measures will be incorporated into the Geotechnical Engineering Report (GER) and provided to VDOT for review and discussion. Our Team will develop an APM Management Plan to outline procedures for the following:

- Monitoring vegetation and water quality.
- Managing or treating surface water to ensure a pH of between six and nine.
- Treatment of cut slopes that may contain APM.
- Management of APM to be used as fill or transported off-site to approved disposal facilities.
- Classification of APM into one of four categories.



<b>EXHIBIT 4.4-3</b> Approach and Solutions for Environmental Concerns/AOCs in the Project Footprint			
ITEM/CONCERN	AVOIDANCE, MINIMIZATION, AND MITIGATION STRATEGY		
Presence of Nesting Migratory Birds under Bridges	<ul><li>Proactively attach exclusion barriers before breeding season.</li><li>Conduct daily inspections during breeding season to remove nests before eggs are laid.</li></ul>		
Hanging Rock Battlefield Trail	<ul> <li>Keep the trail at all times open during construction.</li> <li>Provide effective public outreach.</li> <li>Coordinate with Roanoke County Parks and Recreation Department.</li> <li>Design BMP maintenance access to avoid conflict with the trail.</li> </ul>		
Hazardous Materials	• Conduct the Phase II needed for four sites as early as possible.		
Noise	<ul><li>Conduct final noise analysis.</li><li>Design the walls so that they minimize impacts.</li></ul>		
Air Quality	<ul> <li>Follow regulatory guidelines during construction and take all reasonable precautions to limit the emissions of VOC and NOx during construction of the project</li> <li>Reduce dust to businesses and residential sites.</li> </ul>		
Cultural Resource Sites	• Avoid impacts to the viewshed of the three identified historic properties.		
Water Quality	• Expand the stormwater basin to improve erosion protection and water quality treatment.		
Acid-Producing Materials	<ul> <li>Avoidance by roadway alignments and the use of retaining walls.</li> <li>Elements are further defined in <i>Section 4.4.3 Geotechnical</i>.</li> </ul>		

Our Team will identify potential materials that could be used to treat the onsite APM. For example, Category 4 materials within the Project limits could be blended with low-sulfur Category 2 materials to achieve a Neutralization Potential Ratio (NPR) greater than three. If suitable material is not identified within the Project limits, offsite clean fill could be brought to the project, or the APM could be hauled to an appropriate disposal facility.

#### Approach and Solutions Areas of Concern

As shown above in **EXHIBIT 4.4-3**, the Team has identified Environmental Conditions/Areas of Concern (AOC) within the I-81 Project's footprint, analyzed the risk to that environmental condition/AOC, and identified avoidance and mitigation strategies to avoid adverse effects to the environment condition/AOCs.

Schedule Integration with Environmental Milestones Because construction cannot start until the permits are issued, obtaining environmental permits and environmental approvals promptly is always a schedule and planning priority for any project. As demonstrated in our Proposal Schedule, provided behind "TAB 3" in Volume II, our Team has already integrated key environmental permits, hold points, and approval activities into the Project Schedule.

# 4.4.2 UTILITIES

There are numerous potential utility conflicts in the I-81 Project corridor. WRA's utility mitigation strategy focuses on finding the best solution to accommodate each potential conflict, generally in this order: avoidance, minor adjustments, protection (in place), or relocation. Throughout the Technical Proposal development, our Team conducted an in-depth utility conflict analysis and initiated coordination with all



Utility coordination, adjustments, and relocations are always a major concern on roadway improvement projects. Because of the large volume of impacted utilities, our Team understands that a successful approach to utility coordination and relocations is critical to the success of the I-81 Project. WRA's Utility Team includes staff with years of experience with all utility owners in the I-81 Project corridor.

relevant utility owners to fully understand the existing utility landscape and develop a plan to mitigate potential conflicts. Our efforts allow us to present a construction scheme that will successfully coordinate, avoid, protect, or relocate utilities in accordance with all **RFP and Contract requirements.** 

### EXPERIENCE WORKING WITH SIMILAR UTILITY OWNERS

With three completed and two active D-B projects underway, WRA's Utility Coordination Team is very experienced working on VDOT D-B projects. WRA's utility staff have performed utility coordination





with many utility companies in the past, including Appalachian Power, Dominion Energy, Verizon, Cox, Western Virginia Water Authority, City of Salem, Comcast, Cox, Crown Castle, Lumos, Segra, Summit IG, Uniti Fiber, Verizon, Windstream, and Zayo.

# APPROACH FOR UTILITY COORDINATION, ADJUSTMENTS, AND RELOCATIONS

The key to successful utility coordination for the I-81 Project is early, frequent, and open communication with utility companies with potentially impacted facilities. As highlighted in **EXHIBIT 4.4-5**, we will use an active approach to the utility coordination and relocation that follows the VDOT Utility Manual of Instructions, Utility Relocation Policies & Procedures, which is the standard method for addressing utility coordination and relocations in Virginia. Our Team will ensure that an emphasis is placed on hands-on coordination throughout the life of the Project. This is the most effective method for keeping the utility companies focused and cooperating towards the shared goal of timely and cost-effective relocations. Of equal importance is accurate and complete record-keeping and the timely posting of utility information in the VDOT RUMS system, so tracking utility relocation information is readily available to the Team and VDOT partners.

# POTENTIAL UTILITY CONFLICTS AND MITIGATION MEASURES

Our Team understands the importance of avoiding utility conflicts and relocations wherever possible. We have already taken steps to minimize conflicts in the Conceptual Design, located behind "TAB 1" in Volume II. Project limits are minimized to reduce the impacts on utilities from additional ROW and temporary construction easements. Bridge substructures and access to stormwater detention facilities are designed to avoid impacts to utilities.

As the design progresses, we will minimize relocations with design modifications or protection of the asset; we will relocate utilities to accommodate proposed improvements as a last resort. All relocations will be individually addressed in detail in the construction schedule, emphasizing avoiding delays to the Project and defining with logic where work can be shifted, when necessary, to avoid any delays to daily construction efforts. The Utility Impact Matrix, provided in *Section 4.3.1*, identifies a portion of utilities that conflict with the proposed work. We've also included a matrix containing all utilities in the Project area behind "TAB 2" in Volume II.

Utility coordination activities began during the proposal preparation stage of the Project. All utility companies with facilities in the project area have been contacted, correct contact people with those companies have been

BRANCH KIERS WRA

## **EXHIBIT 4.4-5** | WRA Utility Coordination Process

#### **1** REVIEW RFP PLANS

- Initial plan review.
- Highlight potential utilities/conflicts.
- Determine ROW and project limits/utility easements.

#### <sup>2</sup> REVIEW EXISTING SUE REPORTS

- Review test hole information in plans.
- Review data from SUE studies.
- Update our initial Utility Matrix, inclusive of all utilities.

### $\frac{3}{3}$ SITE INSPECTION

- Experienced and local team members make site inspections.
- Identify and quantify utilities not shown on RFP Plans and SUE reports.
- Update our Utility Matrix and evaluate potential solutions.

#### **4** FIND SOLUTIONS FOR CONFLICTS

- Highlight potential alternatives.
- Coordinate with design engineers to develop solutions.
- Develop innovative approaches to avoid conflicts.

### 5 UTILITY COORDINATION

- Meet with each utility agency (private and public).
- Develop the Utility Relocation Schedule.
- Update relocations in the Project Schedule.

#### 6 FINALIZE SCHEDULE/COST

- Verify each private utilities' prior rights.
- Prepare VDOT UT-9 Forms for each utility.
- Prepare a final Utility Relocation Schedule and prorate costs.

#### 7 FINALIZE DOCUMENTS

- Finalize relocation/adjacent plans with public utilities.
- Combine the schedule with our Conceptual Design.
- Submit to VDOT for approval.

#### 8 **RIGHT OF WAY**

- Obtain easements for relocation if needed.
- Prioritize acquisitions to support early utility relocations and construction.
- Advise utilities when right of way is available for relocations to begin.

### <sup>9</sup> EXECUTION

- Begin utility relocations/adjustments.
- Monitor operations for unforeseen/unknown utilities and act.
- Maintain open communications to quickly resolve
- unforeseen issues.

confirmed, and existing facility records from them have been obtained. These records have been compared to the RFP Design survey and our Project site inspection for accuracy and completeness. The utility companies identified as having facilities in the project area are Appalachian Power, Citizen's Telephone, Comcast, Roanoke Gas, Salem City Electric, Salem City Water and Sewer, Segra, Verizon, Western Virginia Water and



Sewer, and Zayo Communications. Osprey Fiber has agreements with VDOT for future fiber installation in the Project area.

Mitigation strategies to ensure the timely relocation of the facilities in conflict will start with consistent communication with the utility contacts to remind them of their schedule commitments and ensure that they have their preliminary steps underway to complete the work. All pole work needs to be performed in a specific order, starting with the facilities at the top of the old poles, electric, and then working the way down to the lowest lines. Each utility company will be informed of their place in this rotation and will be kept informed of the progress so that crews can be mobilized when it is their turn. The utility designation survey and test holes will be a top priority for the project as soon as an NTP is issued. These activities will determine the exact locations of the existing buried lines and make plans for any necessary relocations.

Our Team will make use of the VA811 Location Enhanced Ticket Search (LETS) service offered by VA811 to ensure daily that all of Miss Utility Tickets are cleared before proceeding with any excavation work. WRA will provide all field supervisors with training in the use of the app. Supervisors will also ensure that all field marking work reported to have been performed by the utilities is performed. If a dis-



crepancy is noted, the three-hour locate request feature of the Underground Utility Damage Prevention Act will be utilized to get the facilities marked.

If a new utility facility is discovered, or if the work of the design-builder damages an existing facility, work in that area will immediately be halted. We will work diligently to identify the facility owner in question and provide all assistance needed to ensure that services are quickly restored. If an unknown facility requires relocation, work will begin as soon as possible to design a new path to eliminate any conflicts. Advanced utility coordination activities will take place immediately following the issuance of an NTP for the Project. Activities will include hosting the 45-day Utility Meeting and Preliminary Utility Review Meeting with all relevant utility companies to explain the Project's impact and work sequence. We will distribute proposal plans to the utilities to allow for their review as early as possible.

Utility companies will be made aware immediately of facilities most likely in conflict and how those conflicts

will play into the Project's staging. We will compile the locations of all necessary utility test holes and investigations performed to verify if the locations for the lines shown in the survey match the actual locations on site. As the design of the Project progresses, close coordination with the utility owners will continue. Our Team will ensure that designs minimize or avoid utility conflicts by using an online, cloud-based utility coordination tracking system that incorporates both "ball-in-court" notifications and set due dates for utility coordination tasks. The utility representatives will be able to access the current version of the tracking system at all times.

When the design has reached a completeness level to show all utility impacts, our Team will hold a Utility Field Inspection (UFI) Meeting. Our Team will distribute plans and a preliminary VDOT UT-9 Form to all affected utility companies approximately two weeks before this meeting. During the UFI Meeting, all of the utilities will be able to put forth relocation strategies, preliminary schedules for performing adjustments and relocations, and utility easement requirements, if they exist.

Our Team does not expect utility easements will be necessary for this project. Due dates will be set for utility relocation and adjustments plan and estimate submittals and no conflict letter submissions. Further, we will harness our extensive resources to benefit each of the utility companies when possible. Examples of assistance that will be made available to utility companies include traffic control assistance, clearing, construction entrances, and lay-down yards. This will reduce costs and help mitigate any delays. As utility adjustments and relocations are completed, we will update VDOT regarding the utilities' progress and close them out as appropriate. The utilities will be directed to submit prompt and correct drawings for all necessary As-Built land use permits.

# INTEGRATION OF UTILITIES INTO SEQUENCING TO PREVENT DELAYS

Upon award of the Project and receipt of an NTP, utility coordination efforts will occur in a manner that is complementary to the developed sequence of construction to minimize impacts on the critical path. A significant utility impact is fiber optic lines throughout the median of I-81 along the Project corridor's entirety. Relocation of these facilities to a permanent location along the shoulders of the future roadway will be a paramount goal at the early stages of the Project. Additionally, we will accelerate mitigation efforts for utility conflicts with proposed bridge substructures to avoid schedule impacts for the bridge construction schedules. We will provide consistent feedback from the utility relocation efforts to the Project Scheduling Team to ensure that the schedule remains optimized for Project completion.



# 4.4.3 Geotechnical

Our Team has reviewed the available geotechnical information for the I-81 Project in the RFP documents, emphasizing the Geotechnical Data Report (GDR) and GDR Addenda, and will perform further investigations upon receipt of an NTP. These efforts will validate and confirm our proposed design and reduce VDOT's construction costs.

A leading national provider of geotechnical, dam, and tunnel engineering services, dedicated design subconsultant **Schnabel Engineering**, **LLC** (Schnabel) has extensive experience in the I-81 corridor, including numerous VDOT bridge and roadway projects; evidence of this is highlighted below in **EXHIBIT 4.4-6**. Schnabel is a leader in karst terrain evaluations, with over 1,000 projects completed in Virginia and the Appalachian Ridge and Valley.

Geotechnical Task Lead, **Steve Conner, PE**, will lead a team of geotechnical engineers who have addressed karst-related problems on hundreds of projects, including characterizing karst features and their impacts on transportation, commercial/industrial, and residential structures/facilities. Schnabel's soil, materials, and asphalt laboratories in Blacksburg, Richmond, and three other offices, **are nearby the I-81 Project site** and accredited by the AASHTO Materials Reference Laboratory and USACE. Schnabel's extensive geotechnical engineering experience with the various local geologies and similar projects will guide our design and analysis. Their firm has a wealth of expertise with over 125 projects along the I-81 corridor and over \$15B of D-B and P-3 transportation projects.

## **CONSTRUCTION METHODS**

Schnabel will be an integral part of this project's construction phase and will work hand-in-hand with Branch, Orders, the Design Team, and the QC Team. Schnabel will be on-site during critical geotechnical construction activities, including shoring and foundation construction, and on standby to help identify and mitigate potential issues that arise during construction. Having the Geotechnical Engineer-of-Record (EOR) intimately involved in construction will reduce risk, reduce overall costs, streamline the schedule by reducing response time to Requests for Information (RFIs), and provide a better overall product to VDOT and the traveling public. The Geotechnical EOR will provide certification that the work was subjected to the necessary testing and inspection requirements and meets the specifications. We will include this certification in our monthly status report.

# ADDRESSING GEOTECHNICAL CHALLENGES

The I-81 Project is located within eight different mapped geologic formations and along the Salem Fault line. Site conditions include highly variable subsurface conditions that can create unexpected issues, increased costs and delays in the Project Schedule during construction. Schnabel's local experience and expertise will enable our Team to identify associated risks, extensive subsurface exploration, and laboratory testing programs to define the geologic formations. We identified geotechnical risks on this project utilizing the borings and test results in the GDR, the GDR Supplement, and GDR Addenda (collectively, the GDRs) provided with the RFP and Addenda.




Our Team understands the site's geotechnical characteristics and has used and refined methods to mitigate similar risks. Our mitigation approaches and previous applications in VDOT's Salem District and other similar areas have proven successful. Our subsurface exploration and testing program will include soil test borings and possibly air-track probing, rock coring, in-situ geophysical testing, and laboratory testing. This program's results will be the basis of our Final GERs, which will include recommendations to mitigate the potential geotechnical risks identified. The Final GERs could also disclose additional potential risks. Schnabel will identify these risks and provide mitigation alternatives in the final reports. Based on the existing data and local experience, our preliminary assessment of the geotechnical risks on this project include (but are not limited to) the items discussed in this section.

#### Construction Near Existing Foundations

New construction of mainline bridges will be performed close to existing foundations. Limited workspace along the existing I-81 corridor could negatively impact the traveling public and worker safety, MOT, scheduling, and stability of existing structures. Also, settlement of the underlying soils due to adjacent embankment construction could result in settlement of the existing embankments and foundations supporting the existing bridges. Most of the existing bridges are founded on vertical and battered piles. The battered piles could be damaged due to settlement from constructing new embankments. The project will require the addition of foundation elements while maintaining the integrity of the existing foundations.

#### POTENTIAL MITIGATION STRATEGIES

- Schnabel's experience with temporary shoring methods applicable to the Salem District and bridge replacement techniques that are safe and effective will benefit the Project's construction.
- Schnabel's team of in-house geostructural engineers will develop efficient temporary and permanent shoring designs.
- Our Conceptual Design considers the integrity of the existing foundations (the ones to be removed and ones to remain). Items considered by our Team include the development of appropriate foundation types and their locations, the sequence of construction, shoring, and the use of lightweight materials to construct embankments.

#### Schnabel Experience Highlight:

On the I-95 SB Rappahannock River Crossing Project, Schnabel utilized sheet piles as shield piles to minimize settlement for the bridge widening of Route 17.

#### Slopes

Our Conceptual Design includes critical and non-critical cut and fill slopes throughout the Project limits. Existing slopes are generally at 2:1 and appear stable at this time. The Conceptual Design utilizes 2:1 or flatter slopes. The geology in some of the critical and non-critical slopes has been identified as potentially APM, which could lead to issues discussed under the APM risk. Also, some slopes containing fine-grained soils may have stability issues requiring additional ROW to flatten the slope or expensive stabilization techniques to achieve an adequate factor of safety.

#### POTENTIAL MITIGATION STRATEGIES

- Our Conceptual Design will minimize the disturbance of existing slopes.
- We will perform the necessary classification and shear strength testing to evaluate the slope stability.
- RFP Addendum borings indicate that around 40% of the existing soils in proposed cut or fill slopes consist of fine-grained soils. Therefore, extensive exploration and advanced laboratory testing will be performed to properly characterize this material's shear strengths, including using peak shear strengths for deeper material and fully-softened shear strengths for infinite slope stability analysis.
- RFP Addendum borings indicate that most of the soils in the slopes consist of sandy soils. Because fine-grained soils were not encountered in these slopes, these slope's stability can be evaluated using peak shear strengths rather than lower fully-softened shear strengths.
- No highly-plastic soils will be used to construct new embankment slopes.

#### Schnabel Experience Highlight:

On the I-81 NB Truck Climbing Lanes, (MM 195 to MM 202.5), Schnabel performed extensive in-situ sampling and laboratory testing to define suitable and unsuitable materials for use in embankment slopes to meet the VDOT's design criteria.

#### Karst Features

The southern portion of the project is within the Elbrook Formation that commonly contains karst features. Karst features include highly-erratic rock surface, sinkholes, caves, and other karst features that adversely affect foundations for bridges and walls, stormwater management structures, embankments, pavements, among others. Improper design and construction could lead to sinkholes, excessive settlement, or other karst-related problems that require future and on-going repairs to pavements and structures, affecting the flow of traffic and Project cost.



#### POTENTIAL MITIGATION STRATEGIES

- Schnabel is experienced with design and construction in karst environments and understands critical steps to reducing risk, including:
  - » Identifying karst features.
  - » Controlling surface water.
  - » Not interfering with the groundwater.
  - » Shifting structure locations, where feasible.
  - » Designing the most appropriate foundation system based on geologic conditions.
  - » Developing a sinkhole mitigation plan that can be implemented quickly, if/when needed.
- Based on experience, geology maps, the RFP borings, and the As-Built bridge plans for the Route 112 intersection, karst features are present at the Route 112 Intersection. Our Team will further define these karst feature's limits during the subsurface exploration program by drilling and geophysical surveys.
- Our bridge foundation design accounts for the erratic nature of karst geology. Semi-integral abutments are used to provide flexibility for the lateral locations of piles during construction (i.e., if a pile skews, walks, or is damaged during driving, it can be re-driven at a different location without having to re-design the entire abutment).

#### Schnabel Experience Highlight:

Schnabel's team of drillers and geophysicists have extensive experience in karst conditions. Recent experience includes the I-81 Over Route 686 (Mulberry Lane) Bridge Replacements.

#### Acid-Producing Materials and Corrosivity

The RFP identifies potential APM within the Project limits. The Millboro and Needmore shales are mapped geologic formations that the project intersects. These formations are known at the regional level to contain APM. The RFP includes laboratory testing results for three soil samples considered Category 2 per the RFP's APM Special Provision.

The effects of APM include environmental impacts to waterways, vegetation, and wildlife; corrosion of structures, including culverts, bridges, signs, and walls, among others; and accelerated weathering of surrounding rock that can lead to rock slides and slope failures. Laboratory test results in the GDR indicate that a significant amount of the on-site soils are corrosive to metal and concrete. Excessive corrosion can lead to maintenance issues or structural failure of bridge foundations, retaining walls, and culverts.

#### POTENTIAL MITIGATION STRATEGIES

- Our testing program will provide sufficient data to follow the APM Special Provision to evaluate the presence and location of APM. These test results will be used to make recommendations for avoidance to minimize disturbance by adjusting the design, covering these soils and rocks with non-aggressive fill, and neutralization with alkaline materials per the Special Provision. We will not place this material around structural foundations to reduce potential corrosive conditions.
- The Conceptual Design focuses on avoiding earthwork in potential APM areas and prioritizes the use of retaining walls to reduce APM exposure.
- Schnabel will provide an APM specialist to provide detailed analysis and recommendations for the I-81 Project when needed.
- Subsurface exploration and laboratory testing will be performed to accurately categorize the corrosivity of the various geologies and soils encountered throughout the project limits in respect to metal and concrete.
- The re-use of corrosive soils will be optimized to not be used as backfill around structures.
- Structural elements will be designed considering the soil corrosivity, such as considering the reduced flange and web thicknesses of piles supporting the bridges per Chapter 23 of the *VDOT Manual of the Structure and Bridge Division*.

#### Schnabel Experience Highlight:

Schnabel's experience includes the I-95 SB Rappahannock River Crossing D-B, where recommendations for use and treatment were supported by appropriate testing of the acidproducing clays of the Calvert Formation.

#### Unsuitable Soils

Almost 50% of the GDR borings indicate unsuitable materials in the upper soils (e.g., the top 3') per the RFP requirements. Based on Schnabel's experience in the I-81 Project area, a significant portion of the fill placed to construct the original I-81 will consist of unsuitable high plasticity clays and silts. The effects of unsuitable soils include increased costs and delays in construction for undercutting and/or treatment of unsuitable materials. Other potential effects include future repairs and possible structure or slope failures from not properly identifying and/or not properly remediating unsuitable materials.

#### POTENTIAL MITIGATION STRATEGIES

• The depths where unsuitable soils are not allowed were updated in the RFP Addendum #2 to depths suitable for in-situ stabilization, which is generally



faster, reduces waste and extra hauling, and is more efficient than traditional undercut and replace. It also reduces exposure of undercut subgrades that could lead to additional undercutting.

- Wet soils that are considered unsuitable due to high moisture contents (except for those containing deleterious materials) will be improved by drying and/ or chemically treating with lime or cement so that they can be reused as compacted embankment fill.
- Highly-plastic or low CBR soils that are also considered unsuitable where present in the pavement or minor structure subgrades will be undercut and replaced with suitable soils or chemically treated in place to the extent permitted by the RFP and VDOT Road and Bridge Specifications.

#### Schnabel Experience Highlight:

Schnabel's experience includes utilization of soils from similar geologic conditions and lime stabilization. Their recent experience includes the I-81 Auxiliary Widening Project, as well as the I-95 SB Rappahannock River Crossing D-B, where lime stabilization was utilized to mitigate undercut and replacement of unsuitable soils.

#### Cobbles and Rubble Fill

RFP borings encountered shallow refusal, skewed augers, and cobbles in the existing fill and natural soils at each of the intersections that require bridge replacements or widening. Erratic subsurface conditions with cobbles and potential rock fill may cause early refusal, misalignment and/or damage of driven piles. These geologic conditions can also obstruct trenchless installation of culverts. Rubble fill can potentially cause a jack-and-bore installation to become stuck or lose line and grade, both of which will be problematic for gravity storm drain installations.

High groundwater and running soils may also be present in stormwater structures due to creeks or drainage channels and the potential for rock or mixed face conditions in the general geologic setting and along waterways. Issues with trenchless installation include requiring alternative trenchless equipment, unplanned soil improvement programs, unexpected MOT adjustments, settlement of active roadways, and other issues.

#### POTENTIAL MITIGATION STRATEGIES

- Additional exploration to provide a better characterization of the subsurface conditions.
- Design semi-integral abutments that allow for more flexibility in pile tolerances over integral abutments.
- Pre-boring piles will reduce the effects of shallow obstructions, ensure proper pile alignment, reduce

or eliminate pile damage, and can streamline foundation construction.

• Schnabel's in-house tunnel experts will help develop proper investigation programs, ground characterization, assessment of risks, and feasible methods for trenchless installations based on ground conditions, length and size of the stormwater structures, and potential risks. Schnabel will work with Branch-Orders to determine the best installation method based on the size and type of structure and anticipated ground conditions.

#### Schnabel Experience Highlight:

Schnabel's experience for obstructions at bridge abutments includes the I-81 Over Route 686 (Mulberry Lane) Bridge Replacement Project (recently completed by Lead Contractor Orders) and the Falls Run Interceptor Project.

#### Pavement Design

RFP Pavement sections for Mainline I-81 will be verified during the early stages of the Project development. The GDR included a limited number of CBR tests and no resilient modulus (Mr) tests or unconfined compression strength tests to correlate to the resilient modulus, as required by the specified *AASHTO Mechanistic-Empirical Pavement Design Guide (MEPDG)* method for pavement design. The GDR test results indicate the on-site materials generally have a low CBR value. The Preliminary Pavement Design Report included in RFP Addendum #3 considered a higher resilient modulus value than would be expected when correlating to CBR values.

The Pavement Design Report indicated the design resilient modulus was based on laboratory testing Schnabel performed for the Auxiliary Lanes Project and the falling weight deflectometer data performed by others specifically for this project. The subgrade strengths beneath the pavement sections need to be further investigated to evaluate the required minimum pavement sections for the project. An inadequate pavement section could lead to poor service life and increased maintenance and long-term costs.

#### POTENTIAL MITIGATION STRATEGIES

- Performing additional testing for CBR and Mr to validate the minimum pavement sections in the RFP. Schnabel will perform this work during the scope validation period.
- Schnabel was one of the first consultants in Virginia to utilize the MEPDG in practice. Their team has extensive experience with MEPDG designs, which will help in evaluating the large stone and



FDR pavement sections specified in the RFP. Their staff also understands the sampling and laboratory requirements necessary for the MEPDG analysis.

#### Schnabel Experience Highlight:

On the I-95 SB Rappahannock River Crossing D-B, the RFP pavement section did not meet the VDOT MOI Chapter 6 requirements. VDOT and Schnabel worked together to determine a solution that met the District's requirements.

# 4.4.4 QUALITY ASSURANCE AND QUALITY CONTROL

Quality is measured by meeting or exceeding VDOT's requirements, specifications, and expectations. By implementing a formal QA/QC Plan, our Team will effectively navigate through the processes, reviews, and reporting activities required to meet quality guidelines and deliver this Project to VDOT, the citizens of Roanoke County, and the City of Salem on time and budget.

The QA/QC Plan will detail expectations of our Team, roles and responsibilities of each Team member, interactions of Team members, methods to determine enough staffing for the work, testing and inspection requirements, and specific requirements for communication and documentation. The QA/QC Plan will meet the VDOT's Minimum Requirements for Quality Assurance and Quality Control on Design-Build and Public-Private Transportation Act Projects, July 2018. We will reinforce to all Team members that quality starts with the individual.

Our Quality Assurance Manager (QAM), Chad McMurray, PE, PMP, CCM, DBIA, will act as a single point-of-contact with VDOT and will manage the QA/QC Plan in accordance with the I-81 Project Contract. With more than 26 years of experience, Mr.

McMurray will work independently of the Designer, Contractor, and QC Team. He will act on behalf of VDOT to ensure that all work and materials, testing, and sampling are performed according to the Contract's requirements and the Approved for Construction (AFC) plans and specifications.

Mr. McMurray will be available immediately upon contract award and on the I-81 Project site full-time for the duration of construction operations. He will also be supported by two full-time on-site Senior QA Inspectors, with one focused on grade work and one focused on bridge work. An additional two to three QA Inspectors will be on-site as work levels demand, with additional support available as needed utilizing materials testing technicians or additional QA inspectors.

#### DESIGN QA/QC APPROACH AND STAFFING

Our Team integrates quality managers into its management staff. Design QA/QC Manager, **Brad Stipes**, **PE**, will be an integrated member of the Design Team and will be invited to all management meetings to facilitate consistency and communication. He will work closely with Design Manager, **Mike Russell**, **PE**, **DBIA**, and design discipline task leads to ensure the review process proceeds according to the QA/QC plan. Our experience and commitment to providing quality and knowledge of RFP requirements, standard specifications, among others, has shown to significantly reduce VDOT's review time and minimize the need for additional QA/QC reviews.

The design quality process will be managed using conformance checks, independent technical reviews, and internal audits. These checks will verify our drawings and specifications comply with applicable criteria and contract requirements. On previous projects, this attention to detail on QA/QC reviews and processes has proven beneficial to VDOT in performance audits. Quality checks and reviews will be per the Quality Planning process and identified in a Project Deliverable

#### **TEAM MEMBER HIGHLIGHT: Quality Assurance Manager**

Mr. McMurray is responsible for construction management and inspection (CMI) for the Southwest Virginia territory of WRA's southern CMI operations. In this role, he has direct control and supervision of all CMI services provided out of the area and oversees a staff of 20 employees. He has 26 years in construction on major highway transportation projects and acting as QAM on D-B projects for VDOT. With extensive experience in the I-81 corridor, he recently worked as the QAM on the I-81 over Route 11. Working with Lead Contractor, Orders Construction, his responsibilities included the development, updating, and implementing of a project specific QA/QC plan for a

project that included two bridges on I-81. His additional experience includes the I-81 Exit 114 D-B in Montgomery County and I-81 Halls Bottom Road Bridge Replacement D-B in Washington County.



Chad McMurray, PE, PMP, CCM, DBIA Whitman, Requardt & Associates, LLP





Quality Matrix. This matrix will establish the framework for all design QA/QC activities. The Project Deliverable Quality Matrix defines the time frames for all quality checks and reviews necessary before submitting a deliverable to VDOT. This process is further explained above in **EXHIBIT 4.4-7**.

Our Team will complete a Discipline QC Check, Independent Design Check (when applicable), and Senior Technical Review (when appropriate). Those comments are resolved and verified before entering Interdisciplinary or Constructability Review. Entrusted Engineer-in-Charge, **Maggie Cossman, PE, DBIA**, will be the conduit between the Construction and Design Teams during this interdisciplinary review. All checks and reviews will be completed, and those comments resolved and verified before completing the QA Review.

We will take steps to ensure each design element receives a thorough review and is documented accurately. QC begins with assigning the most appropriate person to a given design task from the outset. Each member of the Team is responsible for controlling the quality of the deliverable. The specific checking process for each design element involves an Originator, Checker, Back-Checker, Updater, and Verifier, for which explanations for each are provided below:

ORIGINATORS: These are engineers or other qualified persons that initiate a work product. They continuously check their specific work elements during production and must address all comments, questions, and revisions noted by the checkers. The Originator also coordinates reviews with the Design QA Manager, who maintains the schedule to ensure the timely completion of required checks.

- CHECKER: These reviewers perform detailed checks of the design or reviews of reports; they are not involved in the production of those documents. These Team members have technical knowledge and qualifications, at a minimum of the level of the originators of the work being checked or reviewed.
- BACK-CHECKER: These individuals review the checker's comments and resolves any differences regarding the comments. The Back-Checker then makes, supervises, and implements the agreed-upon changes. This person is typically the originator of the document.
- **CORRECTOR:** This is the person who updates the original document after the back checker has agreed with all of the checker's comments. This person can also be the originator.
- **VERIFIER:** The verifier reviews the corrected document to verify the agreed-upon changes have been incorporated correctly. This person may be the checker or the originator if that person did not update the design document.

Our Team anticipates that the Department will continue to utilize the Deliverables Management component of ProjectWise to process and track the various design submittals required. Once a submittal has finalized by following the QA/QC process was described previously, it will be transmitted to the JV's Document Manager. This individual will be responsible for processing the



submittal into Deliverables Management following the appropriate review flow developed for the project. This coordination will ensure all relevant staff are notified that the submittal is ready for VDOT's review. Our quality review process is further demonstrated to the right in **EXHIBIT 4.4-8**.

#### **CONSTRUCTION QA/QC & STAFFING**

The QAM, Chad McMurray, PE, PMP, CCM, DBIA, reports directly to the DBPM, Jeff Humphreys, DBIA, and is responsible for overseeing QA for all construction activities. Mr. McMurray has the responsibility and authority to report any findings directly to VDOT and stop any work that fails to meet contract requirements. He will oversee the personnel responsible for performing QA inspections and testing all materials used and work performed. Adequate QA staff will be available to ensure that VDOT does not require additional QA/QC oversight. Staffing levels will be determined by the schedule and Testing and Inspection Plan developed for each Work Package. We anticipate that the number of QA inspectors will range from two to five at any given time.

Our QC staff, operating independently from the QA staff, will perform all required sampling and testing as required by the contract documents. QA and QC will have separate independent AASHTO Materials Reference Library (AMRL) certified testing laboratories. The QAM will determine and certify to VDOT whether the materials and work are compliant with the approved drawings, specifications, and applicable standards and reference documents, as indicated in the Contract. Mr. McMurray will also ensure all inspectors have the appropriate certifications for the testing to be performed.

QC Manager (QCM), Austin Williams, will report directly to Construction Manager, Bob Cross. Mr Williams and manage the day-to-day QC inspections and material testing. The QC Team will be responsible for the inspection of construction activities and all QC sampling, testing, and required analysis of materials to make sure the construction quality is verified at frequencies that meet or exceed contract requirements.

QC Inspectors for Roadway and Bridges will complete an Inspector Daily Report (IDR). The IDR will be submitted to the QCM, QAM, DBPM, Construction Manager, and others daily, along with documentation of any material tests performed. Specific staffing levels will be determined by the schedule and Inspection and Testing Plan developed for each work package. Between two and eight QC inspectors are anticipated on the Project.





#### **SECTION 4.4 | PROJECT APPROACH**

Technical Proposal, Volume I | I-81 Widening MM 136.6 to MM 141.8 Design-Build



<b>EXHIBIT 4.4-9</b>   Construction Qua	lity Assurance/Quality Control Process	
CONSTRUCTION QA/QC PLANNING	EXECUTION	CLOSEOUT
<ul> <li>Review the Project Schedule.</li> <li>Review item specifications.</li> <li>Develop inspection work plan.</li> <li>Schedule pre-item work meeting.</li> </ul>	<ul> <li>Conduct preparatory meeting.</li> <li>Perform inspection and documentation.</li> <li>Perform required materials testing.</li> <li>Enter documentation into PlanGrid<sup>®</sup> (or similar).</li> </ul>	<ul> <li>Confirm all work is completed.</li> <li>Item pre-final inspection.</li> <li>Create pre-final punch list.</li> <li>Project final inspection/punch list.</li> <li>Punch list work completed.</li> <li>Project acceptance.</li> </ul>

The construction component of our QA/QC plan will address the specific requirements and elements of the construction QA/QC following the 2018 VDOT Minimum Requirements for Quality Assurance and Quality Control on Design Build and PPTA Projects from planning and execution to closeout. Before each AFC work package is submitted for review and acceptance, the QAM will review it with the Design Manager to determine the specific elements of work and the associated QA/QC requirements are included in the package.

As part of the AFC work package, the QAM will work with the Design Manager to identify all work elements that will require testing. As part of this process, the QAM and the QC Manager will review the Project Schedule to determine the staffing needed for the work package. The QAM and QC Manager will also confirm that all required certifications are maintained, identify the definable features of work included in the package, and establish the minimum testing and inspection requirements needed to ensure all work is completed based on the quantities in the work package comply with the Project's requirements. This process, demonstrated above in **EXHIBIT 4.4-9**, provides appropriate staffing for the job and establishes all team members' expectations for the QA/QC of the work.

Conducting a pre-item work meeting before the preparatory meeting for each definable feature of work is the next step in ensuring that all requirements are met. This meeting establishes who will be required at each preparatory meeting, ensures all information is reviewed, and verifies that all previous work is completed so that a successful preparatory meeting can occur.

Once the construction phase begins, and as established by the specific AFC work package QA/QC plan, the QA personnel will monitor the work and monitor the QC process for adherence to the plan. Hold point meetings will be held for all major construction operations. QA will also coordinate their independent assurance system to independently evaluate all sampling, equipment, and testing and inspection procedures used by QC personnel. This system ensures that work has been tested and inspected and that those procedures used during testing and inspection meet industry standards and comply with the requirements of the I-81 Project. Adjustments will be made to the plan to improve workflow, testing processes, and documentation processes to ensure that the QA/QC produces verifiable and documented testing of work and works seamlessly with contractor operations.

The QAM will compile, maintain, and update the Project Materials Book and complete the VDOT C-25 forms. The QAM will maintain the Project Materials Book electronically on VDOT Form TL-142DB and will perform monthly reviews of the Book by spot-checking at least five materials for their source documentation. The QA/QC Plan will specify documentation required for the Project and will establish a system of cloudbased document control, allowing all Team members to have immediate access to the information needed.

The system will also comply with VDOT's D-B Construction Quality Improvement Program (DBCQIP) by putting in place procedures to document that tasks were completed in accordance with the requirements and DBCQIP checklist.

#### CONSTRUCTION QA/QC STAFFING PLAN

For a project of this size, scope, and complexity, we understand that our QA/QC staff must be experienced and robust to ensure we deliver a final product that meets or exceeds the requirements. **Our Team will incorporate proven processes and procedures to standardize and streamline the construction quality approach.** The procedures developed establish proper controls so that the Project will meet all quality requirements and contractual expectations of VDOT and will be built to meet or exceed service-life requirements. The DBPM will have ultimate responsibility to ensure that Project policies are effectively implemented. He also will ensure that our Team is staffed with knowledgeable and dedicated people who are committed to designing and constructing the Project.

**EXHIBIT 4.4-10** on page 39 outlines primary quality personnel and their respective responsibilities.



<b>EXHIBIT 4.4-10</b>   Co	onstruction Quality Asso	urance/Quality Control Personnel and Responsibilities
NAME/ROLE	REPORT	DESCRIPTION OF RESPONSIBILITIES
M. Jeff Humphreys, Jr, DBIA D-B Project Manager	Reports to VDOT	<ul> <li>Responsible for the overall Project design and construction, QA/QC management, and contract administration.</li> <li>Ensures the Project receives the necessary staff and equipment.</li> </ul>
Maggie Cossman, PE, DBIA Entrusted Engineer-in- Charge	Reports to the DBPM	<ul> <li>Responsible for ensuring that all work is integrated and is in conformance with the Contract Documents.</li> <li>Ensures constructability and functionality.</li> <li>Compiles the final AFC Plans and Specifications.</li> <li>Will be onsite full time from commencement of construction through Final Acceptance of the Project.</li> </ul>
<b>Chad McMurray, PE, PMP, CCM, DBIA</b> QA Manager	Reports to the DBPM and VDOT	<ul> <li>Responsible for overall development, implementation, and periodic assessment of the team's QA/QC Plan and independent QA inspection and testing of all materials and work.</li> <li>Verifies that all work and materials testing and sampling on the Project are performed in conformance with the contract requirements and the AFC plans and specifications.</li> <li>Has full authority to stop any work that fails to meet the requirements of the contract documents.</li> <li>Develops the QA/QC Plan, manages the QA testing and sampling program, monitors the contractor's QC program, assures quality in meeting contract requirements, maintains documentation and test reporting, reviews, and certifies requests for payments to VDOT, and communicates closely with VDOT regarding compliance results.</li> <li>Works directly with the Design Manager, Mike Russell, PE, DBIA, to resolve quality issues that require design input.</li> </ul>
<b>Kemmy Mullins</b> Lead QA Roadway <b>Tony Guy</b> Lead QA Bridge	Reports to the QAM	<ul> <li>Verifies QA testing and inspection activities are completed, QC inspections are observed, and any non-conformities are corrected and documented.</li> <li>Responsible for QA inspection activities for conformance with AFC plans and specifications.</li> <li>Responsible for documenting and reporting all inspection and testing within 24 hours of work performed.</li> <li>Additional WRA QA Inspectors will support Lead QA Inspectors when assistance is needed.</li> </ul>
SC Stevenson Consulting Staff QA Testing Lab	Reports to the QAM and Lead QA Inspectors	<ul><li>Provides an AMRL-certified laboratory.</li><li>Completes QA laboratory testing.</li></ul>
<b>Bob Cross</b> Construction Manager	Reports to the DBPM	<ul> <li>Responsible for QC activities and ensuring construction is performed safely and materials and work are in conformance with the approved plans/ contract documents.</li> <li>Responsible for implementing and executing the Construction QC plan.</li> </ul>
Austin Williams Construction QC Manager	Reports to the Construction Manager	<ul> <li>Responsible for verifying all work, materials, inspections, and testing are compliant with contract requirements.</li> <li>Supports the implementation and execution of the Construction QC plan.</li> <li>Ensures the adequate staffing of qualified QC testing and inspection personnel.</li> </ul>
NXL Staff QC Inspections for Roadway and Bridges	Reports to the QCM	<ul> <li>Responsible for QC inspection and testing of items of work for conformance with AFC plans and specifications.</li> <li>Responsible for documenting and reporting all inspection and testing within 24 hours of work performed.</li> </ul>
ECS Staff QC Testing Lab	Reports to the QCM	<ul> <li>Provides an AMRL-certified laboratory and completes QC laboratory testing.</li> <li>Materials testing field and laboratory professionals are VDOT-certified to provide the most thorough inspections and accurate reporting available.</li> <li>Responsible for QC inspection activities for conformance with AFC plans and specifications.</li> </ul>





WRA has performed QA/QC services in the I-81 corridor and are familiar with the area's geology.

**Top left photo:** QA/QC concrete depth check on the I-81 over Route 11 Project.

**Top right photo:** Rebar check identifying improper rebar tie on the I-81 over Route 11 Project.

**Bottom right photo:** QC deck pour dry run on the I-81 over Route 11 Project.



## ENSURING PROJECT QUALITY

Our Team places a strong emphasis on quality, realizing that <u>our work is our legacy</u>. We will reinforce to all Team members who work on design and construction that quality begins with them. To guide them on this mission, we will create a QA/QC Plan using proven policies and control methods to produce quality work. It will be structured to assist our Team in properly managing quality compliance and providing an objective measure of quality performance. All employees will comply with the requirements specified by the QA/QC Plan.

Our QA/QC Plan requires the performance of periodic audits of the contractor, designer, subconsultants, subcontractors, and suppliers. A best practice learned through the years and as a proactive measure, Branch-Orders will visit fabricators' shops to ensure they are following quality standards. Doing so will reduce the risk of quality issues onsite. We will implement a document control system to identify and control materials in coordination with the schedule. Submittals will include all shop drawings, samples, certificates, test reports, and technical information required by the Contract. We will require all subcontractors to adhere to the project-specific QA/QC plan developed. Additionally, all suppliers of materials and producers will be part of VDOT's QA/QC program and be on VDOT's pre-approved materials lists. We will notify the Department at least a month in advance of the materials for which the Department retains responsibility for testing. We will receive, handle, and properly store all construction materials and closely monitor them for compliance with contract specifications.

Our approach to QA/QC is to identify the issue immediately, communicate with VDOT, perform additional testing to diagnose the problem, propose potential solutions, select, implement the desired resolution, and apply corrective procedures sure it does not reoccur.





# SECTION 4.5 Construction of the Project

# **4.5** CONSTRUCTION OF THE PROJECT

OUR TEAM WILL PROVIDE DELIVERY CERTAINTY. HOW? BY USING A SIMPLIFIED APPROACH TO CONSTRUCTION SEQUENCING THAT LEVERAGES **EXTENSIVE LOCAL KNOWLEDGE**, ESTABLISHED STAKEHOLDER RELATIONSHIPS, AND A DEDICATION TO SAFETY AND QUALITY. OUR INTEGRATED JV WILL UTILIZE ITS **DIRECT EXPERIENCE IN THE I-81 CORRIDOR** TO DELIVER PROJECT EXCELLENCE.

# **4.5.1 Sequence of Construction**

Construction of the I-81 Project will be a well-coordinated effort to use adequate means and methods to complete all work while ensuring safe and effective traffic flow within the Project corridor. Our approach will deliver Project success through state-of-the-art construction equipment, highly qualified local staff, technical expertise, and I-81 corridor knowledge. The foundation of this success will be adherence to a tailored Project Management Plan (PMP). **Our ability to self-perform approximately 75% of the work provides the control necessary to ensure timely delivery.** Moreover, no construction activity will proceed without assurance that all safety and environmental protection measures have been followed.

## **OVERALL PROJECT MANAGEMENT**

Our Team developed an overall plan for construction through an intimate knowledge of the local area. All key Team members reside in the Project area, and many use the Project corridor in their daily commute. As demonstrated below in EXHIBIT 4.5-1, construction operations are organized logically and systematically into four Project Areas, each containing relatively similar scopes of work and shorter activity durations. This Project Area breakdown provides phasing flexibility and will allow the Team to advance to the next Phase when the previous Phase is completed. We will perform work within each Project Area concurrently to achieve a Final Completion Date of January 15, 2026.

#### **EXHIBIT 4.5-1** | Project Construction Areas

#### AREA 1

NB: STA 111+50 to STA 156+00 SB: STA 511+10 to STA 555+50

#### AREA 2

NB: STA 156+00 to STA 235+00 SB: STA 555+50 to STA 634+50

#### AREA 3

NB: STA 235+00 to STA 309+00 SB: STA 634+50 to STA 708+50

#### AREA 4

NB: STA 309+00 to STA 376+75 SB: STA 708+50 to STA 763+00



## 



Our approach simplifies construction and enhances schedule flexibility to ensure on-time, on-budget delivery of the I-81 Project. Our Conceptual Design has refined MOT processes with fewer construction phases and minimal traffic switches, resulting in fewer accidents and improving driver expectancy. A high-level explanation of critical elements of work for each of the proposed construction activities is provided below.

#### Phase 1 Construction Operations

Phase 1 will include preparatory operations on I-81 NB and SB lanes. The following will take place during this phase:

- Establish centralized staging areas and mobilize.
- Perform right shoulder strengthening throughout the entire Project corridor, both NB and SB as required, to facilitate traffic shift and Phase 2 construction. These activities will be performed at night under temporary lane closures and by progressing through all areas, which efficiently allows for linear progression and repetition of activities.
- Construct stormwater management basins working behind the existing guardrail at wider shoulder areas or from alternate access points. This will ensure that all necessary erosion and sediment control (E&SC) measures are in place prior to any land disturbing activities in later Phases.
- Remove and relocate existing utilities located in the median.
- Establish the required ROW so that necessary adjustments can be secured well in advance of Phase 3 work.
- Lower the existing roadway profile on Route 635 under I-81 to preclude conflicts with schedule restrictions for this work.
- Perform Early Work Packages in areas where there are no utility conflicts or environmental issues. Activities will include maintenance work on the following bridges:

# Area 3: Bridge B682 (Route 705 Bridge over I-81)

- » Installation of embedded galvanic anodes.
- » Concrete substructure surface repair.
- » Concrete surface protection.
- Area 3: Bridge B677 and B678 (I-81 over Route 311)
  - » Installation of embedded galvanic anodes.
  - » Concrete substructure surface repair.
  - » Concrete crack repair (Type B).
  - » Steel crack repairs (welding).
- Area 4: Bridge B681 (Route 419 Bridge over I-81)
  - » Installation of embedded galvanic anodes.
  - » Concrete substructure surface repair.
  - » Concrete surface protection.

- Perform temporary paving before utility relocations take place.
- Establish temporary MOT for switch to Phase 2 (e.g., temporary barrier service, construction signs, temporary pavement markings, among others) within the mainline corridor and shift traffic onto the strengthened shoulder both NB and SB. It is planned for these operations to be performed in a stacked linear progression through all areas to attain greater efficiency, with crews and subcontractors performing repetitive tasks.

#### Phase 2 Construction Operations

Phase 2 will include grading and drainage; construction of new bridge and miscellaneous structures; and roadway widening in the median. The following will take place during this phase:

- Establish construction access to the median through entire Project and set up satellite staging locations for on-site distributions.
- Clear and grub the work area, which will include the demolition or removal of any conflicting existing roadway elements.
- Perform remaining utility coordination and relocations not completed in Phase 1.
- Perform all median grading and drainage and permanent median barrier construction throughout all four Construction Areas to the final proposed roadway and bridge alignments.
- Perform partial demolition and construct temporary shoring and new bridge structures to the median at the following:
  - Area 1: Bridges B683 and B688 (I-81 over Route 112)
    - » Partial superstructure/substructure removal.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven steel piles.
    - » Pier construction on micropiles.
    - » Installation of new structural steel girders.
    - » Construction of new deck, approach slabs, and parapet.
  - Area 2: Bridges B684 and B685 (I-81 over Route 635)
    - » Partial superstructure/substructure removal.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven piles.
    - » Installation of new structural steel girders.
    - » Construction of new deck, approach slabs, and parapet.
  - Area 2: Bridges B686 and B687 (I-81 over Route 619)
    - » Partial superstructure/substructure removal.
    - » Installation of temporary shoring.



- » Construction of MSE walls and abutments on driven piles.
- » Installation of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- Widening to the median of the following existing structures will also be performed in Phase 2:

#### Project Area 3: Bridges B677 and B678 (I-81 over Route 311 NB)

- » Partial removal of the substructure and superstructure.
- » Installation of temporary shoring.
- » Construction of cast-in-place abutments on driven piles.
- » Installation of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- » HES Patching Type B, Type A Hydro-Demolition, and latex overlay.
- Place stone base and pavement structure up to the intermediate asphalt layer throughout, thereby only leaving surface asphalt and permanent pavement markings to be completed in Phase 4.
- Establish temporary MOT for switch to Phase 3 (e.g., temporary barrier service, construction signs, temporary pavement markings, among others) and switch traffic from right shoulder to the median throughout.

# Phase 3 Construction Operations

Phase 3 will include grading and drainage; construction of retaining walls and noise barriers; replacement of bridges; and roadway widening. The following will take place during this phase:

- Clear and grub the work area, which will include demolition or removal of any conflicting existing roadway elements.
- Perform any necessary ramp reconstruction work to include tie-ins with secondary routes at interchanges.
- Perform all right shoulder side grading/drainage and permanent barrier construction throughout building to the final proposed section and structures.
- Install of guardrail and permanent sign structures along the right shoulder.
- Construct all proposed retaining walls.
- Construct sound walls throughout the Project.
- Perform remaining demolition and replacement of the following structures:
  - Area 1: Bridges B683 and B688 (I-81 over Route 112)
    - » Full removal of existing structure.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven steel piles.

- » Pier construction on micropiles.
- » Construction of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- Area 2: Bridges B684 and B685 (I-81 over Route 635)
  - » Full removal of existing structure.
  - » Installation of temporary shoring.
  - » Construction of MSE walls and abutments on driven steel piles.
  - » Construction of new structural steel girders.
  - » Construction of new deck, approach slabs, and parapet.
- Area 2: Bridges B686 and B687 (I-81 over Route 619)
  - » Full removal of existing structure.
  - » Installation of temporary shoring.
  - » Construction of MSE walls and abutments on driven steel piles.
  - » Construction of new structural steel girders.
  - » Construction of new deck, approach slabs, and parapet.
- Perform widening and rehabilitation of the following structures:
  - Area 3: Bridges B677 and B678 (I-81 over Route 311 NB)
    - » Removal and replacement of overhang and parapet.
    - » Construction of new structural steel girders.
    - » Construction of new deck, approach slabs, and parapet.
    - » Backwall and joint reconstruction.
    - » HES Patching Type B, Type A Hydro-Demolition, and latex overlay.
    - » Replacement of existing beam bearings.
- Installation and integration of roadway lighting and ITS.
- Complete reforestation and landscaping throughout the Project.
- Perform staged removal of temporary MOT items in conjunction with Phase 4 activities, including final surface paving and permanent pavement marking installation.

#### Phase 4 Construction Operations

During Phase 4, final paving, pavement markings, and installation of signage will occur. The following will take also place:

- Perform final paving and installation of pavement markings in all Project Areas.
- Install permanent signage in all Project Areas.
- Convert any temporary sediment basins designated to remain as a stormwater management structure to their permanent configuration.
- Switch traffic into its final pattern.

ITEM	SAFETY MEASURE(S) THE BRANCH-ORDERS TEAM WILL TAKE
Pre-Project Safety Planning	<ul> <li>During design, the Safety Manager will incorporate the safety components from the QA/QC checklist when reviewing plans and will consider safety concerns when facilitating constructability reviews and identify potential project safety hazards.</li> <li>A list of action items will be generated to address and make sure that potentially hazardous work activities are safely and rigorously eliminated.</li> </ul>
Training	<ul><li>All employees will undergo safety training for project specific activities.</li><li>Training will include first aid/CPR, trenching and excavation, fall protection, and rigging.</li></ul>
Site Orientation Meeting	<ul><li>A safety orientation will be given to all individuals who visit the Project site.</li><li>Orientations will ensure that all on-site personnel have a clear understanding of safety requirements.</li></ul>
Pre-Task Planning	<ul> <li>The Construction Manager will perform pre-task planning daily and before the start of each new task. Activities will include completion of a Job Hazard Analysis (JHA) form.</li> <li>Activities will ensure that work is accomplished safely, stringent procedures are implemented, and appropriate safety devices and tools are provided.</li> </ul>
Daily Safety Meetings	• Hold daily meetings with all on-site personnel to review the Daily Risk Assessment (DRA). Meetings will address the day's activities (established in the pre-task planning) to address safety concerns.
Site Walks	<ul> <li>Performance of daily site walks by superintendents and foremen to ensure safety compliance.</li> <li>Once a month, the Construction Manager will attend a more formal site walk with the Construction Team. Equipped with a detailed Job Inspection Checklist, the Construction Manager will review on-site safety compliance and evaluate the site for potential safety risks.</li> </ul>
Project-Specific Safety Program (PSP)	<ul> <li>The PSP will recognize and addresses the unique attributes of the I-81 Project, including its environment, traffic conditions, size, and scope to keep the traveling public and stakeholders informed of construction activities and progress.</li> <li>Mandatory project-specific safety orientations will be performed for all workers and site visitors, regardless of affiliation.</li> <li>The PSP comply with Virginia Occupational Safety and Health (VOSH) Standards and will include safety policies, procedures, training programs, worksite controls, and incident response procedures for ensuring the safety and health of workers and the general public.</li> </ul>

#### **EXHIBIT 4.5-2** | Key Elements of the Team's Safety Measures

#### APPROACH TO SAFETY AND OPERATIONS

Our Team will make **safety the top priority each day**. The DBPM and Safety Manager will manage a stringent Safety Program that will empower employees at all levels to stop work anytime an unsafe action takes place. Our Safety Plan will be based on proven and successful plans from recent VDOT projects. The Safety Team, led by Safety Manager, **Danny Minnix**, and supported by Construction Manager, **Bob Cross**, superintendents, the construction JV Safety Team, and all site personnel, will share a common goal: **to maintain a safe site at all times**.

Safety measures our Team will implement for the I-81 Project are highlighted in this section and are summarized above in **EXHIBIT 4.5-2**. We are aware that construction activities on I-81 present extraordinary challenges for safety. With direct knowledge of the I-81 corridor, Branch is currently working on the nearby I-81 MM 141 to 143 Project. Additionally, Orders has a proven track record with numerous bridge replacements in the southwestern I-81 corridor. Lessons learned will be directly applicable to the successful completion of this Project. Site constraints created by working between opposing lanes of traffic requires effective planning for and utilization of equipment resources, optimum access point placement, and a dedicated safety mindset. Mobilizing large equipment into a work zone bounded on two sides by interstate traffic is no small task. The addition of the constraints presented by high traffic volumes and transportation logistics dictates plans that minimize equipment relocation. We will mitigate these risks by effectively sequencing work and utilizing innovative approaches that eliminate exposure.

We will strategically place construction entrances that allow for safe departure and entry into travel lanes. Lag vehicles for large incoming loads are also critical elements in this planning. It is standard for safe bridge access to have access points on the run-off end of a bridge crossing. Doing so ensures that delivery trucks are backing up to the site, which decreases the crane pick radius and precludes hoisting materials over the cab when offloading, thus improving overall safety. When working in constrained circumstances, large material deliveries, such as structural steel, will not be staged onsite and will be sequenced for nighttime delivery then set directly from the offload. Qualified riggers, certified operators, and experienced staff ensure critical operations are completed flawlessly under challenging circumstances. This calm confidence comes from a strong safety culture and greater assurances for the safety of workers and the traveling public.



#### Measuring Safety Performance

Frequent job site inspections are essential to actively measuring safety performance. The Job Inspection Checklist, work plans, Job Hazard Analysis (JHA) forms, and Daily Risk Assessments (DRAs) are proactive ways to track and address safety on-site, incorporate corrective actions, and identify additional tools needed to safely perform the work. By focusing on "doing the right thing," the Safety Leadership Team has taken safety reporting to a new level. Employees know by consistent experience and observation that reporting any safety issue is the right thing to do.

Mr. Minnix will maintain a Safety Statistics Report that tracks safety incidents, including recordable, reportable, and near-miss incidents. He will also track the number of staff hours worked safely to help identify which operations could be improved. He will also lead monthly Safety Leadership Team meetings to evaluate the type, severity, and frequency of safety issues on the I-81 Project and to identify trends as they emerge. This combination of site walks and active safety documentation will enable constant coordination and the opportunity to learn from safety trends. We will track safety metrics so incidents can be one-offs, not the norm. Also, we will review all reported incidents, including near-misses, with field staff to reduce the potential for future incidents.

#### Staging and Storage Areas

Our Team has identified potential staging and storage area options in the I-81 Project corridor. These areas will be located within the construction limits of the Project. Materials will be carefully coordinated with the crews' needs to limit double handling and minimize large storage areas' need. We will give each supplier-specific delivery instructions and directions to mitigate potential impacts on the traveling public and stakeholders. All major hauling activities to and from the I-81 Project site will be performed on primary and interstate roadways and avoid residential areas.

Construction entrances located adjacent to the public road will provide delivery access to the work areas. Our Team will perform activities in a manner that ensures that preexisting conditions are not worsened. We will coordinate all construction entrances to ensure appropriate sight distance is available for safe egress from these access points. The limitations on the workspace presented by the phasing of construction on the I-81 Project will necessitate prioritizing limited on-site storage and the utilization of separate primary staging locations. The majority of material deliveries will be routed first to primary staging locations and then, as needed, distributed to the respective work locations. Doing so will preclude drivers unfamiliar with access points and



We involve our employees in the safety process at every level of the organization. All employees have the right – and the responsibility – to stop work if unsafe practices occur. As a result, we have managed growth in each of our organizations while simultaneously reducing our incidents.

safety protocol from presenting a hazard and keeping the work areas clear of unnecessary obstructions. This centralized Project staging and secondary material distribution approach have proven to be an effective and safer approach for other highly constrained completed projects in the I-81 corridor.

### ANTICIPATING/MITIGATING POTENTIAL DELAYS

Every D-B project presents a unique set of challenges that require additional attention and transparency with stakeholders to minimize schedule risks and impacts on infrastructure users. In this section, potential problems are discussed, along with methods we will use to mitigate the Project Schedule's effects.

#### Coordination with Adjacent Projects

Pursuant to the Part II, Section 1.7 of the RFP, the Team will coordinate all construction activities with the following projects:

- VDOT Projects:
  - » I-81 NBL & SBL, MM 141.8 MM 143.99 (UPC 108906).
  - » Route 311 and Route 419 Intersection (UPC 108904).
  - » I-81 Bridges over Route 311 (UPC 114300)
- City of Salem Project:
  - » West to East Main Street Downtown City of Salem (Project No. 0460-129-249).
- OSPREY Fiber Installation throughout the I-81 Project Corridor.

Our Team will diligently coordinate with contractors of other active construction projects in the vicinity of the I-81 Project throughout design and construction. The DBPM will organize and conduct joint meetings with other contractors quarterly at a minimum or as requested by VDOT. VDOT will also be invited to





these meetings. All progress milestones will be developed and mutually agreed upon by our Team and contractors of nearby projects.

#### Maintaining the Construction Schedule

ROW acquisition and utility relocation are critical activities that influence the start and sequence of our construction schedule. Prioritizing these activities to maintain our proposed construction sequence will be extremely important. As discussed previously, we developed a unique Sequence of Construction that will allow us to schedule construction activities in multiple Areas concurrently. If we encounter a delay in one work Area, resources will be reallocated to another available Area to accelerate construction until resolution.

#### Responding to COVID-19

We are committed to creating a safe work environment for workers and visitors to the I-81 Project site. The introduction of COVID-19 into the daily work routine compounds safety issues on project sites. To ensure safe construction operations, we will implement the JV's COVID-19 Exposure Prevention, Preparedness, and Response Plan (EPPRP), which we will follow throughout the Project's duration. We will vigilantly follow the EPPRP to mitigate the potential of COVID-19 impacts to the Project Schedule. Our Safety Manager will also continuously monitor the Project to ensure compliance with all current government mandates. Methods of providing a safe Project site currently include:

- The DBPM, in coordination with the construction manager and superintendents, will develop risk assessments identifying workplace hazards and job tasks that may present an exposure risk.
- Social distancing, face coverings, and other personal protective equipment (PPE) will be strictly enforced at all times.
- Clean and safe personal workspaces, common areas, and rest facilities at all times.
- COVID-19 training will be provided, facilitated, and documented for all workers.
- Constant evaluation of workplace conditions and recommendations regarding:
  - » PPE or face coverings.
  - » Occupancy of site buildings.
  - » Necessary social distancing.
  - » Installation of physical barriers.
  - » Placement of signs and notices.
- Methods the DBPM, in coordination with the construction manager, superintendents, and the construction JV's corporate safety professionals, will take to address employee concerns or questions about COVID-19.
- Proper PPE and sanitation supplies will always be readily available to all workers and site visitors.

# 4.5.2 Transportation Management Plan

Our Team has the knowledge, understanding, and experience developing Transportation Management Plans (TMPs) involving major interstate and bridge projects that safely and effectively manage both traffic during construction and communications with the stakeholders. This segment of I-81 is a critical transportation link, with an average daily traffic (ADT) volume that exceeds 64,000 vehicles per day (VPD). Volumes are higher during peak travel periods associated with recreational travel and major regional events, significantly associated with Virginia Tech and destinations south of the I-81 Project area.

There are limited alternate routes available, with Route 11/Route 460 through the City of Salem serving as the primary alternate route to I-81 through this area. I-81 is also an essential commercial truck route for the east coast. Providing a safe and efficient work zone for the traveling public will enable our Team to construct the improvements effectively and is critical to the Project's overall success. We will develop a comprehensive TMP, which will have the following three important elements:

- A Temporary Traffic Control Plan (TTCP).
- A Public Information and Communications Plan (PICP).
- An Incident Management Plan (IMP).

The TTCP will be developed following the *Virginia Work Area Protection Manual (VWAPM)*, all applicable VDOT standards, and Part 2 of the RFP. The TTCP will detail the phases of work, impacts to the travel way, haul routes, construction access, and other critical elements necessary to provide a safe and efficient work zone.

#### **KEY CONSIDERATIONS**

The elements of the proposed TMP consider the varied users of the I-81 corridor. Our Conceptual Design accommodates heavy truck traffic, with WB-67 design vehicle turning movements used to establish required clear area during construction operations, as applicable. We understand the critical nature of the I-81 corridor and varying levels of traffic demand. We acknowledge the specific holiday work restrictions in the limitation of operations and the additional critical dates identified in Section 2.10.3 of the RFP. Our Project Schedule accounts for these critical volume periods when existing travel lanes must remain open to traffic.

#### Maintaining Traffic throughout Construction

Our approach to MOT is focused first on safety for the traveling public and workers. As discussed previously

VDOT

in Section 4.5.1, we have divided the corridor into four Project Areas. We developed this sequence of construction activities to ensure that traffic is maintained through the work zone. Elements of our construction phasing are provided behind "TAB 1-C" in Volume II and are discussed in the following narrative.

#### PHASE 1: NB AND SB CONSTRUCTION OPERATIONS

- **Key Elements:** Outside shoulder strengthening, SWM basin construction, utility relocations, bridge maintenance activities.
- **MOT:** Work along I-81 mainline and other facilities will be performed using temporary lane and shoulder closures in accordance with the allowable restrictions with the RFP.
  - » Route 635 Roadway Profile Adjustment (Area of Focus): The profile of Route 635 will be lowered to provide adequate clearance beneath the I-81 bridges crossing over this facility. In accordance with the RFP, a temporary closure and detour of Route 635 is proposed to facilitate this construction. Our plan also recognizes that Route 619 may not be subject to lane closures or short-term closures while Route 635 is temporarily closed and traffic is detoured.

#### PHASE 2: GRADING, DRAINAGE, BRIDGE REPLACEMENTS AND WIDENING IN THE MEDIAN

- Key Elements: After shifting traffic to the newly strengthened outside shoulders, begin work in the median including grading, drainage structures, utility relocations, placement of aggregate base and intermediate asphalt, and initial phase of the bridge reconstruction for the bridges over Route 112, Route 635, and Route 619) and bridge widening of the I-81 structures over Route 311. Additional details regarding our proposed construction sequence for structures is provided in Section 4.3.2.
- **MOT:** Temporary concrete barrier service will be installed along the right side of the I-81 travel lanes while work is progressing to the outside. The required 34' of clear roadway will be maintained, with the exception of bridge locations where there is not adequate room. In those locations, we will exceed the RFP minimum by providing 26' of clear roadway width between barriers. Temporary lane closures will be used when needed in accordance with the allowable hours in the RFP.

#### PHASE 3: GRADING, DRAINAGE, RETAINING WALLS, NOISE BARRIERS, BRIDGE REPLACEMENTS, AND ROADWAY WIDENING

• **Key Elements:** After shifting traffic to the newly constructed median, complete construction of widening and elements to the outside of the existing

roadway. This will include retaining walls and sound walls, the second (and final phase) of bridge reconstruction for the I-81 bridges over Route 112, Route 635, and Route 619) and the widening of the I-81 structures over Route 311. This phase will also include installation of the required lighting and ITS infrastructure within the Project limits and any reforestation and landscaping.

• **MOT:** Temporary concrete barrier service will be installed along the left side of the I-81 travel lanes while work is progressing in the median. We will exceed the RFP required 34' of clear roadway width and provide 12' travel lanes during this phase, with the exception of bridge locations where there is not adequate room. In those locations, we will exceed the RFP minimum by providing 26' of clear roadway width between barriers. Temporary lane closures will be used when needed in accordance with the allowable hours in the RFP.

# PHASE 4: FINAL PAVING, PAVEMENT MARKERS, AND INSTALLATION OF SIGNAGE

- **Key Elements:** Once the major work elements are complete, install any remaining permanent Project signage, perform final paving of the surface course and install final pavement markings, and switch traffic to the final pattern.
- **MOT:** Work under this final phase will be performed using short-term lane closures as permitted in the RFP. In accordance with the RFP, a minimum of 14 days prior to implementation, we will submit to VDOT a work zone traffic impact assessment for all proposed phases of construction. Work zone access points will be designed to allow safe departure and entry into travel lanes.

#### Closures, Detours, and Time of Day Restrictions

Our proposed approach satisfies all RFP requirements. Lane and ramp closures times will comply with Section 2.10.3 of the Technical Requirements analyses. We will submit supporting analysis and documentation to VDOT to request approval for modified lane closure hours. No detours of I-81 mainline traffic are proposed; thus, our phasing plan was developed to maintain two through lanes per direction along I-81.

As previously noted, we propose one long-term detour for the Project to facilitate lowering the roadway profile along Route 635. This will be accomplished within the allowable 60-day period when schools are not in session. Within the time frames allowed in the RFP, short-term ramp closures may be utilized to facilitate the improvements to the I-81 SB off-ramp to Route 112. If proposed detours are necessary, we will prepare a detour plan for VDOT's approval before implementation.



#### Approach to Flagging Operations

Minimal use of flagging is anticipated as part of this Project, and flagging operations will be constrained to the existing two-lane facilities crossing I-81. Flagging will be conducted by certified staff in accordance with the VWAPM, and we will utilize portable temporary rumble strips following VDOT's requirements.

Lanes Widths and Work Zone Speed Reductions

Our proposed approach satisfies RFP requirements in terms of the minimum lane and shoulder widths. We will provide the required minimum clear pavement width, including the required 11' lanes and left and right shoulder widths; our Team will exceed the minimum 24' clear opening requirements in the vicinity of existing bridges.

The work zone will be designed to accommodate the current posted speed limit of 60 MPH within the Project area, with appropriately designed lane shifts and buffer areas.

### MAJOR PROJECT STAKEHOLDERS

The I-81 Project has many important stakeholders, each with concerns and priorities. **EXHIBIT 4.5-4** below includes a compilation of potential construction-related impacts to specific key stakeholders and our plans to eliminate or mitigate the effects. Our comprehensive PICP will manage public opinion, understanding, and support of the Project. Its primary objectives are to:

- Effectively inform, engage, and raise awareness across all interested stakeholders about the Project.
- Reduce impacts of the Project's construction on the residents and traveling public.
- Emphasize work zone safety during construction.
- Minimize potential opposition from the public.
- Acclimate the traveling public with changes in traffic patterns.
- Mitigate or remove potential issues that could affect the I-81 Project's successful delivery.
- Strengthen the Team's credibility.
- Build and sustain public acceptance, trust, and support for the I-81 Project.

ITEM	NATURE OF IMPACT	BRANCH-ORDERS TEAM MITIGATION MEASURES
VDOT	Degraded relationship due to external pressure and complaints from residents and the traveling public.	<ul> <li>Establish clear communication and coordination with VDOT.</li> <li>Comprehensive Incident Management Plan to rapidly respond to incidents in the work zone and minimize impacts to traveling public.</li> </ul>
Roanoke County	Impacts to local residents due to construction.	<ul><li>Clear communication regarding upcoming work activities.</li><li>Ongoing coordination to address Citizen concerns.</li></ul>
Cities of Salem and Roanoke	Impacts to local residents due to construction and diverted traffic due to incidents.	<ul><li>Clear communication regarding upcoming work activities.</li><li>Ongoing coordination to address Citizen concerns.</li></ul>
Utility Companies	Potential loss of service during construction and cost of facility relocations.	<ul> <li>Assign a dedicated Utility Coordinator to manage utility coordination and relocations.</li> <li>Sequence construction operations to allow time for utility relocations.</li> <li>Effective use of Miss Utility and SUE to locate and protect existing utilities.</li> </ul>
First Responders	Closures of roads used for emergency routes. Access of emergency vehicles in construction areas. Impacts to existing crossovers.	<ul> <li>Provide signing before existing crossovers to alert police/EMS to location.</li> <li>Post identification signs for all work zones.</li> <li>Monthly coordination and direct line of communication with the IMC and MOT Manager, including review of upcoming schedule and MOT patterns.</li> </ul>
Local Schools	Noise pollution and traffic disruptions during construction. Safety concerns related to construction traffic.	<ul> <li>Host a kickoff meeting with schools to promote awareness of construction activities.</li> <li>Conduct construction activities without impacting buses and pedestrians.</li> <li>Complete Route 635 detour when schools are not in session to minimize impacts.</li> </ul>
Residential Areas and Neighborhood Associations	Lack of access due to road closures. Noise and dust from construction.	<ul> <li>Host a kickoff meeting so that all neighborhoods to can review the construction schedule and plans.</li> <li>Issue news releases and provide PCMS boards in advance of any new construction activities.</li> <li>Support VDOT as needed with coordination and responses to</li> </ul>
Local Businesses/ Chamber of Commerce	Traffic disruptions due to road closures. Restricted access due to construction activities.	• Coordinate and inform businesses before any road closure(s) may affect them.
Churches, Parks, and Other Community Facilities	Construction-related delays and traffic impacts as well as noise pollution.	<ul> <li>Regular communication of all work activities and road closures.</li> <li>Avoid working on Sundays or days of religious observance(s).</li> </ul>

#### **EXHIBIT 4.5-4** | Stakeholder Communication Methods





The PICP will be developed in compliance with the VDOT Salem District requirements, and will function as a road map for all communications. The success of the Project can be affected by positive public opinion and stakeholder expectations. The development of a comprehensive public outreach program to efficiently educate, raise awareness, minimize impacts, and demonstrate the Project's advantages to key stakeholders would also serve as the cornerstone of the public communications program. A proactive communication plan consisting of a range of integrated communication tools will provide the necessary scope and frequency to positively engage and influence all stakeholders.

**Owen Peery, PE** is our dedicated Public Relations (PR) Manager. In close collaboration with VDOT Salem District Communications, Roanoke County, and the Cities of Roanoke and Salem, Mr. Peery will manage all public relations on the I-81 Project. He will work through VDOT to respond to media and public inquiries, provide VDOT with the Project's status, distribute traffic information to local media outlets, and plan and support the Incident Management Team.

Mr. Peery will supervise the development of graphics and materials including renderings, drawings, and sketches to help the public understand changes in traffic conditions and upcoming events. These materials will be prepared for use at stakeholder meetings as well as the project web site and other multi-media sites. Members of our Team will attend various stakeholder meetings at key points in the construction of the project. We will also provide up-to-date photographs of the Project site for media and web use on a monthly basis, as well as times when key construction events are taking place.

Throughout design and construction, Mr. Peery will provide support for the following activities:

#### Support for Project Website and Social Media



We recognize that VDOT has developed the Improve 81 website to serve as a key point of access for the public seeking information about ongoing and planned improvement projects along the I-81 corridor. Our Team will

support VDOT's development of Project-specific information to support the website, as well as others when needed.

Media Relations and Print/Broadcast Materials



Our Team will assist with media relations. As needed, we will provide feature articles and broadcast interviews on the Project, traffic alerts, safe driving practices, and Project updates as an integral component of the public outreach campaign to educate the public fully. We will also assist in developing brochures, fact sheets, quarterly newsletters, presentations, and multi-media advertisements that convey the benefits of the Project.

Assistance will be provided to VDOT in the distribution of materials via social media outlets, including regular Project updates, notices about significant upcoming traffic pattern changes, and providing updates during incidents. It is also important to notify the public of upcoming and completed Project milestones (e.g., completion of a major structural element or changes in the traffic pattern) to document the success and demonstrate to the public the Project's benefits and that ongoing progress is being made.

#### Assistance with Public Meetings and Hearings



While the Design Public Hearing for the I-81 Project was held on February 9, 2021, our Team anticipates additional public information meetings to be scheduled regularly throughout the Project. These public

informational meetings will provide Project partners, the public, and other stakeholders a platform for sharing Project updates, primary benefits, potential impacts, opinions, and potential concerns.

COVID-19 presents challenges for keeping the public aware of the construction. Our Team is skilled at holding virtual public hearings for projects throughout Virginia. We have supported VDOT with virtual public involvement opportunities, including formal public hearings such as the recent I-395/Boundary Channel Drive and I-81 Exit 313 Virtual Public Hearings. Members of the Team have also supported the Salem District with virtual public engagement for the US 460 STARS Study in the City of Roanoke and Roanoke County. We are adept at preparing recorded meeting presentations and engaging with the public and stakeholders through virtual Q&A sessions. We have seen increased engagement through these means, resulting in hearing a better cross-section of viewpoints on these projects. This increased engagement level will require detailed preparation, including rehearsals for live presentations and technology checks for all staff who will participate.

Our Team will develop a Crisis Communications/Risk Management Response Plan to anticipate and mitigate any potential concern or controversy. This Plan will be particularly critical on a busy corridor such as I-81, where major incidents may require special measures. The PR Manager will take the lead during these periods and work closely with VDOT to provide rapid, accurate information to the public and other stakeholders.



#### PROJECT SITE COMMUNICATIONS

As part of the TTCP, our Team will leverage Portable Changeable Message Signs (PCMSs) approaching and within the Project area to notify the public of upcoming key work activities. This information will supplement the regular updates to VDOT for dissemination through various media and social media channels. PCMS boards will serve as an essential asset during incidents to provide supplemental real-time information to motorists and assist with implementing the specific action items from our IMP.

#### PUBLIC SAFETY APPROACH

Our Team will develop an IMP that will outline plans for responding and managing incidents in the I-81 Project corridor. **We will develop the IMP in collaboration with VDOT, local EMS, and other stakeholders.** The Team will establish procedures about groups to notify in the case of an incident, including police coordination. Elements of our IMP are highlighted to the right in **EXHIBIT 4.5-5**.

Before construction begins in any work zone or lanes are closed, the IMP will be reviewed and approved by VDOT. This plan will consider the type of incident, its estimated duration, identify key members of the Team, and the measures needed to clear the incidents to meet Section 2.10.2 of Part 2 of the RFP. **The IMP will be a living document that will be continuously updated and modified based on the design development, stakeholder feedback, and lessons learned from previous incidents occurring in the Project limits.** It will demonstrate that the Team thoroughly manages all matters relating to incidents within the I-81 Project area.

## MANAGING INCIDENTS IN THE I-81 CORRIDOR

**David C. Scott** is our **Incident Management Coordinator** (IMC) and will direct the response to incidents. Mr. Scott, **a former law enforcement officer for the City of Roanoke**, will leverage his knowledge of the I-81 corridor and relationships with local law enforcement and first responders to coordinate our IMP onsite implementation. He will ensure proper procedures and communication protocols are in place and facilitate communication with local first responders regarding any roadway conditions due to construction activities.

Mr. Scott will be available to respond during construction operations and respond to incidents within the I-81 Project work zone. He will be VDOT's point of contact for incident management and will apply National Incident Management System (NIMS) principles and practices throughout construction. He will designate a weekly time throughout construction operations to meet with stakeholders and review the IMP, anticipated schedule, concerns, and proposed changes.

#### **EXHIBIT 4.5-5** | Incident Management Plan

# **Incident Management Plan Elements**

**Communication Plan Elements:** A 24/7 point-of-contact for emergency notifications of incidents in the I-81 Project corridor. An Agency and Stakeholder Responsibilities Matrix/ Checklist that communicates Project needs and responsibilities. Methods of communication with the VDOT SWRO TOC, as well as all other stakeholders.  $\checkmark$ A plan for communicating with all first responders and stakeholders in the project corridor. A contact list of all appropriate response personnel. **Implementation Plan Elements:** VDOT-approved emergency detour routes, sign layout plans, and TMP signage. Sign layout and signing plans that show all previously staged detour equipment, and materials needs, emergency detour routes, crossovers, and access points. An up-to-date listing of all revisions and updates made to the design plans. Plans that demonstrate areas of access for law enforcement, fire, and rescue services during incidents. A listing of all programmed messages to be shown on the portable DMS boards during incidents. Simulated situational training drills so that Team members are ready to respond to incidents in the I-81 Project corridor. Mr. Scott will coordinate response efforts and will

develop our comprehensive IMP. The IMP will be based on extensive local knowledge of this segment of I-81, and a thorough understanding of the available alternate routes. The IMP will focus on proactive measures to identify and locate incidents rapidly, quickly respond to them, clear those incidents, and implement planned detours in the event of a major incident. The IMP will leverage existing elements that VDOT has invested in along the corridor, including Safety Service Patrol (SSP), CCTV cameras for real-time traffic monitoring, and signal communication upgrades funded along the parallel routes.

We understand that maintaining mobility in the I-81 corridor is one of VDOT's major concerns. **Branch is currently working on the adjacent I-81 MM 141 to MM 143 Project.** This unparalleled experience enables our Team to anticipate the impacts of incidents on I-81, as well what is needed to respond to them accordingly.

#### **TEAM MEMBER HIGHLIGHT: Incident Management Coordinator**

A successful IMC needs to be able to react calmly during emergencies and determining time-sensitive solutions under stress. Our IMC, David C. Scott, is a former law enforcement officer for the City of Roanoke Police Department. In addition to working for the City of Roanoke, Mr. Scott was also a Special Agent for the Virginia ABC Bureau of Law Enforcement. Because of this, he is very familiar with the I-81 corridor and its issues. He has demonstrated experience in traffic management and has been responsible for traffic control in and around the I-81 Project corridor during major traffic incidents, crowd control, significant weather events, natural disasters, crime scenes, and special events. Mr. Scott will report directly to the DBPM, will be on the Project site for the duration of construction operations, and will respond to all incidents within the Project limits. Mr. Scott has all but one (FHWA SHRP2 "TIM" Responder Training) of the training and certifications required by the RFP for this role, as the training is not available until April 2021. This training will be completed before commencement of construction.

#### TRAINING AND CERTIFICATIONS:

- FEMA ICS/NIMS 100, 200 & 700 (2021)
- FEMA/VDEM Hazardous Materials Awareness (2021)
- Department of Mineral Mining (2016)
- American Red Cross First Aid/CPR/AED Instructor (2018)

When responding to incidents, Mr. Scott will coordinate with wrecker services to ensure rapid response times to incident sites to quickly move disabled vehicles from the roadway. Response activities may include the temporary relocation of a car to the shoulder to allow traffic flow to commence immediately and then schedule a specific time to remove the vehicle from the I-81 Project site entirely. Emergency crossovers will be maintained, where practical, to allow law enforcement and other first responders to reach incident sites rapidly. Methods of communication between Mr. Scott and involved parties are highlighted to the right in **EXHIBIT 4.5-6**.

#### **EMERGENCY PULL-OFFS**

Emergency pull-offs will be provided, where practical, within the work zone to allow motorists to exit the traffic stream in an incident safely. These designated locations will satisfy the RFP requirements for 15' of clear width on a stable surface. Doing so will also provide areas for wrecker services to remove vehicles and law enforcement to perform post-incident activities.

#### DETOURS AND ALTERNATE ROUTES

While our approach does not require detours for I-81 traffic, we recognize that a plan must be in place to move traffic if a major incident occurs within the work zone. As such, the IMP will include detailed, actionable plans for implementing detours from I-81 to the available alternate routes. These will build off the existing SWRO Freeway Traffic Management Incident Detour Plans from VDOT. However, our Team will work with VDOT to refine those plans for incident management via Exits 132, 137, 140, 141, and 143 (via I-581 and Peters Creek Road).

# • EPRO Aerial Life, Scissor Lift Instructor (2012)

- DCJS Defensive Driving Instructor (2011)
- DCJS Academic Instructor (2005)
- Mounted Patrol Certification (2004)
- US Marshall Special Deputy



As demonstrated in **EXHIBIT 4.5-7** on page 52, the primary alternate route through this segment is US 11/US 460. Depending on the location and type of incident, a detour could pass through three different jurisdictions: Roanoke County, City of Salem, and the City of Roanoke, with traffic signals maintained by VDOT and the two cities. Therefore, development of a detailed incident plan will be critical. We will assign specific responsibilities to each entity and the IMC will lead the implementation of the plan during incidents.









#### **EXHIBIT 4.5-7** | Detours and Alternate Routes



- **Route 11/460 (City of Salem)** Capacity along Route 11/Route 460
  - Closely-spaced signals
- B Route 311
  - Route 311/Route 419 Roundabout Project
  - · Two-lane facility
- C Peters Creek Road (City of Roanoke)
  - · Good route with four lanes, but limited number of signals
  - Route 419
  - Good route with four lanes, but limited number of signals

- 4<sup>th</sup> Street/Texas Street (City of Salem)
   Limited capacity
  - Difficult access to Route 419 for trucks
- F Avoid Downtown Salem
  - Limited capacity
  - High pedestrian activityNot appropriate for trucks
  - Desite 211 (C'the of Colored)
- **G** Route 311 (City of Salem)
  - Challenging section in the heart of Salem
  - Good route north of Route 11/Route 460

## MOTORIST INFORMATION

A vital element of the IMP will be integrating it with the overall PICP for the I-81 Project to ensure that motorists receive timely, accurate information while traveling through the construction zone. It is also essential to ensure that information is available in advance so motorists can prepare to use other needs when needed. The IMP will utilize the PCMS boards on the Project site to provide updated information to motorists while also leveraging existing VDOT Dynamic Message Signs along the I-81 corridor. Programmed message packages for different incident scenarios will be developed for deployment by VDOT's TOC.

# **COORDINATION EFFORTS**

Regular coordination will be critical to the success of the IMP. We recognize that incident management for this Project cannot exist in a vacuum – it will require input from VDOT, local governments, and other key stakeholders. Regular partnering meetings will be held to collaborate on the plan, review the plan, and modify it as needed. Activities will include "after-action" meetings to discuss lessons learned and apply those to future actions. Our Team will coordinate with VDOT to understand ongoing projects along the I-81 corridor and ensure that our plan is consistent with nearby projects. These include, but are not limited to,





the proposed project between MM 144 and 150, which is anticipated to begin construction when the I-81 Project is underway. Major incidents from one project have the potential for impacting another. We will work with VDOT to a proactive plan to effectively and efficiently handle any issue that may occur.

# EFFORTS DURING DESIGN TO AVOID/MINIMIZE POTENTIAL SAFETY IMPACTS

Our Conceptual Design for the I-81 Project uses an integrated approach that includes the Team and VDOT. While the Design Team will use the FHWA's Manual on Uniform Traffic Control Devices (MUTCD) and the Virginia Work Area Protection Manual (VWAPM) in the development of the TTCP, there could be variables related to means and methods of construction that may require additional considerations in the design of the TTCP. Including the Construction Team in the early identification of these variables through the constructability review process and the weekly Technical Work Group meetings will allow the Design Team to incorporate and manage safety and mitigate undesirable conditions before finalizing the plans. By doing so, our Team will greatly improve the work zone's safety for construction personnel and the traveling public.

Of particular importance will be identifying locations for safe construction access to the median work area. Identifying safe locations to complete the Project efficiently will involve efforts from both Design and Construction Team members.

#### EFFORTS DURING CONSTRUCTION TO AVOID/ MINIMIZE POTENTIAL SAFETY IMPACTS

Our Team considers the safety of its employees and the general public to be a matter of prime importance. We will involve operations staff with their construction counterparts during the design process so that constructability and safety procedures go hand-in-hand with the design and Project Schedule development. Simultaneously, similar collaboration, coordination, and planning meetings amongst Design and Construction Team members and VDOT will also occur in the development of various portions of the Team's Final Design (e.g., TMP, PICP, among others). In all parts of this Design, we will establish procedures to carry out safety standards, such as ongoing police patrol, first responder, and incident response factors.

Collaboration between stakeholders will also be an essential aspect of developing safe and effective management plans; as previously noted, our IMP and IMC are fundamentals of this collaborative approach to overall safety along the Project corridor. Working in high traffic volumes with a high percentage of trucks involves many factors that need to be planned with stakeholders' and workers' safety in mind. Our Team will proactively address possible hazards before they occur and will never compromise production and cost savings safety.

Because of mandatory VA 811 notifications, underground utilities will be similarly dealt with by identifying, labeling, and securing them to avoid hazardous situations, such as impacts to an unknown utility. Maintaining an impeccable safety record on the I-81 Project will be the primary objective for our Team. At the end of each day, we will ensure workers return home to their families.

We recognize the challenges of working within this segment of the I-81 corridor. Based on publicly available data, there were 565 crashes within the Project area during the preceding five years, plus numerous other incidents (including disabled vehicles, road debris, among others). The accidents occurred without the presence of a long-term work zone and the additional challenges that motorists encounter in this environment. We are prepared to rise to the challenge and ensure that the traveling public safety traverses the Project work zone day in and day out.

Our Team mandates that the most stringent safety guidelines are established and provide proven safety leadership, always starting at the organization's highest levels to attain zero incidents. During design, safety will be the primary driver in the development of the TTCP. During construction, we will emphasize public safety and reinforce travel expectations through work zones regularly to the appropriate audience. As motorists enter the work zone, the signs and markings will provide clear and easily understood guidance as they travel the I-81 Project alignment.

Our experience in the area guided the development of our TMP and MOT Plan to ensure congestion is reduced, allowing continuous and safe travel through the work zone. Our plan satisfies VDOTs requirements to provide a minimum 34' of clear pavement width (except for bridge structures). This width offers room for potential emergency stopping and additional buffer space for drivers to recover if they make a mistake. If incidents occur, we will perform after-action reviews and apply lessons to enhance safety further. Actions may include adjustments to the TTCP to reduce the risk of an incident or adjustments to the IMP to respond better when they do occur. Our approach to public safety will be proactive, starting from day one, and responsive to changing conditions and experience gained working within Project site.



SECTION 4.6 Proposal Schedule

÷

Sec.

Ş

11

mp

Lucz

1 11





# **4.6 PROPOSAL SCHEDULE**

The Branch-Orders Team reviewed the schedule requirements in the RFP and prepared a Proposal Schedule and Proposal Narrative that demonstrates our understanding of the complexities and challenges of this critical Project.

# 4.6.1 Proposal Schedule

The Proposal Schedule utilizes Primavera P6 software and Critical Path Method (CPM) scheduling to depict the scope and sequence of work to design and construct the Project per the RFP requirements. The schedule narrative is included in *Section 4.6.2* below, and the CPM Proposal Schedule is provided behind "**TAB 3**" in Volume II of our Technical Proposal. Per the RFP requirement, our Team has provided PDF copies of the Proposal Schedule and Narrative, as well as a back-up copy of the Proposal Schedule's source document in electronic file format.

# 4.6.2 Proposal Schedule Narrative

Our Team developed the following Proposal Schedule narrative for the overall plan to execute the work. The narrative includes overall sequencing of the Project, the Critical Path, our strategy to ensure successful delivery of the I-81 Project on time and within budget, and other key assumptions on which the Proposal Schedule is based. The narrative also explains how our Team optimizes the benefits of the D-B delivery method to mitigate known risks, conform to MOT requirements, and minimize construction impacts on the public.

## **OVERALL SEQUENCE OF WORK**

Our Proposal Schedule evaluates the Project in a total of three stages:

- 1. DESIGN, UTILITIES, AND RIGHT-OF-WAY (ROW) ACQUISITIONS: The objectives of this stage is to complete all preliminary and final design for the I-81 Project, resolve all utility conflicts, and perform ROW acquisitions.
- 2. **PERMITTING:** The objective of this stage is obtain all environmental permits from applicable agencies (e.g., DEQ, USACE, VMRC).
- **3. CONSTRUCTION:** The objective of this stage is to construct the entire I-81 Project. Activities include the VDOT inspection and acceptance of work, system testing, punchlist, and closeout of the I-81 Project.

## **CRITICAL MILESTONES**

Our Team is committed to a **Final Completion Date of January 15, 2026**. **EXHIBIT 4.6-1** above identifies key procurement dates, which will require coordination between our Team and VDOT and other reviewing **EXHIBIT 4.6-1** | Key Schedule Milestones

MILESTONE	DATE
Technical Proposal Submission	03/03/2021
Price Proposal Submission	03/30/2021
Opening of Price Proposal	03/30/2021
CTB Approval	04/21/2021
D-B Contract Execution	05/21/2021
Notice to Proceed	05/24/2021
Scope Validation Period	05/24/2021 to 09/20/2021
Start of Construction	09/23/2021
Final Completion	01/15/2026

agencies, including, but not limited to, Roanoke County, the City of Salem, and FHWA. Post-award, we will implement an assertive D-B approach, local experience, and relationships to potentially improve these dates.

## WORK BREAKDOWN STRUCTURE (WBS)

The WBS is a multi-level, hierarchical arrangement of the work performed on the I-81 Project. Our Team has laid out the WBS to breakdown the major work Areas of the I-81 Project by element and type of work.

Work has been broken down by Construction Areas, and respective components, including Schedule Milestones, Project Management, Scope Validation, Environmental/Permitting, ROW, Design, Utility Relocation/Coordination, and Construction. WBS areas for the I-81 Project were developed as a collaborative effort between the Design and Construction Teams by evaluating the components as a single project, including type of work along the alignments design considerations, and management of the construction efforts. Below is an outline of our WBS Structure, and a detailed breakdown is presented in **EXHIBIT 4.6-2** on page PS-2.

#### Administration

This section of the Proposal Schedule contains the Health, Safety, and Welfare Plan, as well as the Utility Relocation Plan, ROW Acquisition, and Project Schedule.





# **EXHIBIT 4.6-2** | Work Breakdown Structure

WBS CODE	WBS NAME					
C00116203DB108	I-81 WIDENING MM 136.6 - MM 141.8 PROPOSAL SCHEDULE					
C00116203DB108.1	MILESTONES					
C00116203DB108.4	<b>DESIGN ACTIVITIES</b>					
C00116203DB108.4.20	QA/QC Plan					
C00116203DB108.4.15	Survey					
C00116203DB108.4.16	Geotechnical					
C00116203DB108.4.17	Environmental Permits					
C00116203DB108.4.18	Utility Relocation/Coordination					
C00116203DB108.4.24	Bridge Maintenance and Repair Plans					
C00116203DB108.4.25	Bridge Design					
C00116203DB108.4.19	Shoulder Strengthening Work Package					
C00116203DB108.4.26	MOT, Grading, Drainage, E&SC/SWM, Water, Sewer, and ROW Work Package					
C00116203DB108.4.27	ROW Acquisition					
C00116203DB108.4.1	Noise Barriers					
C00116203DB108.4.22	Final Design					
C00116203DB108.4.21	Pavement Markings/Signage Plans					
C00116203DB108.2	PRELIMINARY ACTIVITIES					
C00116203DB108.3	CONSTRUCTION ACTIVITIES					
C00116203DB108.3.1	Phase 1					
C00116203DB108.3.1.1	I-81 Northbound					
C00116203DB108.3.1.1.1	Area 1					
C00116203DB108.3.1.1.2	Area 2					
C00116203DB108.3.1.1.2.3	Route 635 Roadway Reconstruction					
C00116203DB108.3.1.1.3	Area 3					
C00116203DB108.3.1.1.3.1	I-81 over Route 311 Bridge					
C00116203DB108.3.1.1.3.2	Route 705 over I-81 Bridge					
C00116203DB108.3.1.1.4	Area 4					
C00116203DB108.3.1.1.4.1	Route 419 over I-81 Bridge					
C00116203DB108.3.1.2	I-81 Southbound					
C00116203DB108.3.1.2.1	Area 4					
C00116203DB108.3.1.2.1.1	Route 419 over I-81 Bridge					
C00116203DB108.3.1.2.2	Area 3					
C00116203DB108.3.1.2.2.1	I-81 Over Route 311 Bridge					
C00116203DB108.3.1.2.2.2	Route 705 over I-81 Bridge					
C00116203DB108.3.1.2.3	Area 2					
C00116203DB108.3.1.2.4	Area 1					
00116203DB108.3.2	Phase 2					
C00116203DB108.3.2.5	I-81 Northbound					
C00116203DB108.3.2.5.1	Area 1					
C00116203DB108.3.2.5.1.1	I-81 over Route 112 Bridge					
C00116203DB108.3.2.5.2	Area 2					
C00116203DB108.3.2.5.2.1	I-81 over Route 635 Bridge					
C00116203DB108.3.2.5.2.2	I-81 over Route 619 Bridge					





# **EXHIBIT 4.6-2** | Work Breakdown Structure (*continued*)

WBS CODE	WBS NAME
C00116203DB108.3.2.5.3	Area 3
C00116203DB108.3.2.5.3.1	I-81 over Route 311 Bridge
C00116203DB108.3.2.5.4	Area 4
C00116203DB108.3.2.1	I-81 Southbound
C00116203DB108.3.2.1.4	Area 1
C00116203DB108.3.2.1.4.1	I-81 over Route 112 Bridge
C00116203DB108.3.2.1.3	Area 2
C00116203DB108.3.2.1.3.1	I-81 over Route 619 Bridge
C00116203DB108.3.2.1.3.2	I-81 over Route 635 Bridge
C00116203DB108.3.2.1.2	Area 3
C00116203DB108.3.2.1.2.1	I-81 over Route 311 Bridge
C00116203DB108.3.2.1.1	Area 4
C00116203DB108.3.3	Phase 3
C00116203DB108.3.3.1	I-81 Northbound
C00116203DB108.3.3.1.1	Area 1
C00116203DB108.3.3.1.1.1	I-81 over Route 112 Bridge
C00116203DB108.3.3.1.2	Area 2
C00116203DB108.3.3.1.2.1	I-81 over Route 635 Bridge
C00116203DB108.3.3.1.2.2	I-81 over Route 619 Bridge
C00116203DB108.3.3.1.3	Area 3
C00116203DB108.3.3.1.3.1	I-81 over Route 311 Bridge
C00116203DB108.3.3.1.4	Area 4
C00116203DB108.3.3.5	I-81 Southbound
C00116203DB108.3.3.5.1	Area 4
C00116203DB108.3.3.5.2	Area 3
C00116203DB108.3.3.5.2.1	I-81 over Route 311 Bridge
C00116203DB108.3.3.5.3	Area 2
C00116203DB108.3.3.5.3.1	I-81 over Route 619 Bridge
C00116203DB108.3.3.5.3.2	I-81 over Route 635 Bridge
C00116203DB108.3.3.5.4	Area 1
C00116203DB108.3.3.5.4.1	I-81 over Route 112 Bridge
C00116203DB108.3.4	Phase 4
C00116203DB108.3.4.1	I-81 Northbound
C00116203DB108.3.4.1.1	Area 1
C00116203DB108.3.4.1.2	Area 2
C00116203DB108.3.4.1.3	Area 3
C00116203DB108.3.4.1.4	Area 4
C00116203DB108.3.4.2	I-81 Southbound
C00116203DB108.3.4.2.1	Area 4
C00116203DB108.3.4.2.2	Area 3
C00116203DB108.3.4.2.3	Area 2
C00116203DB108.3.4.2.4	Area 1
C00116203DB108.5	Completion Activities

#### **SECTION 4.6 | PROPOSAL SCHEDULE** Technical Proposal, Volume I | I-81 Widening MM 136.6 to MM 141.8 Design-Build



This section of the Proposal Schedule includes the QA/QC plan and design milestones for surveying; geotechnical engineering; scope validation; environmental permitting; utility relocation and coordination; bridge, retaining wall, and sound wall design; ROW acquisitions; maintenance of traffic (MOT); grading; clearing and erosion and sediment control (E&SC) work package; lighting/sign/striping design; intelligent transportation systems (ITS); and roadway design. Submittal milestones and approvals by VDOT and governing agencies are included.

#### Design – Right-of-Way

This section of the Proposal Schedule outlines and monitors the acquisition of ROW and easements, including title searches, appraisals and reviews, offers, negotiations, settlements, and filing certificates of take (COT) when needed. Prioritized groupings of properties are included on the second level WBS. These groups will enable our Team to focus efforts on the most critical acquisitions and will provide the ability to track these acquisitions to ensure on-time completions.

#### Design – Environmental

This section of the Proposal Schedule includes wetland and stream delineations, jurisdictional determinations, permit management and preparation, mitigation, permit submission, Phase I and II Environmental Site Assessments (ESAs) (as required), and reviews from authorities that have jurisdiction.

#### Utility Relocations

This section includes activities for Utility Field Inspection (UFI) meetings, completion of relocation designs, approval of relocation designs, and construction of the utility relocations. Utility relocations are separated into a second level WBS structure based on the utility owner and construction Work Area.

#### Construction

This section include all roadway, bridge, ITS, lighting, signage, retaining walls, noise barriers, and drainage construction components and includes project management. *Activity durations account for QA/QC inspections/testing, and hold/witness points.* This portion of the Proposal Schedule is segmented into additional WBS structure levels to divide the construction activities into Areas that can be easily managed and tracked to ensure a timely Final Completion.

#### WORK CALENDARS

The following calendars were used in the development of our Proposal Schedule to represent a variety of scenarios:

- **Calendar 1 | Five-Day Work Week with Holidays:** Based on five working days per week, all design, administrative, and construction activities are used except those impacted by adverse weather and holiday restrictions.
- Calendar 2 | Calendar Days: Will be assigned to activities that have durations based on seven days per week without any holidays or adverse weather. This calendar will be used for review periods, fabrications, and milestones.
- Calendar 3 | Five-Day Work Week with Adverse Weather: Will be used for construction activities that are anticipated to be affected due to adverse weather condition. The local average range of precipitation and cold weather data was considered while assuming this information.

For weather analysis, our Team has reviewed the weather data provided by the NOAA observation center located in Blacksburg, Virginia. **EXHIBIT 4.6-3** depicts the number of weather days, by respective months, that our Proposal Schedule considers for inclement weather. We will observe all holidays listed in Part 5, Section 108.02 (Limitation of Operations) in the *VDOT 2020 Road and Bridge Specifications*. In addition, we will observe the following work restrictions listed in the RFP:

- Virginia Tech Graduation
- Virginia Tech Move-in Days
- Radford University Graduation
- Virginia Tech Home Football Games
- Radford University Graduation
- Radford University Move-in Days
- Salem Fair
- Olde Salem Days
- Roanoke College Graduation

#### **OVERALL PLAN AND STRATEGY**

Our Team will develop a comprehensive plan to complete the I-81 Project in a timely and professional manner. Our goal is to minimize the number of construction phases, traffic pattern changes, and interruptions to the traveling public. We will coordinate MOT staging for smooth transitions between the bridge and roadway construction operations.



MONTH & NUMBER OF ANTICIPATED		F	М	А	М	J	J	Α	S	0	N	D
MONTH & NUMBER OF ANTICIPATED WEATHER DELAYS	8	8	7	6	6	4	2	2	2	3	5	8







Our Team will strategically divide design and construction into four geographic Construction Areas. This will allow the I-81 Project to geographically align the design packages with Project segments and streamlines the design-to-construction process. Our segmentation of the I-81 Project allows the design for each Construction Area to be developed concurrently with minimal schedule dependency on the other Areas and a high level of coordination between each. Design packages for each Construction Area will be submitted for VDOT review in accordance with the RFP requirements and Approved for Construction (AFC) design completion stage, ensuring comprehensive VDOT oversight while maintaining design progress.

The Proposal Schedule incorporates all phases of design including preparation, design QA/QC reviews, and submission of roadway, ROW, drainage, storm-water management, E&SC, MOT, signing, pavement marking, signal, lighting, ITS, and bridge plans at multiple stages of the design process including a 21-calendar day activities for VDOT review/approval with each submission.

The design phase also includes activities for completion of surveys, utility designations, noise studies, utility relocations, the Scope Validation Period, and geotechnical investigations. We will begin the design immediately pursuant to Notice to Proceed (NTP) to secure an early start on roadway and bridge plans, temporary traffic control, and the ROW acquisition.

#### Environmental and Permitting

Identifying recognized environmental conditions/areas of concern early in the design process facilitates the timely issuance of environmental permits. Additionally, consistent communication within our Team and resource agencies helps mitigate risk to the I-81 Project Schedule.

Our approach during design includes the following elements. Upon receipt of a Notice to Proceed (NTP), our Team will refine environmental resource locations in the I-81 Project corridor based on the Conceptual Design. We will conduct fieldwork and technical services as necessary. They may include wetland delineation reconfirmation, stream assessments, threatened and endangered (T&E) species reviews, environmentally sensitive areas (ESAs), asbestos inspections on structures, and a final noise analysis that will be utilized for permitting and environmental compliance monitoring. If our refinement identifies unanticipated or unknown resources, the Conceptual Design will be modified to support avoidance and/or minimization opportunities. Our Team will coordinate with the appropriate resource agency(ies) to ensure resource protection if any new resources are identified. We will also review the environmental commitments included in the RFP, the



#### ADHERING TO CULTURAL RESOURCE COMMITMENTS

Because our Conceptual Design is entirely within the RFP Design's footprint, the previously concluded Section 106 effect determination of No Effect, determined on July 28, 2020, should remain valid. Per the RFP, our Team will consider the three identified historic properties along the project limits to be design constraints and will avoid impacting them beyond what is included in the RFP Design. These properties include the Virginia Baptist Children's Home/Hope Tree, Hanging Rock Battlefield, and Freeman Cemetery. We will avoid any other Project-related activities on or within the viewshed of the three historic properties identified in the RFP, including but not limited to staging, borrow/disposal, and any temporary or permanent easements. We understand that any changes beyond the RFP Design may require additional cultural resources studies or coordination with the Virginia State Historic Preservation Office (SHPO).

#### **PROTECTION OF T&E SPECIES**

Our Team has reviewed the T&E species studies and coordination conducted by VDOT. The preliminary T&E Species Clearance Form dated August 21, 2020, identified two species that the Project would have no effect: the Roanoke logperch and orangefin madtom. This Form stated that the proposed Project may affect, but is not likely to adversely affect, the Indiana bat and northern long-eared bat. However, VDOT's June 2020 acoustic survey for T&E bats did not detect the presence of Indiana bat or northern long-eared bat. Additionally, the survey report concluded that a time-of-year restriction for tree cutting will not be required for the Project as long as all tree cutting occurs during the five-year time frame the survey is valid.

Per the RFP, no bridge bat inventories will be required within the five-year time frame the acoustic survey is valid. Upon receipt of an NTP, our Team will continue coordination with natural resource and regulatory agencies to ensure compliance with species protections.

#### SECURE WATER QUALITY PERMITS

Our Team refined the RFP Design to avoid and minimize impacts to streams. The RFP Design resulted in impacts to 0.31 acres (AC) of wetlands and 1,120 LF feet of streams. **Our Conceptual Design was refined to avoid impacts to 25 LF of streams through headwall modification.** This modification also eliminates floodplain impacts for the Project. As the design advances following the receipt of an NTP, we will look for additional ways to improve our Conceptual Design to avoid and further reduce impacts.





The Project will require authorization under a Virginia Water Protection General Permit 3 (up to 1,500 LF and 2 acres of wetlands) and an Individual Permit from the US Army Corps of Engineers (USACE). If impacts can be reduced to less than 0.5 acres of wetlands and 1,000 LF of streams, the Project would be authorized under a Nationwide Permit 23 for approved Categorical Exclusions. The Project will cross four named streams: Horners Branch, Dry Creek, Gish Branch, and Mason Creek. Mason Creek has a drainage area greater than 5 square miles; therefore, a Virginia Marine Resources Commission (VMRC) permit will be necessary.

#### ROW Acquisitions

ROW activities are critical to the success of the I-81 Project and the schedule. Our Proposal Schedule details the acquisition process for the ROW including title research, appraisals, offers, and negotiations. Except for permanent utility easements (yet to be identified) and possible temporary construction easements, our Team proposes the Project alignment will be contained within the ROW limits shown on the RFP Plans. To that extent, we will advance the ROW acquisition in accordance with the guidelines established by VDOT and other Commonwealth and federal guidelines.

The ROW activities shown on the Proposal Schedule mirror the process provided by the guidelines. Preliminary activities such as title exams, preliminary appraisals and preliminary reports can begin before VDOT's NTP for ROW acquisition. Once VDOT's NTP for ROW is received, durations and interaction times are tightly controlled by the Guidelines which require notice durations, minimum response times, and VDOT review and payment processing durations. The ROW and Utilities Management System (RUMS) reporting system is updated throughout the duration of the entire Project.

#### Utilities

Sections 4.3.1 and 4.4.2 lists a portion of anticipated utility relocations and potential conflicts for the Project. The utility companies that have been identified as having facilities in the Project area are: Appalachian Power; Citizen's Telephone; Comcast; Roanoke Gas; Salem City Electric; Salem City Water and Sewer; Segra; Verizon; Western Virginia Water and Sewer; and Zayo Communications. Additionally, Osprey Fiber has agreements with VDOT for future fiber installation in the project area. Mitigation strategies to ensure the timely relocation of the facilities found to be in conflict will start with a consistent communication with the utility contacts to remind them of their schedule commitments and to ensure that they have their preliminary steps underway to complete the work. A detailed Utility Matrix is provided behind "TAB 2" of Volume



# Overall Construction of the Project

Our Team developed an overall plan for construction through an intimate knowledge of the local area. All key Team members reside in the Project area, and many use the Project corridor in their daily com**mute.** As demonstrated in **EXHIBIT 4.6-4** on page PS-7, construction operations are organized logically and systematically into four Project Areas, each containing relatively similar scopes of work and shorter activity durations. This Project Area breakdown provides phasing flexibility and will allow the Team to advance to the next Phase when the previous Phase is completed. We will perform work within each Project Area concurrently to achieve a Final Completion Date of January 15, 2026. Our approach simplifies construction and enhances schedule flexibility to ensure on-time, on-budget delivery of the I-81 Project. Our Conceptual Design has refined MOT processes with fewer construction phases and minimal traffic switches, resulting in fewer accidents and improving driver expectancy. A high-level explanation of critical elements of work for each of the proposed construction activities is provided below.

#### Phase 1 Construction Operations

Phase 1 will include preparatory operations on I-81 NB and SB lanes. The following will occur during this phase:

- Establish centralized staging areas and mobilize.
- Perform right shoulder strengthening throughout the entire Project corridor, both NB and SB as required, to facilitate traffic shift and Phase 2 construction. These activities will be performed at night under temporary lane closures and by progressing through all areas, which efficiently allows for linear progression and repetition of activities.
- Construct stormwater management basins working behind the existing guardrail at wider shoulder areas or from alternate access points. This will ensure that all necessary erosion and sediment control (E&SC) measures are in place prior to any land disturbing activities in later Phases.
- Remove and relocate existing utilities located in the median.
- Establish the required ROW so that necessary adjustments can be secured well in advance of Phase 3 work.
- Lower the existing roadway profile on Route 635 under I-81 to preclude conflicts with schedule restrictions for this work.
- Perform Early Work Packages in areas where there are no utility conflicts or environmental issues. Activities will include maintenance work on the following bridges:



#### • EXHIBIT 4.6-4 | Project Areas Map



- Area 3: Bridge B682 (Route 705 Bridge over I-81)
  - » Installation of embedded galvanic anodes.
  - » Concrete substructure surface repair.
  - » Concrete surface protection.
- Area 3: Bridge B677 and B678 (I-81 over Route 311)
  - » Installation of embedded galvanic anodes.
  - » Concrete substructure surface repair.
  - » Concrete crack repair (Type B).
  - » Steel crack repairs (welding).
- Area 4: Bridge B681 (Route 419 Bridge over I-81)
  - » Installation of embedded galvanic anodes.
  - » Concrete substructure surface repair.
  - » Concrete surface protection.
- Perform temporary paving before utility relocations take place.
- Establish temporary MOT for switch to Phase 2 (e.g., temporary barrier service, construction signs, temporary pavement markings, among others) within the mainline corridor and shift traffic onto the strengthened shoulder both NB and SB. It is planned for these operations to be performed in a stacked linear progression through all areas to attain greater efficiency, with crews and subcontractors performing repetitive tasks.

#### Phase 2 Construction Operations

Phase 2 will include grading and drainage; construction of new bridge and miscellaneous structures; and roadway widening in the median. The following will take place during this phase:

- Establish construction access to the median through entire Project and set up satellite staging locations for on-site distributions.
- Clear and grub the work area, which will include the demolition or removal of any conflicting existing roadway elements.
- Perform remaining utility coordination and relocations not completed in Phase 1.
- Perform all median grading and drainage and permanent median barrier construction throughout all four Construction Areas to the final proposed roadway and bridge alignments.
- Perform partial demolition and construct temporary shoring and new bridge structures to the median at the following:
  - Area 1: Bridges B683 and B688 (I-81 over Route 112)
    - » Partial superstructure/substructure removal.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven steel piles.
    - » Pier construction on micropiles.

Technical Proposal, Volume I | I-81 Widening MM 136.6 to MM 141.8 Design-Build



- » Installation of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- Area 2: Bridges B684 and B685 (I-81 over Route 635)
  - » Partial superstructure/substructure removal.
  - » Installation of temporary shoring.
  - » Construction of MSE walls and abutments on driven piles.
  - » Installation of new structural steel girders.
  - » Construction of new deck, approach slabs, and parapet.
- Area 2: Bridges B686 and B687 (I-81 over Route 619)
  - » Partial superstructure/substructure removal.
  - » Installation of temporary shoring.
  - » Construction of MSE walls and abutments on driven piles.
  - » Installation of new structural steel girders.
  - » Construction of new deck, approach slabs, and parapet.
- Widening to the median of the following existing structures will also be performed in Phase 2:

#### Project Area 3: Bridges B677 and B678 (I-81 over Route 311 NB)

- » Partial removal of the substructure and superstructure.
- » Installation of temporary shoring.
- » Construction of cast-in-place abutments on driven piles.
- » Installation of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- » HES Patching Type B, Type A Hydro-Demolition, and latex overlay.
- Place stone base and pavement structure up to the intermediate asphalt layer throughout, thereby only leaving surface asphalt and permanent pavement markings to be completed in Phase 4.
- Establish temporary MOT for switch to Phase 3 (e.g., temporary barrier service, construction signs, temporary pavement markings, among others) and switch traffic from right shoulder to the median throughout.

# Phase 3 Construction Operations

Phase 3 will include grading and drainage; construction of retaining walls and noise barriers; replacement of bridges; and roadway widening. The following will take place during this phase:

- Clear and grub the work area, which will include demolition or removal of any conflicting existing roadway elements.
- Perform any necessary ramp reconstruction work to include tie-ins with secondary routes at interchanges.
- Perform all right shoulder side grading/drainage and permanent barrier construction throughout building

#### to the final proposed section and structures.

- Install of guardrail and permanent sign structures along the right shoulder.
- Construct all proposed retaining walls.
- Construct sound walls throughout the Project.
- Perform remaining demolition and replacement of the following structures:
  - Area 1: Bridges B683 and B688 (I-81 over Route 112)
    - » Full removal of existing structure.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven steel piles.
    - » Pier construction on micropiles.
    - » Construction of new structural steel girders.
    - » Construction of new deck, approach slabs, and parapet.
  - Area 2: Bridges B684 and B685 (I-81 over Route 635)
    - » Full removal of existing structure.
    - » Installation of temporary shoring.
    - » Construction of MSE walls and abutments on driven steel piles.
    - » Construction of new structural steel girders.
    - » Construction of new deck, approach slabs, and parapet.

#### Area 2: Bridges B686 and B687 (I-81 over Route 619)

- » Full removal of existing structure.
- » Installation of temporary shoring.
- » Construction of MSE walls and abutments on driven steel piles.
- » Construction of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- Perform widening and rehabilitation of the following structures:

#### Area 3: Bridges B677 and B678 (I-81 over Route 311 NB)

- » Removal and replacement of overhang and parapet.
- » Construction of new structural steel girders.
- » Construction of new deck, approach slabs, and parapet.
- » Backwall and joint reconstruction.
- » HES Patching Type B, Type A Hydro-Demolition, and latex overlay.
- » Replacement of existing beam bearings.
- Installation and integration of roadway lighting and ITS.
- Complete reforestation and landscaping throughout the Project.
- Perform staged removal of temporary MOT items in conjunction with Phase 4 activities, including final surface paving and permanent pavement marking installation.



#### Phase 4 Construction Operations

During Phase 4, final paving, pavement markings, and installation of signage will occur. The following will take also place:

- Perform final paving and installation of pavement markings in all Project Areas.
- Install permanent signage in all Project Areas.
- Convert any temporary sediment basins designated to remain as a stormwater management structure to their permanent configuration.
- Switch traffic into its final pattern.

### **CRITICAL PATH**

As demonstrated in **EXHIBIT 4.6-5**, which begins on page PS-10, we have identified a clear critical path while developing the proposal schedule. The critical path highlights the importance of early coordination and continued communication with utility owners to expedite necessary relocations. Our Team's detailed Proposal Schedule is also included behind "**TAB 3**" in Volume II.

- Critical activities will be identified during the design stage and allocate necessary resources before assigning resources to non-critical activities.
- Critical activities will be highlighted and communicated to all Project stakeholders and regulatory authorities during any design review and approval process. We will also address comments as promptly as possible.
- The Construction QA/QC Team will play a part in critical path management by making timely decisions related to critical activities.
- The Team will apply lessons learned to make sure critical activities are completed early or on schedule.
- The schedule and progress of each critical and near critical activity will be monitored throughout the duration of the Project.

# **KEY ASSUMPTIONS**

In addition to the calendars and weather days, our Team made the following key assumptions, on which the Proposal Schedule is based:

- **Partnering and Coordination:** Effective partnering and coordination efforts between the Team, VDOT, Roanoke County, the City of Salem, and all other stakeholders.
- **Submittal Review Time:** Our Team will make timely and complete plan submittals to VDOT. All dates provided in our Proposal Schedule are reliant on prompt reviews by VDOT.
- Weather Impacts: Our Team used weather data provided by the NOAA Station in Blacksburg, Virginia to estimate the weather impact throughout

the year. This data will provide a reliable estimate for standard weather impact.

- Utility Relocations: Utility companies will schedule relocation efforts based on the Proposal Schedule.
- Activity Durations: All durations are based on an eight-hour workday and five-day workweek.

# SCHEDULE MANAGEMENT AND MITIGATION OF DELAY RISK

Effective management and control of a project requires a properly managed scheduling program, documentation control, cost control, and an integrated design-to-construction process.

Our Team developed the Proposal Schedule following the requirements of the RFP. We will use Primavera P6 (P6) scheduling software to plan, schedule, and monitor the I-81 Project. The Project Schedule will be developed, maintained, and updated by the Project Scheduler. The Project Scheduler, supported by the Construction Manager and DBPM, is ultimately responsible for managing the Project Schedule.

Upon receipt of an NTP, our Team will collaborate with VDOT to develop a detailed Baseline Schedule using the Conceptual Design plans. Following an internal analysis and review of the general schedule logic and Critical Path, the baseline schedule will be submitted for approval. The Project Controls Team will generate the Baseline Schedule document, as required, for submission to VDOT.

When changes or unforeseen circumstances arise that impact the Project Schedule, we will notify VDOT (and other appropriate stakeholders) and begin incorporating changes into the "live" CPM schedule. If any changes result in schedule slippage, the DBPM will evaluate the issue to determine if additional manpower, equipment, multiple shifts, a change in subcontractor, or other subcontractors are required. If so, the necessary resources will be mobilized to correct the slippage and maintain the Project Schedule. The Project Schedule will be clearly communicated to all involved parties throughout the duration of the I-81 Project. **EXHIBIT 4.6-5** | Overview Project Schedule

		Original	Start	Finish	03-01
		Duration	Otart		
81 Widening MM	136.6 - MM 141.8 Proposal Schedule	949	03-03-21	01-15-26	▼ 01-15-26, I-81 Widening MM 136.6 - MM 141.8 Pr
MILESTONES		1780	03-03-21	01-15-26	v ∮1-15-26, MILLESTONE\$
M20	MILESTONE: TECHNICAL PROPOSAL DUE	0	03-03-21		MILESTONE: TECHNICAL PROPOSAL DUE. 03-03-21
M40	MILESTONE: ANTICIPATED NTP	0	05-24-21		♦ MILESTONE: ANTICIPATED NTP. 05-24-21
M70	MILESTONE: CONTRACT COMPLETION (01/15/2026)	0		01-15-26*	♦ MILESTONE: CONTRACT COMPLETION (01/15/2)
DESIGN ACTIVIT	TIES	199	05-24-21	06-01-22	▼ 06-01-22, DESIGN/ACTIVITIES
QA/QC Plan		0			
Survey		0			
Geotechnical		0			
Environmental Per	mits	0			
Utility Relocation/C	Coordination	0			
Bridge Maintenand	ce and Repair Plans	0			
Bridge Design		0			
Shoulder Strength	ening Work Package	0			
MOT, Grading, Dra	inage, ESC/SWM, Water, Sewer and ROW Work Package	76	05-24-21	09-09-21	09-09-21, MOT, Grading, Drainage, ESC/SWM, Water, Sewerland ROW Work Package
🔲 D1950	Design of MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW	65	05-24-21	08-24-21	🛑 Design of MOT, Grading, Drainage, ESC/SWN, Water, Sewer and ROW
<b>D1960</b>	QA/QC Review of MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans	10	08-25-21	09-08-21	QA/QC Review of MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans
🔲 D1970	Prepare MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans for Submission	1	09-09-21	09-09-21	I Prepare MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans for Submission
🛓 Right of Way Acqu	isition	132	09-10-21	06-01-22	v v 06-01-22, Right of Way Acquisition
D2030	R/W Authroization, Appraisals/BARS	60	09-10-21	11-08-21	R/W Authroization, Appraisals/BARS
<b>D2040</b>	Independent Appraisal Review	20	11-09-21	12-07-21	Independent Appraisal Review
<b>D</b> 2050	Submit Appraisal/BARS Package to VDOT	2	12-08-21	12-09-21	I Submit Appraisal/BARS Package to VDOT
D2060	VDOT Review	21	12-10-21	12-30-21	VDOT Review
D2070	Negotiations	30	12-30-21	02-14-22	Negotiations
D2080	Final Negotiations Submission	30	02-14-22	03-29-22	Final Negotiations Submission
<b>D</b> 2090	VDOT Review and Funding	21	03-30-22	04-19-22	VDOT Review and Funding
D2100	Closing/Condemnation	30	04-19-22	06-01-22	Closing/Condemnation
Noise Walls		0			
Final Design		0			
Pavement Marking	s/Signage Plans	0			
PRELIMINARY A	CTIVITIES	0			
CONSTRUCTION	ACTIVITIES	695	05-11-22	11-14-25	▼ 11+14+25, CONSTRUCTION ACTIVITIES
PHASE 1		24	05-11-22	06-24-22	₩ 06-24-22, PHASE 1
I-81 NB		14	05-11-22	06-06-22	₩ 06-06-22, I-81 NB
AREA 1		5	05-11-22	05-20-22	▼ 05-20-22, AREA 1
<b>1880</b>	Svvivi Basin (147+50 - 149+50) (I-81 NB) (Area 1) (Phase 1)	5	05-11-22	05-20-22	■ SWM Basin (14/+50 - 149+50) (I-81 NB) (Area 1) (Phase 1)
AREA 2	SWM Basin (161+00 - 165+00) (L81 NB) (Area 2) (Phase 1)	9	05-23-22	06-06-22	₩ U6-U6-22, AKEA 2
	SWM Basin (101700 - 103700) (101100 (1182 1) SWM Basin (Sta 182±00 - 188±00) (1.81 NR) (Δrea 2) (Dhasa 1)	3	05-23-22	05-25-22	I = SWM Rasin (Sta 182±00 - 188±00) (rol NB) (Alea 2) (Filase 1)
<b>DTE 625 P</b>		0	03-27-22	00-00-22	
AREA 3		0			
AREA 4		0			
		10	06-07-22	06-24-22	▼ 06-24-22, I-81 SB
AREA 4		0			
AREA 3		0			
AREA 2	914/14 Depin (Oro E74:00, E70:75) // 04 OD) /A 0) /DL 4)	7	06-07-22	06-20-22	▼ 06-20-22, AREA 2
2275	SWW Basin (Sta. 5/4+00 - 5/6+/5) (I-81 SB) (Area 2) (Phase 1)	3	06-07-22	06-13-22	I SVVM Basin (Sta. 5/4+00 - 5/6+/3) (I+81 (SB) (Area;2) (Phase 1)
2285	Svvivi Basin (Sta. 599+00 - 602+50) (I-81 SB) (Area 2) (Phase 1)	4	06-14-22	06-20-22	► SWIN BASIN (Sta. 599+00 - 602+50) (I-81 (SB) (Area 2) (Phase 1)
AREA 1	SWM Basin (527±00 - 530±00) (L81 SB) (Area 1) (Phase 1)	3	06-21-22	06-24-22	VUD-24-22, AREA T;     SW/M Basin (527±00), 530±00)/(L81 \$B) (Area 1) (Dhase 1)
	(Alea 1) (Filase 1)	217	06-27-22	02-01-24	
FIASE 2		517	50 21-22	02-01-24	



# **EXHIBIT 4.6-5** | Overview Project Schedule

6203DB108		I-81 Widening MM 136.6 - MM 141.8	Proposal Schedu	le							03
D	Activity Name	Original Start	Finish	2021 2022	2023	2024	2025	2026	2027	2028	2029
		Duration									
I-81 NB		106 06-27-22	12-19-22		12-19-22, I	81 NB					
	Install Temperaty Congrete Parties // 81 NP) (Area1) (Phase 2)	62 U0-27-22 8 06 27 22	10-04-22		U-U4-22, ARE	A T Cobordto Por					
2330		00-27-22	07-00-22						nase z)		
2340	Grading/Excavation (I-81 NB) (Area1) (Phase 2)	10 07-01-22	07-19-22		ling/Excavati	on (I-81 INB) (	Area I) (Prha	se Z)			
2350	Install Storm Drainage (I-81 NB) (Area1) (Phase 2)	19 07-12-22	08-11-22		all Storm Dra	ainage (I-81 N	3) (Area1) (I	hase 2)			
2360	Install Median Barrier (I-81 NB) (Area1) (Phase 2)	9 08-08-22	08-19-22	Inst	tall Median E	arrier (I-81 NE	) (Area1) (P	hase 2)			
2370	Install Aggregate Base Course (I-81 NB) (Area1) (Phase 2)	14 08-12-22	09-01-22	Inst	tal Aggregat	e Base Cours	e (I¦-81 NB) (	Area1) (Pha	ase 2)		
2380	Install Asphalt Base Course (I-81 NB) (Area1) (Phase 2)	11 08-24-22	09-08-22	I Ins	stall Asphalt E	Base Course (	-81 NB) (Are	ea1) (Phase	∋ 2)		
2390	Install Asphalt Intermediate Course (I-81 NB) (Area1) (Phase 2)	3 09-09-22	09-13-22	l Ins	stall Asphalt I	ntermediate (	Course (I-81	NB) (Area1	) (Phase 2)		
<b>2400</b>	Install Guardrail (I-81 NB) (Area1) (Phase 2)	6 09-12-22	09-20-22	l Ins	stall Guardra	il (I-81 NB) (Ai	ea1) (Phase	2)			
<b>2410</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area1) (Phase 2)	7 09-21-22	09-30-22	l Re	emove Temp	orary Concret	e Barrier (I-8	31 NB) (Area	a1) (Phase 2	)	
<b>2420</b>	Establish Temp. MOT/Shift Traffic (I-81 NB) (Area1) (Phase 2)	2 10-03-22	10-04-22	) 巨	stablish Tem	p. MOT/Shift	raffic (I-81 I	VB) (Area1)	(Phase 2)		
I-81 OVER RT	TE. 112 BRIDGE	0									
Farea 2		44 10-06-22	12-19-22	E E E E E E <b>F</b>	12-19-22, A	REA 2					
2590	Install Temporary Concrete Barrier (I-81 NB) (Area 2) (Phase 2)	5 10-06-22	10-13-22	) in	nstall Tempor	ary Concrete	Barrier (I-81	NB) (Area 2	2) (Phase 2)		
<b>2600</b>	Grading/Excavation (I-81 NB) (Area 2) (Phase 2)	18 10-11-22	11-07-22		Grading/Exca	avation (I-81 N	B) (Area 2)	(Phase 2)			
<b>2610</b>	Install Storm Drainage (I-81 NB) (Area 2) (Phase 2)	36 10-19-22	12-19-22		Install Storr	n Drainage (I-	31 NB) (Area	a 2) (Phase	2)		
I-81 OVER RT	TE. 635 BRIDGE	0									
I-81 OVER RT	TE. 619 BRIDGE	0									
AREA 3		0									
AREA 4		0									
I-81 SB		211 12-20-22	02-01-24			02-01-24,	I-81 SB				
AREA 1		0									
AREA 2		79 12-20-22	06-08-23	Y	06-08	3-23, AREA 2					
3585	Install Storm Drainage (I-81 SB) (Area 2) (Phase 2)	37 12-20-22	03-17-23		Install S	torm Drainage	(I-81 SB) (/	Area 2) (Pha	ase 2)		
3595	Install Median Barrier (I-81 SB) (Area 2) (Phase 2)	16 02-24-23	03-27-23		Install M	ledian Barrier	(I-81 SB) (A	rea 2) (Pha	se 2)		
3605	Install Aggregate Base Course (I-81 SB) (Area 2) (Phase 2)	25 03-03-23	04-21-23		Install /	Aggregate Ba	se Course (I	-81 \$B)¦(Are	ea 2) (Phase	2)	
<b>a</b> 3615	Install Asphalt Base Course (I-81 SB) (Area 2) (Phase 2)	20 03-17-23	04-25-23		nstall /	Asphalt Base	Course (I-81	SB) (Area	2) (Phase 2)		
<b>a</b> 3625	Install Asphalt Intermediate Course (I-81 SB) (Area 2) (Phase 2)	6 04-27-23	05-05-23		I Install	Asphalt Interr	nediate Cou	rse (I-81 SE	3) (Area 2) (P	hase 2)	
<b>—</b> 3635	Install Guardrail (I-81 SB) (Area 2) (Phase 2)	15 04-28-23	05-25-23		lnstal	Guardrail (I-8	1 SB) (Area	2) (Phase 2	2)		
3645	Remove Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 2)	4 05-26-23	06-02-23		Remo	ve Temporar	/ Conorete E	Barrier (I+81	SB) (Area 2)	(Phase 2)	
<b>a</b> 3655	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 2) (Phase 2)	3 06-05-23	06-08-23		Estat	olish Temp. M	OT/Shift Tra	ffic (I-81 SB	s) (Area 2) (P	nase 2)	
I-81 OVER RT	TE. 619 BRIDGE	0									
I-81 OVER RT	TE. 635 BRIDGE	0									
AREA 3		76 06-09-23	10-10-23			10-10-23, ARE	A 3				
<b>—</b> 3465	Install Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 2)	5 06-09-23	06-16-23		l Insta	Il Temporary (	Concrete Ba	mer (I-81 SI	B) (Area 3) (F	hase 2)	
3475	Grading/Excavation (I-81 SB) (Area 3) (Phase 2)	17 06-15-23	07-13-23		📕 Gra	ding/Excavati	on (I-81 SB)	(Area 3) (P	hase 2)		
3485	Install Storm Drainage (I-81 SB) (Area 3) (Phase 2)	38 06-23-23	08-22-23		📕 Ins	tall Storm Dra	inage (I-81	SB) (Area 3	3) (Phase 2)		
<b>a</b> 3495	Install Median Barrier (I-81 SB) (Area 3) (Phase 2)	15 08-03-23	08-25-23		In:	stall Median E	arrier (I-81 S	SB) (Area 3)	(Phase 2)		
3505	Install Aggregate Base Course (I-81 SB) (Area 3) (Phase 2)	24 08-10-23	09-15-23		📕 In	stall Aggrega	e Base Cou	rse (I-81 SE	3) (Área 3) (F	hase 2)	
3515	Install Asphalt Base Course (I-81 SB) (Area 3) (Phase 2)	19 08-21-23	09-19-23		Ir	istall Asphalt I	Base Course	(I-81 SB) (	Area 3) (Pha	se 2)	
3525	Install Asphalt Intermediate Course (I-81 SB) (Area 3) (Phase 2)	6 09-20-23	09-28-23			nstall Asphalt	ntermediate	Course (I-	81 SB) (Area	3) (Phase 2)	
3535	Install Guardrail (I-81 SB) (Area 3) (Phase 2)	5 09-21-23	09-28-23			stall Guardra	I (I+81 SB) (	Area 3) (Ph	ase 2)		
3545	Remove Temporary Concrete Barrier (I-R1 SR) (Area 3) (Phase 2)	4 00-20-23	10-05-23				orary Concr	ete Barrier (	(1-81 SR) (Are	a 3) (Phace ?	
	Establish Temp, MOT/Shift Traffic (1.91 SD) (Area 3) (Phase 2)	+ UJ723723 2 40.06.02	10-10-22			tetablish tom	MOT/Chi	t Traffic /I o		A U LIASE Z	
<u> </u>		3 10-06-23	10-10-23			-əlanıları iem		с нашс (I-8	, SD) (Alea	or (Filase 4)	
			02.01.24			02 01 04					
		5 10 12 22	10-10-22			nstall Tempo		Barrier /I		(Phase 0)	
	Install Temporary Concrete Partier (1.81 SP) (Area 4) (Phase 2)		10-19-23			nistan tempo			SHIPLICK AND	$-\gamma$ (r (lase 2)	
AREA 4	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2)	5 10-12-25	11 02 02		- i i i <b>-</b> -	Cradin'a /	votion // dt	CD) 14-1-	1) (Dhob- 2)		
AREA 4	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2) Grading/Excavation (I-81 SB) (Area 4) (Phase 2)	12 10-17-23	11-03-23			Grading/Exca	vation (I-81	SB) (Area 4	4) (Phase 2)		
AREA 4 3245 3255 3265 3265	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2) Grading/Excavation (I-81 SB) (Area 4) (Phase 2) Install Storm Drainage (I-81 SB) (Area 4) (Phase 2)	10-17-23 10-17-23 16 10-25-23	11-03-23 11-20-23			Grading/Exca Install Storm	vation (I-81 Drainage (I-	SB) (Area 4 81 SB) (Are	4) (Phase 2) ea 4) (Phase	2)	
AREA 4 3245 3255 3265 3275	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2) Grading/Excavation (I-81 SB) (Area 4) (Phase 2) Install Storm Drainage (I-81 SB) (Area 4) (Phase 2) Install Median Barrier (I-81 SB) (Area 4) (Phase 2)	10-12-23           12           10-17-23           16           10-25-23           11           11-07-23	11-03-23 11-20-23 11-28-23			Grading/Exca Install Storm Install Media	vation (I-81 Drainage (I- n Barrier (I-8	SB) (Area 4 81 SB) (Are 31 SB) (Area	4) (Phase 2) a 4) (Phase a 4) (Phase 2	2) 2)	
Image: Participan state	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2)         Grading/Excavation (I-81 SB) (Area 4) (Phase 2)         Install Storm Drainage (I-81 SB) (Area 4) (Phase 2)         Install Median Barrier (I-81 SB) (Area 4) (Phase 2)         Install Aggregate Base Course (I-81 SB) (Area 4) (Phase 2)	10-12-23         12         10-17-23         16         10-25-23         11         11-07-23         18         11-14-23	11-03-23         11-20-23         11-28-23         12-15-23			Grading/Exca Install Storm Install Media Install Aggre	vation (I-81 Drainage (I- n Barrier (I-8 gate Base (	SB) (Area 4 81 SB) (Are 31 SB) (Area Course (I-81	4) (Phase 2) a 4) (Phase 2 a 4) (Phase 2 t SB) (Area 4	2) 2) ) (Phase 2)	





# **EXHIBIT 4.6-5** | Overview Project Schedule

C00116203DB108	ŀ	-81 Widening MM 136	6.6 - MM 141.	8 Proposal Sched	lule				03-01-21 10:46
Activity ID	Activity Name	Origina	I Start	Finish	20	21	2	022	2023 2024 2025 2026 2027 2028 2029 2030
		Duration	1		Q	QQ	QQC	QQQ	
3295	Install Asphalt Base Course (I-81 SB) (Area 4) (Phase 2)	15	5 11-29-23	01-02-24					Install Asphalt Base Course (I-81 SB) (Area 4) (Phase 2)
3305	Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 2)	Ę	5 01-03-24	01-15-24					Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 2)
3315	Install Guardrail (I-81 SB) (Area 4) (Phase 2)	6	6 01-08-24	01-17-24					I Install Guardrail (I-81 SB) (Area 4) (Phase 2)
3325	Remove Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2)	2	1 01-22-24	01-29-24					Remove Temporary Concrete Barrier (I-81 \$B) (Area 4) (Phase 2)
3335	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 4) (Phase 2)	3	8 01-30-24	02-01-24					I Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 4) (Phase 2)
PHASE 3		222	2 02-05-24	04-04-25					V-04-04-25, PHASE 3
I-81 NB		(	)						
I-81 SB		222	2 02-05-24	04-04-25					V 04-04-25, I-81 SB
	Install Temporary Constrate Derrice (I.94, SD) (Area, 4) (Phase, 2)	62	02-05-24	06-11-24					V Ub-11-24, AREA 4
5515	Creding/Every writing (L94 SP) (Area 4) (Phase 3)	5	02-05-24	02-13-24					I Install temporary Concrete Barner (1-51 SB) (Area 4) (Phase 3)
5525	Grading/Excavation (1-o1 SD) (Area 4) (Phase 3)		02-06-24	02-20-24	_				Glauing/cxcavation (I-o1 SD) (Alea 4) (Phase 3)
5535	Install Storm Drainage (I-81 SB) (Area 4) (Phase 3)	30	02-15-24	04-29-24	_				Install Storm Drainage (I-81 SB) (Area 4) (Phase 3)
	Install Aggregate Base Course (I-81 SB) (Area 4) (Phase 3)	10	03-29-24	05-02-24					■ Install Aggregate Base Course (1-81 SB) (Area 4) (Phase 3)
	Install Asphalt Base Course (I-81 SB) (Area 4) (Phase 3)	18	05-03-24	05-31-24					■ Instali Asphait Base Course (1-8) SB) (Area 4) (Phase 3)
5585	Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 3)		06-03-24	06-10-24					I Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 3)
5595	Install Guardrail (I-81 SB) (Area 4) (Phase 3)	Ę	06-04-24	06-11-24					Install Guardrail (I-81 SB) (Area 4) (Phase 3)
		89	06-13-24	10-31-24					10-31-24, AREA 3
5625	Install Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 3)		06-13-24	06-20-24					I Install lemporary Concrete Barrier (I-81 SB) (Area 3) (Phase 3)
5635	Grading/Excavation (I-81 SB) (Area 3) (Phase 3)	Į.	06-18-24	07-02-24					Grading/Excavation (I-81 SB) (Area 3) (Phase 3)
5665	Install Median Barrier (I-81 SB) (Area 3) (Phase 3)	5	5 09-05-24	09-12-24					I Install Median Barrier (I-81 SB) (Area 3) (Phase 3)
5675	Install Aggregate Base Course (I-81 SB) (Area 3) (Phase 3)	24	1 09-13-24	10-18-24					Install Aggregate Base Course (I-81 SB) (Area 3) (Phase 3)
5685	Install Asphalt Base Course (I-81 SB) (Area 3) (Phase 3)	19	09-24-24	10-22-24					Install Asphalt Base Course (I-81 SB); (Area 3) (Phase 3)
5695	Install Asphalt Intermediate Course (I-81 SB) (Area 3) (Phase 3)	6	6 10-24-24	10-31-24					I Install Asphalt Intermediate Course (I-81 SB) (Area 3) (Phase 3)
5705	Install Guardrail (I-81 SB) (Area 3) (Phase 3)	5	5 10-25-24	10-31-24					I Install Guardrail (I-81 SB) (Area 3) (Phase 3)
5715	Construct Retaining Wall (Sta. 660+50 - 664+50) (I-81 SB) (Area 3) (Phase 3)	15	5 07-03-24	07-26-24					Construct Retaining Wall (Sta. 660+50 - 664+50) (J-81 SB) (Area 3) (Phase 3)
5735	Construct Retaining Wall (Sta. 669+25 - 670+00) (I-81 SB) (Area 3) (Phase 3)	Ę	5 07-29-24	08-02-24					I Construct Retaining Wall (Sta. 669+25 - 670+00) (I-81 SB) (Area 3) (Phase 3)
5745	Construct Retaining Wall (Sta. 691+00 - 701+50) (I-81 SB) (Area 3) (Phase 3)	20	08-05-24	09-04-24					Construct Retaining Wall (Sta. 691+00)- 701+50) (I-81 \$B) (Area 3) (Phase 3)
I-81 OVER RTE.	. 311 BRIDGE	(	)						
AREA 2		69	9 11-01-24	04-04-25					04-04-25, AREA 2
5755	Install Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 3)	5	5 11-01-24	11-11-24					I ¦Install Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 3)
5765	Grading/Excavation (I-81 SB) (Area 2) (Phase 3)	ę	9 11-08-24	11-26-24					Grading/Excavation (I-81 SB) (Area 2) (Phase 3)
<u> </u>	Install Storm Drainage (I-81 SB) (Area 2) (Phase 3)	50	) 11-14-24	03-10-25					Install Storm Drainage (I-81 SB):(Area 2) (Phase 3)
5805	Install Aggregate Base Course (I-81 SB) (Area 2) (Phase 3)	25	5 01-23-25	03-21-25					Install Aggregate Base Course (I-81 SB) (Area 2) (Phase 3)
<b>—</b> 5815	Install Asphalt Base Course (I-81 SB) (Area 2) (Phase 3)	20	02-10-25	03-25-25					Install Asphalt Base Course (I-81 SB) (Area 2) (Phase 3)
5825	Install Asphalt Intermediate Course (I-81 SB) (Area 2) (Phase 3)	6	6 03-27-25	04-04-25					Install Asphalt Intermediate Course (I-B1 SB) (Area 2) (Phase 3)
<b>—</b> 5835	Install Guardrail (I-81 SB) (Area 2) (Phase 3)	Ę	5 03-28-25	04-04-25					Instáll Guardrail (I-81 SB) (Area 2) (Phase 3)
I-81 OVER RTE.	. 619 BRIDGE	(	)						
I-81 OVER RTE.	. 635 BRIDGE	(	)						
AREA 1		(							
PHASE 4		132	04-07-25	11-14-25					
		81	04-07-25	08-26-25	-				■ 06-04-20-20, I-81 NB
	Remove Temporany Concrete Barrier (I-81 NB) (Area 1) (Phase 4)		1 04-07-25	04-18-25					Remove Temporary Concrete Barrier (1-81 NB) (Area 1) (Phase 4)
	Install Asphalt Surface Course (L81 NB) (Area 1) (Phase 4)		04-07-20	04-25-25					Install Asnhalt Sulface Course/(L81 NB) (Area 1) (Phase 4)
5200	Install Permanent Payament Markings/Signage (J. 81 NR) (Area 1) (Phase 4)		04 10 20	05.01.25	_				Install Pomonont Povomont Martings/Signage (L.S.1, NP) (Area 1) (Phase
	Install Fernanent Favenient Markings Signage (For ND) (Alea T) (Friase 4)	20	05 02 25	06 17 25					
AREA 2	Remove Temporary Concrete Barrier (I-81 NR) (Area 2) (Phase 4)	13	3 05-02-25	05-29-25					■ Remove Temporary Concrete Barrier (I-81 NR) (Area 2) (Phase 4)
5220	Install Ashhalt Suiface Course (I-R1 NR) (Area 2) (Phase 4)	10	3 05-10-25	06-10-25					<ul> <li>Ingtall Adobalt Surface Cource (LS1'NR) (Alrea 2) (Deace A)</li> </ul>
5230	Install Permanent Pavement Markings/Signage (I-81 NR) (Area 2) (Phase 4)	10	) 06-02-25	06-17-25					Install Permanent Pavement Markings/Signage /L&1 MR) (Area 2) (Pha
			06-10-25	07-24-25					<ul> <li>Ποιαίτι επιτατείτι τα νετιτείτι ματαλιτίζου οι μια το ματά τ Επιστρισμοτο ματά το ματά τ</li></ul>
AREA 3	Remove Temporary Concrete Barrier (I-81 NR) (Area 3) (Phase 4)	12	06-19-25	07-08-25					Remove Temporary Concrete Barrier /I-R1 NR) (Area 3) (Phase /I)
5250	Install Asphalt Surface Course (I-R1 NR) (Area 3) (Phase 4)	12	2 06-30-25	07-18-25					■ Install Asnhalt Sulfade Course /L&1 NR) (Area 3) (Phase /)
			- 00 00 20	07 10 20			<u> </u>		
Actual Level of Effort	Remaining Work    Milestone	F	Page 3 of 4						Branch-Orders Joint Venture
Actual Work	Critical Remaining Work V		-						




### **EXHIBIT 4.6-5** | Overview Project Schedule

C00116203DB108			I-81 Widening MM 136.6 - MM 141.8 Proposal Schedule										03-	01-21 10:46		
ctivity ID		Activity Name		Original Start Fin		Finish	2021	2022	2023	2024	2025	2026	2027	2028	2029	2030
	<b>5</b> 260	Install Permanent Pavement Markings/Signage (I-81 NB) (Area	3) (Phase 4)	10	07-10-25	07-24-25					Inst	all Permanent	Pavement M	arkings/Signa	age (I-81 N	B) (Area 3) (Ph
	AREA 4			21	07-25-25	08-26-25					<b>W</b> 08	-26-25, AREA	4			
	<b>5270</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area 4) (Phase 4	4)	11	07-25-25	08-11-25					Re	nove Tempora	iry Concrete E	Barrier (I-81 N	IB) (Area 4)	) (Phase 4)
	<b>5280</b>	Install Asphalt Surface Course (I-81 NB) (Area 4) (Phase 4)		11	08-04-25	08-20-25					Ins	tall Asphalt Su	rface Course	(I-81 NB) (Ar	ea 4) (Phas	se 4)
	<b>=</b> 5290	Install Permanent Pavement Markings/Signage (I-81 NB) (Area	4) (Phase 4)	9	08-14-25	08-26-25					📕 Ins	stall Permanen	t Pavement N	larkings/Sig	nage ( <b> </b> -81	age (I-81 NB) (Area 4) (P
	- I-81 SB			51	08-27-25	11-14-25						11-14-25, I-81	SB			
	AREA 4			9	08-27-25	09-10-25					<b>W</b> 09	9-10-25, AREA	4			
	<b>=</b> 5300	Remove Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 4	4)	9	08-27-25	09-10-25					R R	emove Tempo	ary Concrete	Barrier (I+81	SB) (Area 4	4) (Phase 4)
	AREA 3			12	09-11-25	09-29-25					🗰 0	9-29-25, ARE/	3			
	<b>=</b> 5330	Remove Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 4	4)	12	09-11-25	09-29-25					E F	emovę Tempo	rary Concrete	Barrier (1-81	SB) (Årea	3) (Phase 4)
	AREA 2			22	09-30-25	10-31-25					•	10-31-25, ARE	A 2			
	<b>=</b> 5360	Remove Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 4	4)	13	09-30-25	10-20-25					<b>I</b> I	Remove Temp	orary Concret	e Barrier (I-8	1 SB) (Area	2) (Phase 4)
	<b>5</b> 370	Install Asphalt Surface Course (I-81 SB) (Area 2) (Phase 4)		13	10-09-25	10-28-25						Install Asphalt	Surface Cour	se (I-81 SB)	(Area 2) (Pl	hase 4)
	5380	Install Permanent Pavement Markings/Signage (I-81 SB) (Area	2) (Phase 4)	10	10-20-25	10-31-25					1	Install Perman	ent Pavemen	t Markings/S	ignage (I-8	1 SB) (Area 2)
	AREA 1			8	11-03-25	11-14-25						11+14+25, ARI	A1			
	<b>=</b> 5410	Install Permanent Pavement Markings/Signage (I-81 SB) (Area	1) (Phase 4)	8	11-03-25	11-14-25					1	Install Permar	ent Pavemei	nt Markings/	Signage (I-8	31 SB) (Area 1
<b>F</b> (	COMPLETION A	CTIVITIES		62	11-15-25	01-15-26					•	🗸 01-15-26, C	OMPLETION	ACTIVITIES		
	1840	Cleanup - Punchlist		62	11-15-25	01-15-26						Cleanup - P	unchlist			

Actual Level of Effort Remaining Work    Milestone	Page 4 of 4	Branch-Orders Joint Venture
Actual Work Critical Remaining Work summary		





# APPENDICES

### **APPENDIX 4.0.1.1** Technical Proposal Checklist and Contents

#### ATTACHMENT 4.0.1.1

#### I-81 WIDENING MM 136.6 TO MM 141.8

#### TECHNICAL PROPOSAL CHECKLIST AND CONTENTS

Offerors shall furnish a copy of this Technical Proposal Checklist, with the page references added, with the Technical Proposal.

Technical Proposal Component	Form (if any)	RFP Part 1 Cross Reference	Included within page limit?	Technical Proposal Page Reference
Technical Proposal Checklist and Contents	Attachment 4.0.1.1	Section 4.0.1.1	no	Appendix 4.0.1.1
Acknowledgement of RFP, Revisions, and/or Addenda	Attachment 3.7 (Form C-78-RFP)	Sections 3.7, 4.0.1.1	no	Appendix 3.7
List of Approved ATC's (if applicable)	Attachment 3.6.7 (Form C-78-RFP)	Sections 3.6.7	no	N/A
Letter of Submittal	NA	Sections 4.1		1
Letter of Submittal on Offeror's letterhead	NA	Section 4.1.1	yes	1
Identify the full legal name and address of Offeror	NA	Section 4.1.1	yes	1
Authorized representative's original signature	NA	Section 4.1.1	yes	1
Declaration of intent	NA	Section 4.1.2	yes	1
120 day declaration	NA	Section 4.1.3	yes	1
Point of Contact information	NA	Section 4.1.4	yes	1
Principal Officer information	NA	Section 4.1.5	yes	1
Interim Milestone and Final Completion Date(s)	NA	Section 4.1.6	yes	1
Unique Milestone Date	NA	Section 4.1.7	<u>yes</u>	1
Proposal Payment Agreement or Waiver of Proposal Payment	Attachment 9.3.1 or 9.3.2	<u>Section 4.1.8 *</u>	no	Appendix 9.3.1

\* Per VDOT's advice, information in the Technical Proposal Checklist has been changed to match RFP requirements.

#### ATTACHMENT 4.0.1.1

#### I-81 WIDENING MM 136.6 TO MM 141.8

#### **TECHNICAL PROPOSAL CHECKLIST AND CONTENTS**

Technical Proposal Component	Form (if any)	RFP Part 1 Cross Reference	Included within page limit?	Technical Proposal Page Reference
Certification Regarding Debarment Forms	Attachment 11.8.6(a) Attachment 11.8.6(b)	Section 4.1.9 *	no	Appendix 11.8.6
Written Statement of DBE Participation (9%)	NA	Section 4.1.10	<u>yes</u>	1
Offeror's Qualifications	NA	Section 4.2		2-3
Confirmation that the information provided in the SOQ submittal remains true and accurate or indicates that any requested changes were previously approved by VDOT	NA	Section 4.2.1	yes	2
Organizational chart with any updates since the SOQ submittal clearly identified	NA	Section 4.2.2	yes	3
Revised narrative when organizational chart includes updates since the SOQ submittal	NA	Section 4.2.2	yes	2
Design Concept	NA	Section 4.3		4-21, Vol I Tab 1, Vol II
Conceptual Roadway Plans and description	NA	Section 4.3.1.1	yes	4-15, Vol I Tab 1-A, Vol II
Conceptual Structural Plans and description	NA	Section 4.3.1.2	yes	15-21, Vol I Tab 1-B, Vol II
Project Approach	NA	Section 4.4		22-40
Environmental Management	NA	Section 4.4.1	yes	23-28
Utilities	NA	Section 4.4.2	yes	28-30
Geotechnical	NA	Section 4.4.3	yes	31-35

\* Per VDOT's advice, information in the Technical Proposal Checklist has been changed to match RFP requirements.

#### ATTACHMENT 4.0.1.1

#### I-81 WIDENING MM 136.6 TO MM 141.8

#### TECHNICAL PROPOSAL CHECKLIST AND CONTENTS

Technical Proposal Component	Form (if any)	RFP Part 1 Cross Reference	Included within page limit?	Technical Proposal Page Reference
Quality Assurance/ Quality Control (QA/QC)	NA	Section 4.4.4	yes	35-40
Construction of Project	NA	Section 4.5		41-53
Sequence of Construction	NA	Section 4.5.1	yes	41-46
Transportation Management Plan	NA	Section 4.5.2	yes	46-53
Disadvantaged Business Enterprises (DBE)	NA	Section 4.6		
	NA	Section 4.6	<del>yes</del>	+
Proposal Schedule	NA	Section 4. <u>6</u> 7		PS-1-PS-13, Vol I Tab 3, Vol II
Proposal Schedule	NA	Section 4.67	no	PS-1, Vol I Tab 3, Vol II
Proposal Schedule Narrative	NA	Section 4. <u>6</u> 7	no	PS-1-PS-10, Vol 1
Proposal Schedule in single .pdf	NA	Section 4. <u>6</u> 7	no	Provided in Tab 3 Vol II

## **APPENDIX 3.7**

Form C-78-RFP (Acknowledgment of Receipt of RFP, Revisions, and/or Addenda

#### ATTACHMENT 3.7

#### COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION

 RFP NO.
 C00116203DB108

 PROJECT NO.:
 0081-080-946

#### ACKNOWLEDGEMENT OF RFP, REVISION AND/OR ADDENDA

Acknowledgement shall be made of receipt of the Request for Proposals (RFP) and/or any and all revisions and/or addenda pertaining to the above designated project which are issued by the Department prior to the Letter of Submittal submission date shown herein. Failure to include this acknowledgement in the Letter of Submittal may result in the rejection of your proposal.

By signing this Attachment 3.7, the Offeror acknowledges receipt of the RFP and/or following revisions and/or addenda to the RFP for the above designated project which were issued under cover letter(s) of the date(s) shown hereon:

1.	Cover letter of	RFP – October 28, 2020
		(Date)
2.	Cover letter of	Addendum #1- December 16, 2020
		(Date)
3.	Cover letter of	Addendum #2- January 7, 2021
		(Date)
4.	Cover letter of	Addendum #3- January 27, 2021
		(Date)
5.	Cover letter of	Addendum #4- February 12, 2021
		(Date)

SIGNATURE

March 3, 2021

DATE

Jason Hoyle

Vice President Branch Civil, Inc.

PRINTED NAME

TITLE

### **APPENDIX 9.3.1** Proposal Payment Agreement

#### <u>ATTACHMENT 9.3.1</u> PROPOSAL PAYMENT AGREEMENT

**THIS PROPOSAL PAYMENT AGREEMENT** (this "Agreement") is made and entered into as of this <u>3<sup>rd</sup></u> day of <u>March</u>, 2021\_\_, by and between the Virginia Department of Transportation ("VDOT"), and <u>The Branch-Orders Joint Venture</u> ("Offeror").

#### WITNESSETH:

WHEREAS, Offeror is one of the entities who submitted Statements of Qualifications ("SOQs") pursuant to VDOT's May 29, 2020 Request for Qualifications ("RFQ") and was invited to submit proposals in response to a Request for Proposals ("RFP") for the **I-81** Widening MM 136.6 to MM 141.8, Project No. 0081-080-946 ("Project"), under a designbuild contract with VDOT ("Design-Build Contract"); and

WHEREAS, as part of the procurement process for the Project, Offeror has already provided and/or furnished to VDOT, and may continue to provide and/or furnish to VDOT, certain intellectual property, materials, information and ideas, including, but not limited to, such matters that are: (a) conveyed verbally and in writing during proprietary meetings or interviews; and (b) contained in, related to or associated with Offeror's proposal, including, but not limited to, written correspondence, designs, drawings, plans, exhibits, photographs, reports, printed material, tapes, electronic disks, or other graphic and visual aids (collectively "Offeror's Intellectual Property"); and

WHEREAS, VDOT is willing to provide a payment to Offeror, subject to the express conditions stated in this Agreement, to obtain certain rights in Offeror's Intellectual Property, provided that Offeror submits a proposal that VDOT determines to be responsive to the RFP ("Offeror's Proposal"), and either (a) Offeror is not awarded the Design-Build Contract; or (b) VDOT cancels the procurement or decides not to award the Design-Build Contract to any Offeror; and

**WHEREAS**, Offeror wishes to receive the payment offered by VDOT, in exchange for granting VDOT the rights set forth in this Agreement.

**NOW, THEREFORE**, in consideration of the mutual covenants and agreements set forth in this Agreement and other good and valuable consideration, the receipt and adequacy of which are acknowledged by the parties, the parties agree as follows:

1. <u>VDOT's Rights in Offeror's Intellectual Property</u>. Offeror hereby conveys to VDOT all rights, title and interest, free and clear of all liens, claims and encumbrances, in Offeror's Intellectual Property, which includes, without restriction or limitation, the right of VDOT, and anyone contracting with VDOT, to incorporate any ideas or information from Offeror's Intellectual Property into: (a) the Design-Build Contract and the Project; (b) any other contract awarded in reference to the Project; or (c) any subsequent procurement by VDOT. In receiving all rights, title and interest in Offeror's Intellectual Property, VDOT is deemed to own all intellectual property rights, copyrights, patents, trade secrets, trademarks, and service marks in Offeror's Intellectual Property, and Offeror agrees that it shall, at the request of VDOT, execute all papers and perform all other acts that may be necessary to ensure that VDOT's rights, title and interest in Offeror's ability to use Offeror's Intellectual Property without the obligation to notify or seek permission from Offeror.

2. <u>Exclusions from Offeror's Intellectual Property</u>. Notwithstanding Section 1 above, it is understood and agreed that Offeror's Intellectual Property is not intended to include, and Offeror does not convey any rights to, the Escrow Proposal Documents submitted by Offeror in accordance with the RFP.

**3.** <u>Proposal Payment</u>. VDOT agrees to pay Offeror the lump sum amount of **Two-hundred twenty five thousand and 00/100 Dollars (\$225,000.00)** ("Proposal Payment"), which payment constitutes payment in full to Offeror for the conveyance of Offeror's Intellectual Property to VDOT in accordance with this Agreement. Payment of the Proposal Payment is conditioned upon: (a) Offeror's Proposal being, in the sole discretion of VDOT, responsive to the RFP; (b) Offeror complying with all other terms and conditions of this Agreement; and (c) either (i) Offeror is not awarded the Design-Build Contract, or (ii) VDOT cancels the procurement or decides not to award the Design-Build Contract to any Offeror.

4. <u>Payment Due Date</u>. Subject to the conditions set forth in this Agreement, VDOT will make payment of the Proposal Payment to the Offeror within forty-five (45) days after the later of: (a) notice from VDOT that it has awarded the Design-Build Contract to another Offeror; or (b) notice from VDOT that the procurement for the Project has been cancelled and that there will be no Contract Award.

5. <u>Effective Date of this Agreement</u>. The rights and obligations of VDOT and Offeror under this Agreement, including VDOT's ownership rights in Offeror's Intellectual Property, vests upon the date that Offeror's Proposal is submitted to VDOT. Notwithstanding the above, if Offeror's Proposal is determined by VDOT, in its sole discretion, to be nonresponsive to the RFP, then Offeror is deemed to have waived its right to obtain the Proposal Payment, and VDOT shall have no obligations under this Agreement.

6. <u>Indemnity</u>. Subject to the limitation contained below, Offeror shall, at its own expense, indemnify, protect and hold harmless VDOT and its agents, directors, officers, employees, representatives and contractors from all claims, costs, expenses, liabilities, demands, or suits at law or equity ("Claims") of, by or in favor of or awarded to any third party arising in whole or in part from: (a) the negligence or wilful misconduct of Offeror or any of its agents, officers, employees, representatives or subcontractors; or (b) breach of any of Offeror's obligations under this Agreement, including its representation and warranty under Section 8 hereof. This indemnity shall not apply with respect to any Claims caused by or resulting from the sole negligence or wilful misconduct of VDOT, or its agents, directors, officers, employees, representatives or contractors.

7. <u>Assignment</u>. Offeror shall not assign this Agreement, without VDOT's prior written consent, which consent may be given or withheld in VDOT's sole discretion. Any assignment of this Agreement without such consent shall be null and void.

8. <u>Authority to Enter into this Agreement</u>. By executing this Agreement, Offeror specifically represents and warrants that it has the authority to convey to VDOT all rights, title, and interest in Offeror's Intellectual Property, including, but not limited to, those any rights that might have been vested in team members, subcontractors, consultants or anyone else who may have contributed to the development of Offeror's Intellectual Property, free and clear of all liens, claims and encumbrances.

#### 9. <u>Miscellaneous</u>.

a. Offeror and VDOT agree that Offeror, its team members, and their respective employees are not agents of VDOT as a result of this Agreement.

b. Any capitalized term used herein but not otherwise defined shall have the meanings set forth in the RFP.

c. This Agreement, together with the RFP, embodies the entire agreement of the parties with respect to the subject matter hereof. There are no promises, terms, conditions, or obligations other than those contained herein or in the RFP, and this Agreement shall supersede all previous communications, representations, or agreements, either verbal or written, between the parties hereto.

d. It is understood and agreed by the parties hereto that if any part, term, or provision of this Agreement is by the courts held to be illegal or in conflict with any law of the Commonwealth of Virginia, validity of the remaining portions or provisions shall not be affected, and the rights and obligations of the parties shall be construed and enforced as if the Agreement did not contain the particular part, term, or provisions to be invalid.

e. This Agreement shall be governed by and construed in accordance with the laws of the Commonwealth of Virginia.

**IN WITNESS WHEREOF**, this Agreement has been executed and delivered as of the day and year first above written.

#### VIRGINIA DEPARTMENT OF TRANSPORTATION

By:		

Name: \_\_\_\_\_

Title:

The Br	anch-Orders Joint Venture	
Bv·	Jan Han	
29.		

Name: Jason Hoyle

Title: \_\_\_\_\_Vice President – Branch Civil, Inc.\_\_\_\_\_

# **APPENDIX 11.8.6**

Certification Regarding Debarment; Primary and Lower Tier Covered Transactions

#### <u>ATTACHMENT 11.8.6(a)</u> <u>CERTIFICATION REGARDING DEBARMENT</u> <u>PRIMARY COVERED TRANSACTIONS</u>

#### Project No.: 0081-080-946

1) The prospective primary participant certifies to the best of its knowledge and belief, that it and its principals:

a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency.

b) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; and have not been convicted of any violations of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification, or destruction of records, making false statements, or receiving stolen property;

c) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1) b) of this certification; and

d) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

2) Where the prospective primary participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

March 3, 2021

Vice President - Design-Build/Major Projects

Signature

Date

Branch Civil, Inc.

#### ATTACHMENT 11.8.6(a) CERTIFICATION REGARDING DEBARMENT PRIMARY COVERED TRANSACTIONS

#### Project No.: 0081-080-946

The prospective primary participant certifies to the best of its knowledge and belief, that 1) it and its principals:

a) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal department or agency.

Have not within a three-year period preceding this proposal been convicted of or b) had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; and have not been convicted of any violations of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification, or destruction of records, making false statements, or receiving stolen property;

Are not presently indicted for or otherwise criminally or civilly charged by a c) governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph 1) b) of this certification; and

Have not within a three-year period preceding this application/proposal had one or d) more public transactions (Federal, State or local) terminated for cause or default.

Where the prospective primary participant is unable to certify to any of the statements in 2) this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

1/11/21 Signature

Prusident

Name of Firm

#### <u>ATTACHMENT 11.8.6(b)</u> <u>CERTIFICATION REGARDING DEBARMENT</u> <u>LOWER TIER COVERED TRANSACTIONS</u>

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

Muhal A. June 1/20/2021 Signature Date

Vice-President Title

Whitman, Requardt, and Associates, LLP Name of Firm

#### ATTACHMENT 11.8.6(b) CERTIFICATION REGARDING DEBARMENT LOWER TIER COVERED TRANSACTIONS

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

Signature

Date

Partner Title

Rummel, Klepper & Kahl, LLP

Name of Firm

#### <u>ATTACHMENT 11.8.6(b)</u> <u>CERTIFICATION REGARDING DEBARMENT</u> <u>LOWER TIER COVERED TRANSACTIONS</u>

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

1/7/21

Date

Vice President Title

Schnabel Engineering, L	LC

Name of Firm

Signature

#### ATTACHMENT 11.8.6(b) **CERTIFICATION REGARDING DEBARMENT** LOWER TIER COVERED TRANSACTIONS

#### Project No.: 0081-080-946

The prospective lower tier participant certifies, by submission of this proposal, that 1) neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

Date PRESIDENT Title

Signature

KDR PEAL ESTATE SERVICES

Name of Firm

#### ATTACHMENT 11.8.6(b) CERTIFICATION REGARDING DEBARMENT LOWER TIER COVERED TRANSACTIONS

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

Title SISH ASSOC Date

#### <u>ATTACHMENT 11.8.6(b)</u> <u>CERTIFICATION REGARDING DEBARMENT</u> <u>LOWER TIER COVERED TRANSACTIONS</u>

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

2/12/2021

President Title

Precision Measurements, Inc. Name of Firm

#### ATTACHMENT 11.8.6(b) CERTIFICATION REGARDING DEBARMENT LOWER TIER COVERED TRANSACTIONS

#### Project No.: 0081-080-946

1) The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction by any Federal department or agency.

2) Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

The undersigned makes the foregoing statements to be filed with the proposal submitted on behalf of the Offeror for contracts to be let by the Commonwealth Transportation Board.

Aslynn	F.Ce	0107/2020	VP,	Bushas	HOLINSTRATION	)
Signature /	Date		Title	e		

SO STORENTON CONSULTING, Inc.

Name of Firm

### VDOT APPROVED CHANGES Evidence of VDOT Approval for Team



**COMMONWEALTH of VIRGINIA** 

DEPARTMENT OF TRANSPORTATION

Stephen C. Brich, P.E. Commissioner 1401 East Broad Street Richmond, Virginia 23219

(804) 786-2701 Fax: (804) 786-2940

February 16, 2021

Mr. Donald Bryson Branch-ORDERS Joint Venture 442 Rutherford Ave, NE Roanoke, VA 24016

Subject: Request for Team Change I-81 Widening MM 136.6 to MM 141.8 Roanoke County and City of Salem, Virginia Project No.: 0081-080-946 Contract ID No.: C00116203DB108

Dear Mr. Bryson,

Thank you for your request for a change to the Branch-ORDERS Joint Venture (Branch-ORDERS JV) team for the above referenced project. As you noted in your request and per a VDOT letter of December 3. 2020, H&B Surveying and Mapping LLC was released from the Branch-ORDERS JV as a condition of not precluding the Branch-ORDERS JV team from participating in the pursuit of the design-build contract for this project. The Branch-ORDERS JV proposed Precision Measurements, Inc. (PMI) as a replacement firm for their Surveying/Subsurface Utility Engineering services.

The Branch-ORDERS JV team also proposed the addition of Land Planning and Design Associates, Inc. for their landscaping services.

The information required for firms as part of the Statement of Qualifications was provided for the above referenced firms.

After careful consideration of the information provided by Branch-ORDERS Joint Venture and in accordance with Part 1 Section 11.4 of the RFP which allows VDOT to approve a change in the Team Structure under extraordinary circumstances, VDOT has determined it will grant the substitution of Precision Measurements, Inc. for H&B Surveying and Mapping LLC and the addition of Land Planning and Design Associates, Inc. to your team.

Sincerely,

Bryan W. Stevenson, P.E., DBIA Senior Project Delivery Engineer Alternative Project Delivery Division





(**Q**) 442 Rutherford Avenue, NE, Roanoke, VA 24016 (**C**) 540.982.1678

www.branchcivil.com | www.ordersconstruction.com



**TECHNICAL PROPOSAL - VOLUME II** 

### I-81 WIDENING MM 136.6 TO MM 141.8

ROANOKE COUNTY AND CITY OF SALEM, VIRGINIA

State Project No.: 0081-080-946, P101, R201, C501, B677, B678, B681, B682, B683, B684, B685, B686, B687, B688 Federal Project No.: NHPP-0812 (323) Contract ID Number: C00116203DB108



Joint Venture -----

in association with Lead Designer



### ELECTRONIC SUBMISSION



### MARCH 3, 2021





# A. ROADWAY DESIGN



dll6203000\_Title\_Sheet.dgn

Plotted By: ahusted-sherman

LIMITED ACCESS HIGHWAY By Resolution of Highway Commission dated Oct. 4, 1956





LOCATION	BRANCH-ORDERS MAXIMUM GRADE	ALLOWABLE MAXIMUM GRADE
1-81	3.50%	4%
Route II2 Ramp A	4.70%	3-5%
Route II2 Ramp B	3.60%	3-5%
Route II2 Ramp D	4.00%	4-6%
Route II2 Loop D	1.50%	5-7%
Route II2 Loop D Spur	3.00%	6-8%
Route II2 (Wildwood Rd.)	NZA	NZA
Route 311 Ramp A	3.60%	3-5%
Route 311 Ramp B	1.30%	3-5%
Route 311 Ramp D	2.90%	4-6%
Route 311 Loop D	3.70%	5-7%
Route 419 Ramp B	2.30%	4-6%
Route 419 Ramp D	3.70%	4-6%
Route 419 Loop B	2.80%	5-7%
Route 419 Loop D	3.20%	5-7%
Route 635 (Goodwin Ave.)	7.00%	10%
Route 619 (Wildwood Rd.)	NZA	NZA





\$1

\$DATE\$

\$*F1LE\$* 

NOTE: SEE RFP FOR PROPOSED PAVEMENT STRUCTURE









\$FILE\$





\$FILE\$


\$DATE\$

\$FILE\$



\$DATE\$





\$DATE\$

\$F1LE\$







\$*F1LE\$* 



















\$*F1LE\$* 



# **B. STRUCTURE DESIGN**



STATE		FEDERAL AID		SHEET			
STATE	ROUTE	PROJECT	ROUTE	PRO	NO.		
VA.			81	0081-080-946	, B683, B688	1	
Federal Structure No.				FHWA Construction and Scour Code:			
Fede	ral St	ewardship and Oversight Cod	e: UPC No.				

DESIGN EXCEPTION(S):

#### GENERAL NOTES:

The original approved sheet, including original signatures, is filed in the VDOT Central Office. Any misuse of electronic files, including scanned signatures is illegal. Violators will be prosecuted to the full extent of the applicable laws.

Width: 60'-0" face-to-face of curbs (NBL Str. No. B683). 72'-0" face-to-face of curbs (SBL Str. No. B688).

Span layout: 73'-4" - 66'-8" (NBL Str. No. B683). 73'-8" - 67'-0" (SBL Str. No. B688).

Capacity: HL-93 loading.

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2020.

Design: AASHTO LRFD Bridge Design Specifications, 8th Edition, 2017; including Errata and VDOT Modifications.

Standards: Virginia Department of Transportation Road and Bridge Standards, 2016; including all current revisions.

These plans are incomplete unless accompanied by the Supplemental Specifications and Special Provisions included in the contract documents.

Design loading includes 20  $\ensuremath{\mathsf{psf}}$  allowance for construction tolerances and construction methods.

Design loading includes 15 psf allowance for future wearing surface.

All structural steel shall be ASTM A709 Grade 50W and shall be unpainted.

Concrete in superstructure, barriers and integral backwalls shall be Low Shrinkage Class A4 Modified in accordance with Section 217.12(a); in substructure, Class A3.

Concrete surface color coating shall be grey, similar to Federal Standard Color No. 595-36622 and shall be required at all locations of architectural treatment.

All reinforcing steel shall be deformed and shall conform to ASTM A615, Grade 60 except for steels noted as Corrosion Resistant Reinforcing (CRR) which shall conform to Section 223 of the Specifications. All reinforcing bar dimensions on the detailed drawings are to centers of bars except where otherwise noted and are subject to fabrication and construction tolerances.

CRR steels shall conform to one or more of the three Classes listed in Section 223 of the Specifications. The Class(es) of CRR steel(s) required on this project is/are noted on plan sheets and in the reinforcing steel schedule. CRR Steel, Class II or Class III may be substituted for Class I. CRR Steel, Class III, may be substituted for Class II.

Bridge No. of existing NBL Str. No. B683 bridge is 2004. Plan No. is 151-03 (NBL Str. No. B683). Bridge No. of existing SBL Str. B688 bridge is 2005. Plan No. is 151-03 (SBL Str. No. B688).

Drystack architectural treatment shall be placed on exterior faces of parapets, abutments and MSE walls.



## COMMONWEALTH OF VIRGINIA

DEPARTMENT OF TRANSPORTATION PROPOSED BRIDGE REPLACEMENT ON I-81 NBL OVER ROUTE 112 (WILDWOOD ROAD) ROANOKE CO. - 6.83 MI. N. OF MONTGOMERY CO. PROJ. 0081-080-946, B683 I-81 SBL OVER ROUTE 112 (WILDWOOD ROAD) ROANOKE CO. - 4.29 MI. S. OF ROUTE 419 PROJ. 0081-080-946, B688

 Recommended for Approval:
 District Project Development Engineer
 Date

 Approved:
 District Administrator
 Date

 ISING Administration
 ISING Administrator
 ISING Administrator

 Date:
 March 3, 2021
 © 2021, Commonwealth of Virginia
 Sheet 1 of 5



STATE		FEDERAL AID		SHEET	
	ROUTE	PROJECT	ROUTE	PROJECT	N0.
VA.	—		81	0081-080-946, B683, B688	2

_			1 ''	1 01 0461 112								
				DEVELOPED SECTION								
			AND	AND TRANSVERSE SECTION								
	Description	Date	Designed:	Date	Plan No.	Sheet No.						
	0000 (p / 0//		Drawn:									
Revisions			Checked:	Mar. 2021	151-030	2 of 5						





STAT.	STATE	FEDERAL AID			STATE			
	STATE	ROUTE PROJECT		ROUTE	PROJECT	NO.		
	VA.	_		81	0081-080-946, B683, B688	4		

			MSE	ABUTMENT AND MSE WALL ELEVATIONS						
o.	Description	Date	Designed:	Date	Plan No.	Sheet No.				
	Revisions		Drawn: Checked:	Mar. 2021	151-030	4 of 5				
	1041310113									



STATE		FEDERAL AID		SHEET	
	ROUTE	PROJECT	ROUTE	N0.	
VA.	—		81	008I-080-946, B683, B688	5

Note:

Pier protection not shown for clarity.



_			DEP	COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION							
			STE	STRUCTURE AND BRIDGE DIVISION							
			-8	I-81 OVER RTE. 112							
_			PIER ELEVATIONS								
			AND	TYPICA	L END VIE	W					
o.	Description	Date	Designed:	Date	Plan No.	Sheet No.					
	Revisions	1	Drawn: Checked:	Mar. 2021	151-03C	5 of 5					



	STATE		FEDERAL AID		SHEET		
	JIAIL	ROUTE	PROJECT	ROUTE	PRO	JECT	NO.
	VA. —		81	0081-080-946	, B684, B685	1	
	Fede	ral St	ructure No.	FHWA and	Construction Scour Code:	n .	
	Federal Stewardship and Oversight Code: UPC No.						

#### **DESIGN EXCEPTION(S):**

### GENERAL NOTES:

The original approved sheet, including original signatures, is filed in the VDOT Central Office. Any misuse of electronic files, including scanned signatures is illegal. Violators will be prosecuted to the full extent of the applicable laws.

Width: 60'-0" face-to-face of curbs. (NBL Str. No. B684) 60'-0" face-to-face of curbs. (SBL Str. No. B685)

Span layout: 81'-6" (NBL Str. No. B684) 83'-5¾", Varies (SBL Str. No. B685)

Capacity: HL-93 loading.

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2020.

Design: AASHTO LRFD Bridge Design Specifications, 8th Edition, 2017, including Errata; and VDOT Modifications.

Standards: Virginia Department of Transportation and Bridge Standards, 2016; including all current revisions.

These plans are incomplete unless accompanied by the Supplemental Specifications and Special Provisions included in the contract documents.

Design loading includes 20  $\ensuremath{\mathsf{psf}}$  allowance for construction tolerances and construction methods.

Design loading includes 15 psf allowance for future wearing surface.

All structural steel shall be ASTM A709 Grade 50W and shall be unpainted.

Concrete in superstructure, parapets, and integral backwalls shall be Low Shrinkage Class A4 Modified in accordance with Section 217.12(a); in substructure, Class A3.

Concrete surface color coating shall be grey, similar to Federal Standard Color No. 595-36622 and shall be required at all locations of architectural treatment.

All reinforcing steel shall be deformed and shall conform to ASTM A615, Grade 60 except for steels noted as Corrosion Resistant Reinforcing (CRR) which shall conform to Section 223 of the Specifications. All reinforcing bar dimensions on the detailed drawings are to centers of bars except where otherwise noted and are subject to fabrication and construction tolerances.

CRR steels shall conform to one or more of the three Classes listed in Section 223 of the Specifications. The Classes of CRR steels required on this project are noted on plan sheets and in the reinforcing steel schedule. CRR Steel, Class II or Class III may be substituted for Class I. CRR Steel, Class III, may be substituted for Class II.

Bridge No. of existing I-81 NB structure is 2010 and Plan No. is 151-10. Bridge No. of existing I-81 SB structure is 2011 and Plan No. is 151-10.

Drystack architectural treatment shall be placed on exterior faces of parapets, abutments, and MSE walls.



COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION PROPOSED BRIDGE REPLACEMENT ON

I-81 NBL OVER ROUTE 635 (GOODWIN AVE.) ROANOKE CO. - I.26 MI. N OF ROUTE II2 PROJ. 0081-080-946, B684
I-81 SBL OVER ROUTE 635 (GOODWIN AVE.) ROANOKE CO. - 3.03 MI. S OF ROUTE 419 PROJ. 0081-080-946, B685

Recommended for Approve	l:District Project Development Engineer	Date
Approved:	District Administrator	81 Date
Date:March_3, 2021	© 2021, Commonwealth of Virginia Sheet	I of 4



## DEVELOPED SECTION ALONG I-81 CONSTR. B

NBL shown, SBL similar. \*15'-8" minimum vertical clearance will be exceeded in proposed to provide minimum 15'-8" vertical clearance for future widening.



CONSTRUCTION COMPANY

	STATE	ROUTE	FEC	DERAL A	AID FCT	ROUTE		STATE		SHEET NO.
	VA.				201	81	0081-	080-946, B684,	B685	2
				, [c.	.G. Sta. 202+1	5.89				
		-	1.08%	C. V.	.G. Elev. 1155. .C. = 720' +1.01%	66				
, _										
<u> </u>			<u> </u>	-						
							3/4" <sup>†</sup>			
					DRIP	DET	AIL			
					Not to	o scal	e			
۰			24'-0''-							
Ъ	Point	of ed or	ode l	Face (	'-2 <sup> </sup> /2''		- 1'-4''			
/ `			_ <u>2% slo</u>	ope -			-Noise	drip bead		
	Ţ			5						
— 3	spa.	@ 10'	-0" = 30'-	-0''—		<b> </b>	2'-10''			
				S a t	SCP with no rchitectural reatment					
			r							
					DEP	COMMO ARTME	NWEAL NT OF	TH OF VIRGINIA TRANSPORTATIO	N	
				-+	STF		VFP	BRIDGE DIVISION		
							ED S	SECTION A	ND	งา
No.	D	escript	ion [	)ate (	Designed:	CRIM		Plan No.	N She	ðZ et No.
		Revisi	ions		Drawn: Checked:	Mar.	2021		2 c	of 4





EXISTING







PHASE 3





FINAL

Scale: 1/8" = 1'-0"

© 2021, Commonwealth of Virginia

	STATE		FEDERAL	AID			STATE		SHEET
	J.AIE	ROUTE	PRO	JECT	ROUTE	000	PROJECT	DCCT	NO.
	VA.	<u> </u>			81	-1800	uxu-946, B684,	8685	3
— No	oise b	arrier							
SS	CP wi	th no							
∽ar  tr	chitec eatme	stural Int ty	p.						
L		5							
-   '-4 	1" 1/2"								
, -Z	/2								
				Г	000	1 16 416			
					FKF		IART PLANS		
					THESE		NOT TO BE USE	D	
				L					
				0.55	СОММО	NWEAL			
				UEF				IN .	
				SII					
				[-]		IVER	RIE 635	1	
				SEQUE	NCF	OF	CONSTRUC		Noa
						<b>.</b> .			83
No.	De	escripti	on Date	Designed:	Do	ite	Plan No.	She	e† No.
		Revisio	ons	Checked:	Mar.	2021		3 0	of 4



SBL ELEVATION

Abutment B shown, Abutment A similar opposite hand.



STATE	FEDERAL AID			STATE			
	ROUTE	PROJECT	ROUTE	PROJECT			
VA.			81	0081-080-946, B684, B685	4		





TYPICAL SECTION

Scale: 1/4" = 1'-0"

			DEF	COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION							
			STI	RUCTURE AND	BRIDGE DIVISION						
			-	I-81 OVER RTE 635							
			ABUTMENT AND								
			MSE WALL ELEVATIONS 84								
No.	Description	Date	Designed:	Date	Plan No.	Sheet No.					
	Revisions	Drawn: Checked:	Mar. 2021		4 of 4						



	STATE	FEDERAL AID			STATE				
STATE		ROUTE	PROJECT		PROJECT			NO.	
	VA.			8.1	0081-080-946	, B686,	B687	1	
	Federal Structure No.			FHWA and	Construction Scour Code:	٦			
	Federal Stewardship and Oversight Cod				1. Sec. 1. Sec	UPC No			

#### **DESIGN EXCEPTION(S):**

### GENERAL NOTES:

The original approved sheet, including original signatures, is filed in the VDOT Central Office. Any misuse of electronic files, including scanned signatures is illegal. Violators will be prosecuted to the full extent of the applicable laws.

Width: 60'-0" face-to-face of curbs. (NBL Str. No. B687) 60'-0" face-to-face of curbs. (SBL Str. No. B686)

Span layout: 70'-2'/2" (NBL Str. No. B687) 70'-2'/2" (SBL Str. No. B686)

Capacity: HL-93 loading.

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2020.

Design: AASHTO LRFD Bridge Design Specifications, 8th Edition, 2017, including Errata; and VDOT Modifications.

Standards: Virginia Department of Transportation and Bridge Standards, 2016; including all current revisions.

These plans are incomplete unless accompanied by the Supplemental Specifications and Special Provisions included in the contract documents.

Design loading includes 20  $\ensuremath{\mathsf{psf}}$  allowance for construction tolerances and construction methods.

Design loading includes 15 psf allowance for future wearing surface.

All structural steel shall be ASTM A709 Grade 50W and shall be unpainted.

Concrete in superstructure, barriers, and integral backwalls shall be Low Shrinkage Class A4 Modified in accordance with Section 217.12(a); in substructure, Class A3.

Concrete surface color coating shall be grey, similar to Federal Standard Color No. 595-36622 and shall be required at all locations of architectural treatment.

All reinforcing steel shall be deformed and shall conform to ASTM A615, Grade 60 except for steels noted as Corrosion Resistant Reinforcing (CRR) which shall conform to Section 223 of the Specifications. All reinforcing bar dimensions on the detailed drawings are to centers of bars except where otherwise noted and are subject to fabrication and construction tolerances.

CRR steels shall conform to one or more of the three Classes listed in Section 223 of the Specifications. The Classes of CRR steels required on this project are noted on plan sheets and in the reinforcing steel schedule. CRR Steel, Class II or Class III may be substituted for Class I. CRR Steel, Class III, may be substituted for Class II.

Bridge No. of existing I-81 NB structure is 2008 and Plan No. is 151-04. Bridge No. of existing I-81 SB structure is 2011 and Plan No. is 151-04. Drystack architectural treatment shall be placed on exterior faces of parapets, abutments, and MSE walls.



COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION PROPOSED BRIDGE REPLACEMENT ON

I-81 NBL OVER ROUTE 619 (WILDWOOD RD)
ROANOKE CO. - 1.65 MI. N. OF ROUTE 112 PROJ. 0081-080-946, B687
I-81 SBL OVER ROUTE 619 (WILDWOOD RD)
ROANOKE CO. - 1.23 MI. S. OF ROUTE 311 PROJ. 0081-080-946, B686

Recommended for Approval	District Project Development Engineer	-	 Dat	 e
Approved			8	85
	District Administrator	-	Dat	e
Date:March_3, 2021	© 2021, Commonwealth of Virginia Sheet	T	of	4



		Т					07.4TF			
	STATE		FEDERAL AID		_		SIAIL			SHEET
		ROUTE	PROJECI	ROUIE	E		PROJE	CT		NU.
	VA.			81	(	0-1800	80-946,	B686,	B687	2
-										
C.0	3. <u>S</u> to	J. 221	+80.00							
	j. Ele	V. 117	5.49							
[	/• = .	100								
+	3.40%									
	— Fin	ished	arade							]
y	/ • …	101100								
										]
			╵╢╴╟							
			//							
			//							
			<u>//</u>							
			// 11							
		/	/							
					_					]
				/.						
							×4"			
				/	•		1			
					$\sim$		<u> </u>			
						Ξ.,	2/			
					ī	> r_;	¥4"			
					-	<b> </b> ← "	/			
				172	F	←				
					_		/			

No.	Description	Date	Designed:	Date	Plan No.	Sheet No.	
	becomprise						
Revisions			-Drawn: Checked:	Mar. 2021		2 of 4	





EXISTING







PHASE 3



FINAL



Scale: 1/8" = 1'-0"

© 2021, Commonwealth of Virginia

STATE	DOUTE		FEDERAL	AID		DOUTE		STATE			SHEET
VA.	ROUTE		PRC	IJECI		ROUTE	0081-	PROJE	CT B686	B687	NU. 3
						01	0001	000 510,	5000,	0001	5
-21/2											
-											
					Г	DDEI	IN AIN I				
loise	barr	ier				רתבו		ARIF	LANS		
					1	THESE F		NOT TO	BE USEI	5	
SCP	with	no				F					
rchi reat	tectu ment	ral tvp.									
		· )p.		-							
						соммо	NWEAL	TH_OF_VI	RGINIA		
					DEP	PARTME	NT OF	TRANSPO	ORTATIO	N	
					ST	RUCTUR	E AND	BRIDGE	DIVISION		
				l	1-8	BI C	VER	RTE	619	)	
			_		、 <del>.</del> .		~ <b>-</b>	001-0			
				SE(	3UE	NCE	OF	CONS	I RU(	1101	NQ7
				I				-			0/
				-		n -	<b>+</b> Δ	DI	NC	Ch-	
D	escript	ion	Date	Designed: . Drawn:		Da	te 2021	Plar	No.	She z	et No.



SBL ELEVATION Abutment B shown, Abutment A similar opposite hand.



NBL ELEVATION







STATE	FEDERAL AID			STATE				
	ROUTE	PROJECT	ROUTE	PROJECT	NO.			
VA.	—		81	0081-080-946, B686, B687	4			

Notes:

HR-I railing as required by RFP now shown. Only part of the architectural treatment is shown for clarity.



			DEF	COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION								
			STE	RUCTURE AND	BRIDGE DIVISION							
			-	I-81 OVER RTE 619								
			AE	ABUTMENT AND MSE								
No.	Description	Date	Designed:	Date	Plan No.	Sheet No.						
Revisions			Drawn: Checked:	Mar. 2021		4 of 4						

Due to the proximity of the bridges, they were combined into a single plan for clarity. This is for the Response to RFP only; plans will be developed for the structures in accordance with VDOT practice for future plan submittals.



1	STATE		FEDERAL AID		SHEET			
	STATE	ROUTE	PROJECT	ROUTE	PRO	ECT		NO.
	VA.			81	0081-080-946	, B677,	B678	I
	Federal Structure No.			FHWA and	Construction Scour Code:	٦		
	Federal Stewardship and Oversight Code					LIPC No	)	

DESIGN EXCEPTION(S):

#### GENERAL NOTES:

The original approved sheet, including original signatures, is filed in the VDOT Central Office. Any misuse of electronic files, including scanned signatures is illegal. Violators will be prosecuted to the full extent of the applicable laws.

Width: 58'-0" face-to-face of curbs (NBL Str. No. B678). 70'-0" face-to-face of curbs (SBL Str. No. B677).

Span layout: 140'-0" (NBL Str. No. B678). 140'-0" (SBL Str. No. B677).

Capacity: HL-93 loading (widening and bearings), HS-20-44 and military loading (existing structure).

Specifications:

Construction: Virginia Department of Transportation Road and Bridge Specifications, 2020.

Design: AASHTO LRFD Bridge Design Specifications, 8th Edition, 2017; including Errata and VDOT Modifications (widening and bearings).

Standards: Virginia Department of Transportation Road and Bridge Standards, 2016; including all current revisions.

These plans are incomplete unless accompanied by the Supplemental Specifications and Special Provisions included in the contract documents.

Design loading includes 20  $\ensuremath{\mathsf{psf}}$  allowance for construction tolerances and construction methods.

All structural steel shall be ASTM A709  $\mbox{Grade}$  50W and shall be unpainted.

Concrete in superstructure, parapets, and terminal walls shall be Low Shrinkage Class A4 Modified in accordance with Section 217.12(a); in substructure, Class A3.

Concrete surface color coating on the substructure shall be coordinated with the Department.

All reinforcing steel shall be deformed and shall conform to ASTM A615, Grade 60 except for steels noted as Corrosion Resistant Reinforcing (CRR) which shall conform to Section 223 of the Specifications. All reinforcing bar dimensions on the detailed drawings are to centers of bars except where otherwise noted and are subject to fabrication and construction tolerances.

CRR steels shall conform to one or more of the three Classes listed in Section 223 of the Specifications. The Classes of CRR steels required on this project are noted on plan sheets and in the reinforcing steel schedule. CRR Steel, Class II or Class III may be substituted for Class I. CRR Steel, Class III, may be substituted for Class II.

Architectural treatment on the substructure widening/reconstruction shall match the existing substructure architectural treatment.

Bridge No. of existing NBL Str. No. B678 bridge is 2015. Plan No. is 257-79 (NBL Str. No. B678). Bridge No. of existing SBL Str. B677 bridge is 2014. Plan No. is 257-79 (SBL Str. No. B677).

## VDOT

## COMMONWEALTH OF VIRGINIA

DEPARTMENT OF TRANSPORTATION PROPOSED BRIDGE WIDENING ON I-81 NBL OVER ROUTE 311 (THOMPSON MEMORIAL DRIVE) ROANOKE CO. - 2.94 MI. N. OF ROUTE 112 PROJ. 0081-080-946, B678 I-81 SBL OVER ROUTE 311 (THOMPSON MEMORIAL DRIVE) ROANOKE CO. - 1.30 MI. S. OF ROUTE 419 PROJ. 0081-080-946, B677

Recommended for Approval		
	District Project Development Engir	neer Date
Approved:		
	District Administrator	Date
		257-701
		201-19A
Date: March 3, 2021	© 2021, Commonwealth of Virginia	Sheet   of 5



STATE		FEDERAL AID		SHEET	
	ROUTE	PROJECT	ROUTE	PROJECT	N0.
VA.	—		81	0081-080-946, B677, B678	2



STATE		FEDERAL AID		SHEET		
	STATE	ROUTE	PROJECT	ROUTE	PROJECT	N0.
	VA.			81	0081-080-946, B677, B678	3

			COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION					
			STRUCTURE AND BRIDGE DIVISION					
			I-81 OVER RTE. 311					
			SEQUENCE OF CONSTRUCTION					
			SHEET I UF Z					
lo.	Description	Date	Designed: Date Plan No. Sheet No	).				
	Revisions		Checked: Mar. 2021 257-79A 3 of 5					



Т	STATE	FEDERAL AID		STATE			
		ROUTE PROJECT		ROUTE PROJECT			N0.
	VA.	—		81	0081-080-946, B677	, B678	4

			COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION						
			STRUCTURE AND BRIDGE DIVISION						
			I-81 OVER RTE. 311						
			SEQUENCE OF CONSTRUCTION						
			SHEET Z OF Z						
o.	Description	Date	Designed: Date Plan No. Sheet No.						
	Revisions		Checked: Mar. 2021 257-79A 4 of 5						



	CTATE	FEDERAL AID			SHEET		
	STATE	ROUTE	PROJECT	ROUTE	PROJECT	N0.	
	VA.	—		81	0081-080-946, B677, B678	5	

			COMMONWEALTH OF VIRGINIA DEPARTMENT OF TRANSPORTATION						
			STRUCTURE AND BRIDGE DIVISION						
			1-8	31 OVER	RTE. 311				
			ABUTMENT						
			MODIFICATIONS						
о.	Description	Date	Designed:	Date	Plan No.	Sheet No.			
	Revisions		Drawn: Checked:	Mar. 2021	257-79A	5 of 5			




# TECHNICAL PROPOSAL CONCEPTUAL DESIGN I-81 WIDENING MM 136.6 TO MM 141.8 UPC II6203 (PROJECT # 0081-080-946)



94



**TAB 2** Utility Matrix

1111000

INTER

EH

#### UTILITY MATRIX

Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation.

Date of last update: 3/1/2021 **Cost Responsibility Reason Codes** 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility district or public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. -

LEFT. OFFSETS UTILITY ROADWAY TYPE OF ON ROW, OFF ROW, PLAN RIGHT, MEASUREMENT TEST CONFLICT COST Proiect Item QUANTITY ADDITIONAL DESCRIPTIVE REMARKS SIZE POLE NUMBER STATIONS FROM UPC RESPONSIBI # SHEET COMPANY CENTERLINE FACILITY HOLES EVALUATION OR IN EASEMENT OR UNITS CENTERLINE вотн Roll 116203 VDOT I-81 NB FO 99+52 - 107+13 L 13' - 21' LF 772 No Conflict ON ROW Project Plot ' Roll 116203 VDOT I-81 NB FO 107+13 - 121+44 21' - 26' LF 1432 Cables in conflict with median widening In Conflict ON ROW L Project Plot ' Roll 116203 City of Salem I-81 SB Р 510+16 146' ΕA OFF ROW L 1 No Conflict Proiect Plot ' Roll City of Salem R 136' EA 1 116203 I-81 NB Р 112+63 Project No Conflict ON ROW Plot 1 Roll 116203 City of Salem I-81 SB Р 512+68 L 128' ΕA 1 No Conflict OFF ROW Project Plot 1 Roll 16203 City of Salem I-81 NB 113+15 - 113+20 R 163' - 129' LF 34 No Conflict ON ROW Project Е Plot ' Roll 116203 City of Salem I-81 NB Е 113+18 - 113+20 R 163' - 129' LF 36 No Conflict ON ROW Project Plot 1 Roll 116203 City of Salem I-81 NB Р 113+20 R 129' EA 1 ON ROW Project No Conflict Plot 1 Roll 116203 I-81 NB Р R ΕA 1 City of Salem 113 + 26207' No Conflict ON ROW Project Plot 1 Roll 10 116203 City of Salem I-81 NB Р 113+35 R 163' ΕA 1 No Conflict ON ROW Project Plot 1 Roll Plot 1 16203 Р City of Salem I-81 NB 114+91 R 158' ΕA 1 No Conflict ON ROW Project Roll 12 116203 I-81 NB Р R 155' ΕA Project City of Salem 115+68 1 ON ROW No Conflict Plot ' Roll 13 116203 City of Salem I-81 SB Р L 227' ΕA 1 ON ROW 520+70 No Conflict Project Plot ' Roll 116203 City of Salem I-81 SB S 8" 520+75 - 522+02 L 188' - 308' 1 F 176 Continues as item # 16 No Conflict ON ROW Project Plot ' Roll 16203 VDOT I-81 NB FO 121+44 - 130+91 26' - 22' LF 947 Cables in conflict with median widening In Conflict ON ROW Project L Plot ' Roll 16203 City of Salem Rt 112 RPD s 8" 1304+51 - 1307+76 R 62' - 66' LF 347 Continuation of Item # 14 No Conflict ON ROW Project Plot ' Roll 116203 City of Salem Rt 112 RPD 8" 1304+36 - 1304+51 R 145' - 62' 1 F 86 Project 17 S No Conflict ON ROW Plot 1 Roll 18 116203 City of Salem Rt 112 RPD S 8" 1303+08 - 1304+51 R 64' - 62' LF 169 No Conflict ON ROW Project Plot 1 Roll 19 116203 City of Salem Rt 112 RPD s 8" 1301+66 - 1303+08 R 119' - 64' LF 161 No Conflict ON ROW Project Plot 1 Roll 20 16203 City of Salem Rt 112 RPD Р 1307+82 R 85' ΕA No Conflict ON ROW Project 1 Plot ' Roll 21 116203 City of Salem Rt 112 RPD Р 1305+42 R 41' ΕA 1 No Conflict ON ROW Project Plot 1 Roll Phone line feeding this pedestal is 22 16203 Verizon Rt 112 RPD T Ped 1304+62 R 89' ΕA 1 No Conflict ON ROW Project Plot ' missina. Roll 23 16203 Rt 112 RPD R 107' ΕA 1 ON ROW City of Salem Hydrant 1304+50 Water line feeding this hydrant is missing. No Conflict Project Plot ' Roll Phone line feeding this pedestal is 24 116203 Verizon Rt 112 RPD T Ped 1304+13 R 72' ΕA 1 No Conflict ON ROW Project Plot ' missing Roll 25 116203 City of Salem Rt 112 RPD Р 1303+96 R 71' ΕA 1 No Conflict ON ROW Project Plot 1 Roll 27 116203 Rt 112 RPD R ΕA Project City of Salem Р 1302+52 109' 1 No Conflict ON ROW Plot 1 Roll Conflict #1: Possible conflict with 28 116203 Roanoke Gas Rt 112 BL G 4" 1404+50 - 1408+00 L 41' - 39' LF 352 Possible Conflict ON ROW Project Plot 1 replacement of storm drain. Roll 29 116203 City of Salem Rt 112 BL Ρ 1404+46 R 53' ΕA 1 No Conflict ON ROW Project Plot 1 Roll 30 116203 Citizens Rt 112 BL Tel Cab 1404+46 R 51' ΕA 1 No Conflict ON ROW Utility Plot ' Roll 31 116203 Verizon Rt 112 BL T Ped 1404+46 R 54' EA 1 No Conflict ON ROW Project Plot 1 Possible conflict with existing 12" water Roll main and proposed storm sewer. Vertical LF 32 116203 City of Salem Rt 112 BL W 12" 1404+50 - 1408+00 L 35' - 36' 352 None Possible Conflict ON ROW Project Plot 1 separation is approximatley 4 inches. Water main is on top.

counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-330 used on private property.; 8. - Prior Rights.; 9.

LITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	1		
	1		
	1		
	1		
	1		
	1		
	1		
	1		
	1		
	1		
	1		
	4		
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	4		
	4		
	4		
	4		
	1		
	1		
	2		
	1		
	2		
	1		
	1		
	2	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.
	1		
	9		
	2		
	1	IN-PLAN	IN-PLAN WORK: Relocate existing 12" water main under existing and proposed storm sewers at Sta. 1408+78

UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 4. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-300 used on Arterial Projects for utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-300 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. - Prior Rights.; 9. - Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation.

ltem Project # UPC	PLAN SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE	POLE NUMBER	STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMENT UNITS	QUANTITY	TEST HOLES	ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
33 116203	Roll Plot 1	WVWS	Rt 112 BL	s	10"		1404+50 - 1406+67	R	40' - 34'	LF	216	None	Possible horizontal conflict with existing sanitary sewer manhole. Vertical separation between existing sanitary sewer pipe and proposed storm sewer is approximlatey 17 - 32 inches. Gravity sewer is under storm.	Possible Conflict	ON ROW	Project	4	IN-PLAN	Adjust location of proposed storm sewer to avoid manhole.
34 116203	Roll Plot 1	Citizens	Rt 112 BL	FO	1 - 240 Count		1404+62 - 1405+89	R	39' - 68'	LF	138		Possible conflict with replacement of storm drain pipe	Possible Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
35 116203	Roll Plot 1	Verizon	Rt 112 BL	Tel Cab			1405+70	L	66'	EA	1			No Conflict	ON ROW	Project	2		
36 116203	Roll Plot 1	Verizon	Rt 112 BL	Т			1405+70 - 1406+01	L	66' - 104'	LF	51			No Conflict	ON ROW	Project	2		
38 116203	Roll Plot 1	Verizon	Rt 112 BL	Р			1406+01	L	104'	EA	1			No Conflict	ON ROW	Project	2		
39 116203	Roll Plot 1	WVWS	Rt 112 BL	S	10"		1406+67 - 1408+01	R	34' - 37'	LF	134	None	see comment for Item 33	Possible Conflict	ON ROW	Project	4	IN-PLAN	Adjust location of proposed storm sewer to avoid manhole.
40 116203	Roll Plot 1	Roanoke Gas	Rt 112 BL	G	4"		1408+00 - 1412+00	L	39' - 40'	LF	403			No Conflict	ON ROW	Project	2		
41 116203	Roll Plot 1	City of Salem	Rt 112 BL	w	12"		1408+00 - 1412+00	L	36' - 36'	LF	403	4, 5, 6	Conflict to be avoided by limiting subgrade removal of existing bridge foundations to proximity and methods that will not damage existing water main	No Conflict	ON ROW	Project	1		
42 116203	Roll Plot 1	City of Salem	Rt 112 BL	Р			1408+05	L	49'	EA	1			No Conflict	ON ROW	Project	1		
43 116203	Roll Plot 1	Verizon	Rt 112 BL	Р			1408+20	L	84'	EA	1			No Conflict	ON ROW	Project	2		
44 116203	Roll Plot 1	Comcast	Rt 112 BL	CATV			1408+05 - 1411+54	L	49' - 57'	LF	362		Conflict #2: Line in conflict with new bridge substructure	In Conflict	ON ROW	Project	2	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.
45 116203	Roll Plot 1	Segra	Rt 112 BL	FO			1408+05 - 1411+54	L	49' - 57'	LF	360			No Conflict	ON ROW	Project	2		
46 116203	Roll Plot 1	Comcast	Rt 112 BL	CAFO			1408+05 - 1411+54	L	49' - 57'	LF	360			No Conflict	ON ROW	Project	2		
47 116203	Roll Plot 1	Zayo	Rt 112 BL	FO			1408+05 - 1411+54	L	49' - 57'	LF	359			No Conflict	ON ROW	Project	2		
48 116203	Roll Plot 1	Comcast	Rt 112 BL	CATV			1408+05 - 1411+54	L	49' - 57'	LF	368			No Conflict	ON ROW	Project	2		
49 116203	Roll Plot 1	Verizon	Rt 112 BL	т			1408+20 - 1411+54	L	84' - 57'	LF	342		Conflict #3: Line in conflict with new bridge substructure	In Conflict	ON ROW	Project	2	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.
50 116203	Roll Plot 1	City of Salem	Rt 112 BL	Е			1408+05 - 1411+54	L	49' - 57'	LF	375			No Conflict	ON ROW	Project	1		
51 116203	Roll Plot 1	wvws	Rt 112 BL	S	10"		1408+01 - 1410+78	R	37' - 38'	LF	274	7, 8, 9	Conflict to be avoided by limiting subgrade removal of existing bridge foundations to proximity and methods that will not damage existing sewer main	No Conflict	ON ROW	Project	4		
52 116203	Roll Plot 1	City of Salem	Rt 112 BL	Р			1411+54	L	57'	EA	1			No Conflict	ON ROW	Project	1		
53 116203	Roll Plot 1	WVWS	Rt 112 BL	S	10"		1410+78 - 1414+75	R	38'	LF	394	None	8.5 feet deep at manhole Sta. 1414+75	No Conflict	ON ROW	Project	4		
54 116203	Roll Plot 1	Roanoke Gas	Rt 112 BL	G	4"		1412+00 - 1418+24	L	40' - 35'	LF	629		Conflict #4: possible conflict with a replacement storm drain pipe and new pavement widening.	Possible Conflict	ON ROW	Project	2	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.
55 116203	Roll Plot 1	City of Salem	Rt 112 BL	w	12"		1412+00 - 1419+22	L	36' - 22'	LF	722	None	Possible conflict with proposed pavement section (proximity during construciton <2 feet) and proposed storm sewer pipe. TH #4 notes "exposed water main was corroded".	Possible Conflict	ON ROW	Project	1	IN-PLAN	Optional not shown on plans: Relocate ~450 LF existing 12" water main from approx Sta. 1411+00 to 1415+50 to avoid conflict with excavation for new pavement and proposed storm sewer. Assign risk percentage <100% for opportunity to avoid conflict & relocation.
56 116203	Roll Plot 1	City of Salem	Rt 112 BL	Р			1413+32	L	53'	EA	1			No Conflict	ON ROW	Project	1		
57 116203	Roll Plot 1	City of Salem	Rt 112 BL	Р			1415+09	L	55'	EA	1			No Conflict	ON ROW	Project	1		
58 116203	Roll Plot 1	WVWS	Rt 112 BL	S	10"		1410+73 - 1410+78	R	54' - 38'	LF	17			No Conflict	ON ROW	Project	4		
59 116203	Roll Plot 1	WVWS	Rt 112 BL	S	10"		1410+73 - 1410+76	R	54' - 92'	LF	38			No Conflict	ON ROW	Project	4		

#### UTILITY MATRIX

Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation.

Date of last update: 3/1/2021 **Cost Responsibility Reason Codes** 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility district or public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. -

LEFT, OFFSETS ROADWAY TYPE OF ON ROW, OFF ROW, PLAN UTILITY RIGHT, MEASUREMENT TEST CONFLICT COST Proiect Item QUANTITY ADDITIONAL DESCRIPTIVE REMARKS SIZE POLE NUMBER STATIONS FROM RESPONSIBI # UPC SHEET COMPANY CENTERLINE FACILITY HOLES EVALUATION OR IN EASEMENT OR UNITS CENTERLINE вотн Roll 60 116203 City of Salem Rt 112 BL Р 1416+44 L 54' ΕA 1 No Conflict ON ROW Project Plot 1 Roll 61 116203 City of Salem Rt 112 BL Р 1417+26 L 54' ΕA 1 No Conflict ON ROW Project Plot ' Roll 62 116203 City of Salem Rt 112 BL Р 1417+93 76' ΕA ON ROW L 1 No Conflict Proiect Plot ' Service pole for what appears to be a Roll 63 62' ΕA 116203 AFP Rt 112 BI Р 1418+26 1 1 OFF ROW Project No Conflict Plot 1 weather station Roll 64 116203 WVWS I-81 SB S 8" 531+77 - 534+45 L 105' LF 268 No Conflict ON ROW Project Plot 1 Roll 65 116203 WVWS I-81 SB S 8" 534+45 - 534+78 105' - 186 LF 86 No Conflict ON ROW Project L Plot ' Roll 66 116203 I-81 SB s 8" LF 180 WVWS 534+78 - 536+29 L 186' - 123' No Conflict ON ROW Project Plot 1 Roll 67 16203 WVWS I-81 SB s 8" 536+29 - 536+90 L 123' - 178' LF 82 No Conflict ON ROW Project Plot ' Roll 68 I-81 SB 8" LF 114 116203 WVWS S 536+90 - 537+54 L 178' - 275' OFF ROW Project No Conflict Plot 1 Roll 69 16203 VDOT I-81 NB FO 130+91 - 133+66 L 21 '- 22' LF 300 In Conflict ON ROW Project Plot 1 Roll 70 16203 VDOT I-81 NB FO 133+66 - 144+40 22' - 21 LF 1074 In Conflict ON ROW Project L Plot ' Roll 116203 VDOT I-81 NB FO 144+40 - 154+23 21' - 23' LF 983 ON ROW Project L In Conflict 7 Plot ' Roll 72 116203 VDOT I-81 NB FO 154+23 - 161+79 L 23' - 26' LF 756 In Conflict ON ROW Proiect Plot 1 Roll 73 116203 VDOT FO 26' - 27' 1 F Project I-81 NB 161+79 - 170+59 880 ON ROW L In Conflict Plot 1 Roll 74 116203 VDOT I-81 NB FO 170+59 - 183+31 L 27' - 28' LF 1272 In Conflict ON ROW Project Plot 1 Roll 75 116203 I-81 NB FO 183+31 - 195+18 28' - 19' LF 1187 VDOT L In Conflict ON ROW Project Plot ' Roll 70 16203 Citizens I-81 SB FO - 240 Coun 585+87 - 594+29 R 26 - 36' LF 842 In conflict with median roadway widening In Conflict ON ROW Utility Plot ' Roll R 77 16203 Citizens I-81 SB FO - 240 Coun 574+88 - 585+87 26' - 26' LF 1099 In Conflict ON ROW Utility In conflict with median roadway widening Plot ' Roll 78 R LF 16203 Citizens I-81 SB FO 1 - 240 Coun 548+03 - 574+88 26' - 26' 2685 In conflict with median roadway widening In Conflict ON ROW Utility Plot ' Roll 79 16203 I-81 SB FO - 240 Count В 26'L - 71'R LF 120 ON ROW Utility Citizens 548+03 In conflict with median roadway widening In Conflict Plot ' Roll RT 112 RPB Possible conflict with sound wall 80 16203 Citizens FO - 240 Coun 1100+66 - 1115+42 R 17' - 17' LF 1471 Possible Conflict ON ROW Utility Plot 1 BL construction **RT 112 RPB** Roll 81 116203 VDOT Е 145+35 - 146+60 В 46' L - 47' R LF 241 No Conflict ON ROW Project Plot ' RI Roll 82 116203 I-81 NB Е 1 F 333 Project City of Salem 144+77 - 148+09 R 46' - 45' No Conflict ON ROW Plot 1 Roll 83 116203 I-81 SB FO 559+35 - 559+74 В 156' R - 170' L LF 327 **Possible Conflict** ON ROW Utility Verizon Plot ' RT 112 RPB Roll 84 116203 City of Salem Р 1101+84 R 129' FA 1 No Conflict ON ROW Proiect Plot 1 BL Roll **RT 112 RPB** 85 16203 City of Salem Р 1107+53 R 109' ΕA 1 No Conflict ON ROW Project Plot ' BL Roll RT 112 RPB City of Salem Р 86 16203 1109+35 R 106' ΕA 1 No Conflict ON ROW Project Plot 1 BL Roll RT 112 RPE 87 116203 City of Salem Р 1111+86 R 86' ΕA No Conflict ON ROW Project 1 Plot ' Roll RT 112 RPB 88 116203 City of Salem Ρ 1118+76 R 76' ΕA 1 No Conflict ON ROW Project Plot 1 BL Roll I-81 SB 167' EA 89 116203 AEP Р 559+77 L 1 No Conflict ON ROW Utility Plot '

	•

counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. - Prior Rights.; 9.

LITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
	1		
	1		
	1		
	7		
	4		
	4		
	4		
	4		
	4		
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	1	OUT-of-PLAN	
		OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.
	1		
	1		
	1		
	1		
	1		

### UTILITY MATRIX

 Date of last update:
 3/1/2021
 Cost Responsibility Reason Codes

 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities located in city streets.; 3. - 33.2-307 (b) used on Arterial Projects for utilities owned by a county, city, town or projects for utilities owned by a county, city, town or projects for utilities owned by a county, city, town or projects for utilities owned by a county, city, town or projects for utilities owned by a county of projects for utilities owned by a county, city, town or projects for utilities owned by a county of projects for utilities owne

1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 4. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-301 used on secondary projects for utilities owned by county, city, town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. – Prior Rights.; 9. – Prior Rights.; 10 - (other) \_\_was just part of a recent VDOT relocation.

Item Project PLAN # UPC SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE	POLE NUMBER STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMEN UNITS	T QUANTITY	TEST HOLES	ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
90 116203 Roll Plot 1	AEP	I-81 SB	Р		559+39	L	158'	EA	1			No Conflict	ON ROW	Utility			
91 116203 Roll Plot 1	WVWS	RT 112 BL	S	8"	1417+61 - 1417+44	L	108' - 62'	LF	47			No Conflict	ON ROW	Project	4		
92 116203 Roll Plot 1	WVWS	RT 112 BL	S	8"	1417+44 - 1417+17	В	62' L - 39' R	LF	102			No Conflict	ON ROW	Project	4		
93 116203 Roll Plot 1	wvws	RT 112 BL	S	10"	1417+17 - 1414+74	R	39' - 34'	LF	237	None	Possible conflict with method of construction for proposed storm sewer pipes. Proposed vertical separation between existing gravity sewer and proposed storm sewer approx 6 inches.	Possible Conflict	ON ROW	Project	4	IN-PLAN	
94 116203 Roll Plot 1	WVWS	RT 112 BL	w	12"	1417+80 - 1408+55	В	27' L - 591' R	LF	1132			No Conflict	ON ROW	Project	4		
95 116203 Roll Plot 1	WVWS	I-81 SB	W	12"	537+16 - 540+11	L	132' - 167'	LF	304			No Conflict	ON ROW	Project	4		
96 116203 Roll Plot 1	WVWS	I-81 SB	w	12"	540+11 - 559+07	L	167' - 110'	LF	1919			No Conflict	ON ROW	Project	4		
97 116203 Roll Plot 1	WVWS	I-81 SB	w	12"	559+07 - 565+95	L	110' - 304'	LF	751			No Conflict	ON ROW	Project	4		
98 116203 Roll Plot 1	WVWS	RT 112 BL	G	Unknown	1418+20 - 1408+52	В	34' L - 634' R	LF	1170			No Conflict	ON ROW	Project	4		
99 116203 Roll Plot 1	AEP	RT 112 BL	Р		1417+57	R	242'	EA	1			No Conflict	OFF ROW	Project	7		
100 116203 Roll Plot 1	AEP	RT 112 BL	Р		1414+53	R	379'	EA	1			No Conflict	OFF ROW	Project	7		
101 116203 Roll Plot 1	AEP	RT 112 BL	Р		1413+10	R	432'	EA	1			No Conflict	OFF ROW	Project	7		
102 116203 Roll Plot 1	AEP	I-81 SB	Р		536+04	L	233'	EA	1			No Conflict	OFF ROW	Project	7		
103 116203 Roll Plot 1	AEP	I-81 SB	Р		536+92	L	210'	EA	1			No Conflict	OFF ROW	Project	7		
104 116203 Roll Plot 1	AEP	I-81 SB	Р		544+33	L	251'	EA	1			No Conflict	OFF ROW	Project	7		
105 116203 Roll Plot 1	AEP	I-81 SB	E		546+58	L	335'	EA	1			No Conflict	OFF ROW	Project	7		
106 116203 Roll Plot 1	AEP	I-81 SB	E		549+40	L	165'	EA	1			No Conflict	OFF ROW	Project	7		
107 116203 Roll Plot 1	Verizon	I-81 SB	Р		551+11	L	157'	EA	1			No Conflict	ON ROW	Utility			
108 116203 Roll Plot 1	Verizon	I-81 SB	Р		552+92	L	164'	EA	1			No Conflict	ON ROW	Utility			
109 116203 Roll Plot 1	Verizon	I-81 SB	Р		555+07	L	164'	EA	1			No Conflict	ON ROW	Utility			
110 116203 Roll Plot 1	AEP	I-81 SB	E		550+07	L	130'	EA	1			No Conflict	ON ROW	Utility			
111 116203 Roll Plot 1	AEP	I-81 SB	E		553+20	L	128'	EA	1			No Conflict	ON ROW	Utility			
112 116203 Roll Plot 1	AEP	I-81 SB	E		555+06	L	120'	EA	1			No Conflict	ON ROW	Utility			
113 116203 Roll Plot 1	AEP	I-81 SB	E		557+52	L	117'	EA	1			No Conflict	ON ROW	Utility			
114 116203 Roll Plot 1	AEP	I-81 SB	E		561+56	L	156'	EA	1			No Conflict	ON ROW	Utility			
115 116203 Roll Plot 1	AEP	I-81 SB	E		563+38	L	160'	EA	1			No Conflict	ON ROW	Utility			
116 116203 Roll Plot 1	AEP	I-81 SB	Р		564+15	L	193'	EA	1			No Conflict	ON ROW	Utility			
117 116203 Roll Plot 1	AEP	I-81 SB	Р		565+09	L	220'	EA	1			No Conflict	ON ROW	Utility			
118 116203 Roll Plot 1	AEP	I-81 SB	Р		564+20	L	194'	EA	1			No Conflict	ON ROW	Utility			
119 116203 Roll Plot 1	AEP	I-81 SB	Р		565+20	L	105'	EA	1			No Conflict	ON ROW	Utility			
120 116203 Roll Plot 1	City of Salem	Rt 112 RPB BL	Р		1101+94	R	129'	EA	1			No Conflict	ON ROW	Project	1		
121 116203 Roll Plot 1	City of Salem	Rt 112 RPB BL	Р		1107+60	R	109'	EA	1			No Conflict	ON ROW	Project	1		

1	

### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes 1. - 33.2-348 used on urban projects for utilities owned by a county, city, town or public utility authority, public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 3. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-300 used on secondary projects for utilities owned by county, city, town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. - Prior Rights.; 9. - Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation.

ltem Project # UPC	PLAN SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE POLE NUMBER	STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMEN UNITS	QUANTITY	TEST HOLES ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
122 116203	Roll Plot 1	City of Salem	Rt 112 RPB BL	Р		1109+36	R	107'	EA	1		No Conflict	ON ROW	Project	1		
123 116203	Roll Plot 1	City of Salem	Rt 112 RPB BL	Ρ		1111+58	R	86'	EA	1		No Conflict	ON ROW	Project	1		
124 116203	Roll Plot 1	VDOT	Rt 112 RPB BL	Ρ		1115+12	R	36'	EA	1		No Conflict	ON ROW	Project			
125 116203	Roll Plot 1	City of Salem	Rt 112 RPB BL	Р		1118+81	R	151'	EA	1		No Conflict	ON ROW	Project	1		
126 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	594+29 - 597+74	В	36'R - 45'L	LF	376	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
127 116203	Roll Plot 2	VDOT	I-81 SB	FO		594+52 - 599+40	R	54' - 53'	LF	516		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
128 116203	Roll Plot 2	Citizens	I-81 SB	T Ped		597+74	L	45'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
129 116203	Roll Plot 2	Citizens	I-81 SB	Ρ		597+74	L	47'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
130 116203	Roll Plot 2	Citizens	I-81 SB	Ρ		598+63	L	41'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
131 116203	Roll Plot 2	Citizens	I-81 SB	T Ped		598+64	L	43'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
132 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	598+64 - 608+80	В	43'L - 27'R	LF	1059	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
133 116203	Roll Plot 2	VDOT	I-81 SB	FO		599+40 - 619+72	R	53' - 47'	LF	2034		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
134 116203	Roll Plot 2	City of Salem	I-81 NB	Ρ		197+72	R	184'	EA	1		No Conflict	ON ROW	Project	2		
135 116203	Roll Plot 2	City of Salem	I-81 NB	Е		197+72 - 198+91	В	184'R - 162'L	LF	367		No Conflict	ON ROW	Project	2		
136 116203	Roll Plot 2	Comcast	I-81 NB	CATV		198+11 - 198+91	В	79'R - 162'L	LF	256	Google Earth street view does not show it	No Conflict	ON ROW	Utility			
137 116203	Roll Plot 2	City of Salem	I-81 NB	Ρ		193+41	R	114'	EA	1		No Conflict	OFF ROW	Project	7		
138 116203	Roll Plot 2	City of Salem	I-81 NB	Р		195+88	R	155'	EA	1		No Conflict	OFF ROW	Project	7		
139 116203	Roll Plot 2	City of Salem	I-81 NB	Ρ		197+86	R	138'	EA	1	has streetlight	No Conflict	ON ROW	Project	2		
140 116203	Roll Plot 2	City of Salem	I-81 NB	Ρ		198+28	R	138'	EA	1	Guy Pole Only	No Conflict	ON ROW	Project	2		
141 116203	Roll Plot 2	City of Salem	I-81 NB	W	6"	197+71 - 198+00	R	233' - 139'	LF	99	None Possible conflict with existing 6 water main. Proposed vertical separation approx 26 inches	Possible Conflict	ON ROW	Project	1	IN-PLAN	
142 116203	Roll Plot 2	City of Salem	I-81 NB	S	8"	197+72 - 197+87	R	275' - 233'	LF	44	Existing manhole within pavement mill & overlay area.	Possible Conflict	ON ROW	Project	1	IN-PLAN	
143 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	608+80 - 614+45	R	27' - 29'	LF	566	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
144 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	614+45 - 619+80	В	29'R - 69'L	LF	601	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
145 116203	Roll Plot 2	Citizens	I-81 SB	T Ped		619+80	L	69'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
146 116203	Roll Plot 2	Citizens	I-81 SB	Ρ		619+78	L	69'	EA	1	relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
147 116203	Roll Plot 2	VDOT	I-81 SB	FO		619+72 - 621+32	R	47' - 46'	LF	185		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
148 116203	Roll Plot 2	City of Salem	I-81 SB	W		620+19 - 620+27	L	187'	LF	7	spur to hydrant	No Conflict	ON ROW	Project	1		
149 116203	Roll Plot 2	City of Salem	Rte 619	W	8"	34+54 - 39+37	L	12' - 13'	LF	487	13, 14, 15         Possible conflict between existing water main and proposed demolition of exsting bridge piers	Possible Conflict	ON ROW	Project	1	IN-PLAN	Horizontal clearance betewen edge of bridge column and water main ~6-8 feet. Protect during construction to avoid conflict.

-		

#### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility district or public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (a) used on Interstate and Primary projects in city streets.; 4. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (b) used on Interstate in city streets.; 5. - 33.2-307 (b) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. - 33.2-307 (c) used on Interstate and Primary projects in city streets.; 5. -

Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation. LEFT, OFFSETS ROADWAY TYPE OF ON ROW, OFF ROW, PLAN UTILITY RIGHT, MEASUREMENT TEST CONFLICT COST Proiect Item QUANTITY ADDITIONAL DESCRIPTIVE REMARKS SIZE POLE NUMBER STATIONS FROM RESPONSIBIL # UPC SHEET COMPANY CENTERLINE FACILITY HOLES EVALUATION OR IN EASEMENT OR UNITS CENTERLINE вотн Roll 150 116203 Roanoke Gas Rte 619 G 3" 34+50 - 39+36 В 12'L - 12'R LF 517 No Conflict ON ROW Project Plot 2 Roll 151 116203 City of Salem Rte 619 s 8" 34+50 - 34+96 R 14' - 5' LF 47 No Conflict ON ROW Project Plot 2 Roll 152 116203 City of Salem Rte 619 8" 34+96 - 37+40 R LF 242 19, 20, 21 ON ROW S 5' No Conflict Proiect Plot 2 Roll 153 City of Salem LF 202 116203 Rte 619 S 8" 37+40 - 39+45 R 5' - 42' Project No Conflict ON ROW Plot 2 Roll 154 116203 Verizon Rte 619 т 34+50 - 34+87 R 14' - 28' LF 43 No Conflict ON ROW Project Plot 2 Roll 155 16203 AEP Rte 619 Р 34+87 R 31' ΕA 1 No Conflict OFF ROW Project Plot 2 Roll Conflict #5: Line in possible conflict with 156 R LF 324 116203 Verizon Rte 619 т 34+87 - 38+14 28' - 35' **Possible Conflict** ON ROW Project Plot 2 new MSE wall Roll 157 116203 Comcast Rte 619 CATV 34+87 - 37+67 R 31' - 11' LF 290 ON ROW Project No Conflict Plot 2 Roll 158 116203 AFP Rte 619 R LF 344 E 34+87 - 38+20 31' - 34' No Conflict ON ROW Project Plot 2 Roll 159 116203 Comcast Rte 619 CATV 34+87 - 38+20 R 31' - 34' LF 339 No Conflict ON ROW Project Plot 2 Roll 160 16203 CAFO Comcast Rte 619 34+87 - 38+20 R 31' - 34' LF 341 No Conflict ON ROW Project Plot 2 Roll 161 116203 Verizon Rte 619 R 35' - 18' LF 135 Т 38+14 - 39+48 ON ROW Proiect No Conflict Plot 2 Roll 162 AFP Rte 619 Р R 34' EA 1 OFF ROW 116203 38+20 No Conflict Project Plot 2 Roll relocation needed due to adjacent I-81 SB 163 116203 71' EA In Conflict Citizens T Ped 620+89 L 1 ON ROW Utility Plot 2 conflicts needing relocations relocation needed due to adjacent Roll 164 16203 Citizens I-81 SB Р 620+89 L 72' ΕA In Conflict ON ROW Utility 1 Plot 2 conflicts needing relocations Roll Utility 165 116203 Citizens I-81 SB FO 1 - 240 Coun 620+89 - 645+38 в 71'L - 14'R LE 2492 In conflict with median roadway widening In Conflict ON ROW Plot 2 Roll 166 116203 City of Salem I-81 NB Р 221+86 R 115' ΕA 1 No Conflict OFF ROW Project Plot 2 Roll 167 116203 VDOT I-81 SB FO 621+32 - 634+13 R 46' - 39' LF 1281 In Conflict ON ROW Project Plot 2 Roll 168 16203 City of Salem I-81 NB Р 224+48 R 112' EA No Conflict OFF ROW 1 Proiect Plot 2 Roll 169 116203 I-81 NB Т 225+86 - 225+91 R 165' - 112' LF 53 No Conflict OFF ROW Verizon Proiect Plot 2 Roll 170 R 108' ΕA OFF ROW 116203 City of Salem I-81 NB P 225+94 1 No Conflict Project Plot 2 Roll 171 116203 City of Salem I-81 NB Р 227+22 R 109' ΕA 1 No Conflict OFF ROW Project Plot 2 Roll 172 116203 City of Salem I-81 NB Р 228+46 R 112' ΕA 1 No Conflict OFF ROW Project Plot 2 Roll 173 City of Salem 116203 I-81 NB Р 229+81 R 112' EA 1 No Conflict OFF ROW Project Plot 2 Roll 174 116203 City of Salem I-81 NB Р R 118' EA 1 OFF ROW Project 230+53 No Conflict Plot 2 175 Roll 116203 City of Salem I-81 NB Е 231+72 - 231+75 R 170' - 129' LF 42 No Conflict OFF ROW Project Plot 2 Roll 176 116203 City of Salem I-81 NB Р 231+75 R 129' ΕA 1 No Conflict OFF ROW Project Plot 2 Roll 177 116203 City of Salem I-81 NB Р 232+88 R 138' EA 1 No Conflict OFF ROW Project Plot 2 Roll 178 116203 634+13 - 645+74 R LF 1162 VDOT I-81 SB FO 39' - 39' In Conflict ON ROW Proiect Plot 2 Roll 179 16203 City of Salem I-81 NB Р 235+37 R 137 ΕA 1 No Conflict OFF ROW Project Plot 2 Roll Sta 642+34 possible conflict with 180 116203 City of Salem I-81 SB W 8" 641+85 - 644+18 В 237'R - 185'L LF 505 **Possible Conflict** ON ROW Project Plot 2 proposed storm sewer drop inlet Roll 182' - 194' 18 16203 City of Salem I-81 SB W 8" 641+88 - 644+86 R LF 300 No Conflict ON ROW Project Plot 2

counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. - Prior Rights.; 9.

LITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY					
	2							
	1							
	1							
	1							
	2							
	7							
	2	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.					
	2							
	2							
	2							
	2							
	2							
	7							
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.					
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.					
	9	OUT-of-PLAN	Traffic control, lay down areas, and equipment parking areas					
	1							
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default					
	1							
	7							
	1							
	1							
	1							
	1							
	1							
	1							
	1							
	1							
	N/A	IN-PLAN	VDOT facilities are in-plan work items by default					
	1							
	1	IN-PLAN						
	1							

### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes

1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.: 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities located in city streets.: 3. - 33.2-307 (b) used on Arterial Projects for utilities owned by a county, city, town or u

1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 3. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-300 used on Arterial Projects for utilities owned by county, city, town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. - Prior Rights.; 9. - Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation.

ltem #	Project PLAN UPC SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE	POLE NUMBER STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMENT UNITS QU	UANTITY	TEST HOLES ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
182	116203 Roll Plot 2	City of Salem	I-81 SB	W	8"	643+34 - 644+68	В	85'R - 182'L	LF	298	one. Online GIS shows one water main in	Possible Conflict	ON ROW	Project	1	IN-PLAN	
183	116203 Roll Plot 2	AEP	I-81 SB	Р		644+44	R	204'	EA	1		No Conflict	ON ROW	Project	2		
184	116203 Roll Plot 2	Verizon	I-81 SB	T Ped		644+47	R	204'	EA	1		No Conflict	ON ROW	Project	2		
185	116203 Roll Plot 2	AEP	I-81 SB	Р		644+48	R	199'	EA	1		No Conflict	ON ROW	Project	2		
186	116203 Roll Plot 2	Verizon	I-81 SB	Ţ		644+47 - 644+67	R	204' - 238'	LF	53		No Conflict	ON ROW	Project	2		
187	116203 Roll Plot 2	Verizon	I-81 SB	FO		644+47 - 646+42	В	204'R - 125'L	LF	385		No Conflict	ON ROW	Project	2		
188	116203 Roll Plot 2	Verizon	I-81 SB	Т		644+47 - 646+67	В	204'R - 185'L	LF	452		No Conflict	ON ROW	Project	2		
189	116203 Roll Plot 2	AEP	I-81 SB	Р		644+68	R	235'	EA	1		No Conflict	ON ROW	Project	2		
190	116203 Roll Plot 2	City of Salem	I-81 SB	W	8"	644+60 - 647+00	В	238'R - 177'L	LF	480		No Conflict	ON ROW	Project	1		
191	116203 Roll Plot 2	Verizon	I-81 SB	T Ped		646+42	L	125'	EA	1		No Conflict	ON ROW	Project	2		
192	116203 Roll Plot 2	Verizon	I-81 SB	T Ped		646+65	L	185'	EA	1		No Conflict	ON ROW	Project	2		
193	116203 Roll Plot 2	AEP	I-81 SB	Р		646+66	L	186'	EA	1		No Conflict	OFF ROW	Project	7		
194	116203 Roll Plot 2	Verizon	I-81 SB	FO		646+42 - 646+89	L	125' - 92'	LF	58		No Conflict	ON ROW	Project	2		
195	116203 Roll Plot 2	Zayo	I-81 SB	FO		646+66 - 646+78	L	186' - 95'	LF	105		No Conflict	ON ROW	Project	2		
196	116203 Roll Plot 2	City of Salem	I-81 SB	E		646+80 - 647+39	L	86' - 128'	LF	75		No Conflict	ON ROW	Project	1		
197	116203 Roll Plot 2	City of Salem	I-81 SB	Р		647+39	L	128'	EA	1		No Conflict	ON ROW	Project	1		
198	116203 Roll Plot 2	Verizon	I-81 SB	Т		646+66 - 650+71	L	186' - 123'	LF	432		No Conflict	OFF ROW	Project	7		
199	116203 Roll Plot 2	Verizon	I-81 SB	Т		646+89 - 650+71	L	92' - 123'	LF	406	2 parallel lines shown in plans	No Conflict	OFF ROW	Project	7		
200	116203 Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	645+38 - 645+83	R	14' - 13'	LF	46	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
201	116203 Roll Plot 2	VDOT	I-81 SB	FO		645+74 - 655+39	R	39' - 51'	LF	960		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
202	116203 Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	645+83 - 666+53	R	13' - 26'	LF	2081	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
203	116203 Roll Plot 2	Verizon	I-81 SB	Т		650+71 - 650+80	L	123' - 165'	LF	44		No Conflict	OFF ROW	Project	7		
204	116203 Roll Plot 2	City of Salem	I-81 SB	E		650+82 - 652+18	L	164' - 121'	LF	190		No Conflict	OFF ROW	Project	1		
205	116203 Roll Plot 2	City of Salem	I-81 SB	E		650+86 - 652+18	L	164' - 121'	LF	184		No Conflict	OFF ROW	Project	1		
206	116203 Roll Plot 2	VDOT	I-81 SB	FO		655+39 - 666+41	R	51' - 42'	LF	1101		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
207	116203 Roll Plot 2	VDOT	I-81 SB	FO		666+41 - 677+60	R	42' - 41'	LF	1119		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
208	116203 Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	666+53 - 678+97	R	26' - 42'	LF	1245	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
209	116203 Roll Plot 2	Verizon	I-81 SB	Р		670+19	L	96'	EA	1		No Conflict	OFF ROW	Project	7		
210	116203 Roll Plot 2	Verizon	I-81 SB	Т		670+19 - 671+05	В	96'L - 181'R	LF	297		No Conflict	OFF ROW	Project	7		
211	116203 Roll Plot 2	VDOT	I-81 SB	FO		677+60 - 683+06	R	41' - 152'	LF	565		In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
212	116203 Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count	678+97 - 685+46	R	42' - 136'	LF	714	In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.

### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 4. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-301 used on secondary projects for utilities owned by county.; 5. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. – Other County and for utilities owned by a sugnary of a recent VDOT relocation.

ltem Project # UPC	PLAN SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE	POLE NUMBER	STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMENT UNITS	QUANTITY	TEST HOLES	ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
213 116203	Roll Plot 2	Roanoke Gas	Rte 311 RPD	G			2302+13 - 2304+23	R	88' - 126'	LF	282			No Conflict	OFF ROW	Project	7		
214 116203	Roll Plot 2	AEP	Rte 311 RPD	Ρ			2303+16	R	46'	EA	1			No Conflict	ON ROW	Utility			
215 116203	Roll Plot 2	AEP	Rte 311 RPD	Р			2302+30	R	62'	EA	1			No Conflict	ON ROW	Utility			
216 116203	Roll Plot 2	VDOT	Rte 311 LPD	Е			2202+70	В	30'L - 17'R	LF	47			No Conflict	ON ROW	Project			
217 116203	Roll Plot 2	VDOT	Rte 311 LPD	Е			2202+70 - 2205+21	R	17' - 95'	LF	222			No Conflict	ON ROW	Project			
218 116203	Roll Plot 2	VDOT	I-81 SB	FO			683+06 - 686+78	R	152' - 118'	LF	378			No Conflict	ON ROW	Project			
219 116203	Roll Plot 2	VDOT	I-81 SB	Е			684+28 - 686+81	R	93' - 362'	LF	422			No Conflict	ON ROW	Project			
220 116203	Roll Plot 2	VDOT	I-81 SB	FO			684+18 - 686+78	R	94' - 118'	LF	271			No Conflict	ON ROW	Project			
221 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count		685+46 - 686+85	R	136' - 132'	LF	155			No Conflict	ON ROW	Utility	9		
222 116203	Roll Plot 2	VDOT	I-81 SB	FO			686+78 - 686+85	R	118' - 132'	LF	16			No Conflict	ON ROW	Project			
223 116203	Roll Plot 2	WVWA	I-81 SB	S	8"		685+41 - 685+46	R	228' - 324'	LF	97			No Conflict	ON ROW	Project	4		
224 116203	Roll Plot 2	WVWA	I-81 SB	S	8"		685+41 - 685+62	R	228' - 146'	LF	84			No Conflict	ON ROW	Project	4		
225 116203	Roll Plot 2	WVWA	I-81 SB	S	8"		685+62 - 685+66	В	146'R - 139'L	LF	286			No Conflict	ON ROW	Project	4		
226 116203	Roll Plot 2	WVWA	I-81 SB	S	8"		685+54 - 685+66	L	212' - 139'	LF	73			No Conflict	ON ROW	Project	4		
227 116203	Roll Plot 2	WVWA	I-81 SB	S	8"		685+54 - 685+80	L	212' - 438'	LF	73			No Conflict	ON ROW	Project	4		
228 116203	Roll Plot 2	WVWA	I-81 SB	W	12"		685+55 - 686+68	В	272'R - 470'L	LF	759			No Conflict	ON ROW	Project	4		
229 116203	Roll Plot 2	VDOT	I-81 SB	Е			685+14 - 686+25	L	238' - 423'	LF	243			No Conflict	ON ROW	Project			
230 116203	Roll Plot 2	VDOT	I-81 SB	Е			686+16 - 686+19	R	252' - 195'	LF	57			No Conflict	ON ROW	Project			
231 116203	Roll Plot 2	City of Salem	I-81 SB	W	8"		686+24 - 686+30	R	248' - 176'	LF	73			No Conflict	ON ROW	Project	1		
232 116203	Roll Plot 2	City of Salem	I-81 SB	W	12"		686+30 - 692+71	R	176' - 177'	LF	642			No Conflict	ON ROW	Project	1		
233 116203	Roll Plot 2	Roanoke Gas	I-81 SB	G	3"		686+72 - 688+34	В	263'R - 388'L	LF	734			No Conflict	ON ROW	Project	2		
234 116203	Roll Plot 2	VDOT	I-81 SB	FO			686+78 - 686+82	В	118'R - 73'L	LF	192			In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
235 116203	Roll Plot 2	VDOT	I-81 SB	FO			686+82 - 688+91	L	73' - 85'	LF	213			No Conflict	ON ROW	Project			
236 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count		686+85 - 688+46	R	132' - 144'	LF	167			No Conflict	ON ROW	Utility	9		
237 116203	Roll Plot 2	Verizon	I-81 SB	Р			688+26	R	246'	EA	1			No Conflict	OFF ROW	Project	7		
238 116203	Roll Plot 2	Verizon	I-81 SB	Т			688+26 - 688+32	В	246'R - 195'L	LF	442			No Conflict	ON ROW	Project	2		
239 116203	Roll Plot 2	Verizon	I-81 SB	Т			688+26 - 689+73	R	246' - 213'	LF	159			No Conflict	ON ROW	Project	2		
240 116203	Roll Plot 2	Citizens	I-81 SB	FO	1 - 240 Count		688+46 - 692+65	R	144' - 42'	LF	474		In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
241 116203	Roll Plot 3	Citizens	I-81 SB	FO	1 - 240 Count		692+65 - 703+92	R	42' - 49'	LF	1125		In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Traffic control, lay down areas, and equipment parking areas
242 116203	Roll Plot 3	City of Salem	I-81 SB	Р			698+92	R	206'	EA	1			No Conflict	ON ROW	Project	1		
243 116203	Roll Plot 3	City of Salem	I-81 SB	Р			701+26	R	205'	EA	1			No Conflict	ON ROW	Project	1		
244 116203	Roll Plot 3	VDOT	I-81 SB	FO			701+76	В	31'R - 40'L	LF	71			In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
245 116203	Roll Plot 3	VDOT	I-81 SB	FO			701+76 - 702+00	L	40' - 191'	LF	153			In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default

### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes 1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility district or public utility authority.; 2. - 33.2-307 (a) used on Interstate in cities or towns for utilities owned by a county, city, town or public utility authority located in existing streets.; 4. - 33.2-308 used on Interstate and Primary projects in counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town extending into any county.; 5. - 33.2-301 used on secondary projects for utilities owned by county.; 5. - 33.2-1014 used for utilities located on private property.; 8. – Prior Rights.; 9. – Other County and for utilities owned by a sugnary of a recent VDOT relocation.

ltem Projec # UPC	PLAN SHEET	UTILITY COMPANY	ROADWAY CENTERLINE	TYPE OF FACILITY	SIZE	POLE NUMBER	STATIONS	LEFT, RIGHT, OR BOTH	OFFSETS FROM CENTERLINE	MEASUREMENT UNITS	QUANTITY	TEST HOLES	ADDITIONAL DESCRIPTIVE REMARKS	CONFLICT EVALUATION	ON ROW, OFF ROW, OR IN EASEMENT	COST RESPONSIBILITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
246 116203	Roll Plot 3	VDOT	I-81 SB	FO			701+76 - 703+30	R	31' - 39'	LF	152			In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
247 116203	Roll Plot 3	VDOT	I-81 SB	FO			703+30 - 703+94	R	39' - 44'	LF	62			In Conflict	ON ROW	Project	N/A	IN-PLAN	VDOT facilities are in-plan work items by default
248 116203	Roll Plot 3	City of Salem	I-81 SB	Р			702+48	R	202'	EA	1			No Conflict	ON ROW	Project	1		
249 116203	Roll Plot 3	Citizens	I-81 SB	FO	1 - 240 Count		703+92 - 735+13	R	49' - 57'	LF	3117		In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
250 116203	Roll Plot 3	City of Salem	I-81 SB	Р			707+52	R	278'	EA	1			No Conflict	ON ROW	Project	1		
251 116203	Roll Plot 3	WVWA	I-81 SB	w			734+59 - 735+78	L	151' - 109'	LF	124			No Conflict	ON ROW	Project	4		
252 116203	Roll Plot 3	Roanoke Gas	I-81 SB	G	4"		735+30 - 737+30	L	151' - 69'	LF	213			No Conflict	ON ROW	Utility			
253 116203	Roll Plot 3	WVWA	I-81 SB	W	8"		735+55 - 736+66	L	151' - 70'	LF	144			No Conflict	ON ROW	Project	4		
254 116203	Roll Plot 3	WVWA	I-81 SB	W	2"		735+69 - 735+85	L	165' - 106'	LF	62			No Conflict	ON ROW	Project	4		
255 116203	Roll Plot 3	WVWA	I-81 SB	S	8"		735+91 - 736+88	L	140' - 53'	LF	127			No Conflict	ON ROW	Project	4		
256 116203	Roll Plot 3	WVWA	I-81 SB	W	12"		736+66 - 737+27	В	175'L - 184'R	LF	391			No Conflict	ON ROW	Project	4		
257 116203	Roll Plot 3	Citizens	I-81 SB	FO	1 - 240 Count		735+13 - 735+30	R	57' - 154'	LF	106		In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
258 116203	Roll Plot 3	Citizens	I-81 SB	Р			735+30	R	154'	EA	1		relocation needed due to adjacent conflicts needing relocations	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
259 116203	Roll Plot 3	Comcast	I-81 SB	CATV			737+07 - 737+08	В	149'L - 250'R	LF	399			No Conflict	ON ROW	Utility			
260 116203	Roll Plot 3	WVWA	I-81 SB	S	8"		736+80 - 736+83	L	103' - 177'	LF	74			No Conflict	ON ROW	Project	4		
261 116203	Roll Plot 3	WVWA	I-81 SB	S	8"		736+80 - 736+88	L	103' - 53'	LF	51			No Conflict	ON ROW	Project	4		
262 116203	Roll Plot 3	WVWA	I-81 SB	S	8"		736+88 - 737+31	В	53'L - 173'R	LF	228			No Conflict	ON ROW	Project	4		
263 116203	Roll Plot 3	WVWA	I-81 SB	S	8"		736+88 - 736+95	L	53' - 176'	LF	123			No Conflict	ON ROW	Project	4		
264 116203	Roll Plot 3	Verizon	I-81 SB	т			737+05 - 737+16	В	154'L - 259'R	LF	414			No Conflict	ON ROW	Utility			
265 116203	Roll Plot 3	Comcast	I-81 SB	CATV			737+05 - 737+16	В	154'L - 259'R	LF	417			No Conflict	ON ROW	Utility			
266 116203	Roll Plot 3	AEP	I-81 SB	Е			737+14 - 737+25	В	154'L - 258'R	LF	413			No Conflict	ON ROW	Utility			
267 116203	Roll Plot 3	WVWA	I-81 SB	W	8"		736+69 - 737+26	L	73' - 60'	LF	58			No Conflict	ON ROW	Project	4		
268 116203	Roll Plot 3	WVWA	I-81 SB	W	8"		737+26 - 737+29	В	68'L - 144'R	LF	213			No Conflict	ON ROW	Project	4		
269 116203	Roll Plot 3	Roanoke Gas	I-81 SB	G	4"		736+90 - 737+30	L	176' - 69'	LF	137			No Conflict	ON ROW	Utility			
270 116203	Roll Plot 3	Roanoke Gas	I-81 SB	G	12"		737+53 - 737+62	В	110'L - 210'R	LF	321			No Conflict	ON ROW	Utility			
271 116203	Roll Plot 3	Roanoke Gas	I-81 SB	G	12"		737+57 - 748+75	L	120' - 124'	LF	1072			No Conflict	OFF ROW	Project	7		
272 116203	Roll Plot 3	City of Salem	I-81 SB	Р			740+26	R	276'	EA	1			No Conflict	OFF ROW	Project	1		
273 116203	Roll Plot 3	City of Salem	I-81 SB	Р			742+84	R	189'	EA	1			No Conflict	ON ROW	Project	1		
274 116203	Roll Plot 3	City of Salem	I-81 SB	Р			742+86	R	219'	EA	1			No Conflict	OFF ROW	Project	1		
275 116203	Roll Plot 3	Citizens	I-81 SB	FO	1 - 240 Count		742+84 - 756+44	R	189' - 33'	LF	1492		In conflict with median roadway widening	In Conflict	ON ROW	Utility	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
276 116203	Roll Plot 3	City of Salem	I-81 SB	Р			745+56	R	188'	EA	1			No Conflict	OFF ROW	Project	1		

#### UTILITY MATRIX

Date of last update: 3/1/2021 Cost Responsibility Reason Codes

1. - 33.2-348 used on urban projects for utilities owned by a municipality, public utility authority.; 2. - 33.2-307 (a) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county, city, town or public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county of the public utility authority.; 2. - 33.2-307 (b) used on Interstate and Primary projects for utilities owned by a county of the public counties for all utilities owned by a county or political subdivision of the state or county and for water or sanitary sever owned by a city or town, authority or district.; 6. - 33.1-1701 used on certain bond projects; 7. - 33.2-330 used on private property.; 8. - Prior Rights.; 9. Prior Agreements (provide date).; 10 - (other) \_\_was just part of a recent VDOT relocation. LEFT, OFFSETS Project PLAN UTILITY ROADWAY TYPE OF MEASUREMENT TEST CONFLICT ON ROW, OFF ROW, COST RIGHT, Item QUANTITY ADDITIONAL DESCRIPTIVE REMARKS SIZE POLE NUMBER STATIONS FROM # UPC SHEET COMPANY CENTERLINE FACILITY HOLES EVALUATION OR IN EASEMENT RESPONSIBIL OR UNITS CENTERLINE вотн Roll 277 116203 City of Salem I-81 SB OFF ROW Р 747+35 R 253' EA 1 No Conflict Project Plot 3 Roll Plot 3 Trans. 278 116203 City of Salem I-81 SB 747+80 R 263' EA 1 No Conflict OFF ROW Project Tower Roll 279 116203 Roanoke Gas Rte 419 RPD G 12" 3304+00 - 3313+76 R 179' - 86' LF 985 No Conflict OFF ROW Project Plot 3 Roll 280 City of Salem 116203 I-81 SB Р 756+37 R 213' EA 1 ON ROW No Conflict Project Plot 3 Roll 281 EA 116203 City of Salem I-81 SB Р 758+54 L 163' 1 No Conflict OFF ROW Project Plot 3 Roll 282 1 - 240 Count R LF 116203 Citizens I-81 SB FO 756+44 - 776+00 33' - 9' 1958 In conflict with median roadway widening In Conflict ON ROW Utility Plot 3 Roll Trans. 283 City of Salem 156' EA OFF ROW 116203 I-81 SB 758+91 L 1 No Conflict Project Plot 3 Tower Roll 284 WVWA I-81 SB 761+88 - 762+03 285'R - 111'L LF 395' ON ROW 116203 S 8" в No Conflict Project Plot 3 Roll 285 Р ΕA 116203 City of Salem I-81 NB 198+91 L 162' 1 No Conflict ON ROW Project Plot 2 Roll 286 116203 City of Salem I-81 NB Р 200+22 301' ΕA 1 No Conflict ON ROW Project L Plot 2 Roll Conflict #6: Pole in conflict with new basir 287 116203 202+98 EA City of Salem I-81 NB Ρ 343' 1 In Conflict ON ROW Project L Plot 2 access pavement

LITY	COST RESPONSIBILITY REASON CODE	IN-PLAN or OUT- of-PLAN RELOCATION WORK	DESCRIPTION OF MITIGATION MEASURES THAT D-B CAN PERFORM FOR UTILITY
	1		
	1		
	7		
	1		
	1		
	9	OUT-of-PLAN	Utility is interested in a combined relocation with VDOT fibers. Traffic control, lay down areas, and equipment parking areas can be provided by Design-Builder.
	1		
	4		
	7		
	7		
	7	OUT-of-PLAN	Assistance with traffic control and providing an area to park equipment.



TAB 3 Proposal Schedule

C00116203DB108		I-81 Widening MM 136.6 - MM 141.8	Proposal Schedu	lule 03-01-21 10:45
Activity ID	Activity Name	Original Start Duration	Finish	2021         2022         2023         2024         2025         2026         2027         2028         2029         2030           Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q
😑 I-81 Widening MM 1	36.6 - MM 141.8 Proposal Schedule	949 03-03-21	01-15-26	V 01-15-26, I-81 Widening MM 136.6 - MM 141.8 Proposal Sci
		1780 03-03-21	01-15-26	v 01-15-26, MILESTONES
		0 02 02 21		
		0 05-03-21		
		0 03-24-21	01 15 26*	
		262 05-24-21	09-15-22	
			00 10 22	
	Scope Validation	120 05-24-21	09-20-21	
	Prepare Baseline Schedule	90 05-24-21	08-21-21	Prepare Baseline Schedule
	Prepare Health & Safety Plan	4 05-24-21	05-27-21	I Prepare Health & Safety Plan
	Submit Health & Safety Plan	1 05-28-21	05-28-21	I Submit Health & Safety Plan
	Submit Deseline Schedule	21 03-29-21	00-18-21	
			08-22-21	I VDOT Approved of Departure Calendrice
	VDOT Approval of Baseline Schedule	21 06-23-21	09-12-21	
		21 05-24-21 5 05-24-21	05-29-21	
D1010	Prepare QAVQC Plan	5 05-24-21	05-28-21	L Submit 04/00 Plan
D1020			06-01-21	
D1030	Povice and Resubmit OA/OC Plan	5 06 22 21	06-22-21	L Pourise and Populari
Di040		172 05 24 21	02.01.22	
	Droporty Our or Notification Lattern	173 05-24-21	02-01-22	Property Output Netification I attent
D1050	Supplemental Suprey & Test Holes	<u> </u>	07-06-21	
D1080	Supplemental Survey & Test Holes	60 07-07-21	09-29-21	Supplemental Survey & lest Holes
D1070		65 07-28-21	10-21-21	
D1080	Dight of Way Sheet Propagation	05 07-07-21	10-06-21	
D1120	Right of Way Sheet Pleparation	21 10-22-21	02.01.02	
	Right of Way Stakeout	21 12-30-21	02-01-22	
	Evaluration Plan	10 05-24-21	01-20-22	
D1140		21 06 09 21	06.28.21	
D1140	Litility Clearance Landowner Netifications and Permits	30 05 24 21	07.06.21	
D1160	Contractorical Subsurface Evaluation	65 07 07 21	10.06.21	
D1180		65 07-07-21	10-00-21	Control Subsulace Exploration
D1180	Shoulder Strengthoning Popert	30 07-21-21	09 17 21	Gevieulinical Labolatory lesting
D1180	04/0C Shoulder Strengthening Report	1 09 19 21	08 18 21	L OM/OC Shoulder Strengthoning Report
D1300	VPOT Poview of Shoulder Strengthoning Poport	21 00-10-21	00.08.21	I VDOT Paview of Shoulder Strengthening Penet.
D1200	Submit Boying Shoulder Strengthoning Report	10 00 09 21	09-00-21	Subtrit Baliand Chaulder Strengthaning Report
D1210	Ridge Costebrical Reports	80 09 04 21	11 20 21	
D1220		10 11-30-21	12-13-21	
D1230	VDOT Review Bridge Geotechnical Reports	21 12-14-21	01-03-22	VDOT Review Bridge Gentechnical Reports
D1240	Submit Revised Bridge Geotechnical Reports	10 01-12-22	01-05-22	Submit Revised Bridge Geotechnical Reports
D1250	Median Roadway Report	40 09-01-21	10-28-21	
D1200		10 10-29-21	11-12-21	
D1280	VDOT Review of Median Roadway Report	21 11-13-21	12-03-21	VDOT Review of Median Roadway Report
D1200	Submit Revised Median Roadway Report	10 12-03-21	12-03-21	I Submit Revised Median Roadway Report
D1230	Shoulder Slones & Retaining Walls Roadway Report	30 09-23-21	11-04-21	Shoulder Slopes & Retaining Walls Readway Report
D1310	OA/OC Shoulder Slopes & Retaining Walls Readway Report	10 11_05 21	11-10-21	OA/OC Shoulder Slopes & Retaining Walls Roadway Report
	VDOT Review Shoulder Slopes & Retaining Walls Roadway Report	21 11-20-21	12-10-21	VDOT Review Shoulder, Slopes & Retaining Walls Roadway Report
D1330	Submit Revised Shoulder Slopes & Retaining Walls Roadway Report	21 11-20-21 ort 10 12-10-21	12-021	Submit Revised Shoulder Slopes & Retaining Walls Reading: Report
D1340	Noise Wall Report	201 10-15-21	11-12-21	
D1340		10 11_15 21	11-20-21	
D1360	VDOT Review Noise Wall Report	28 11-30-21	12-27-21	It VDOT Review Noise Wall Report
		20 11-00*21		
Actual Level of Effort Actual Work	Remaining Work <ul> <li>Milestone</li> <li>Critical Remaining Work</li> <li>Summary</li> </ul>	Page 1 of 13		Branch-Orders Joint Venture

	I-81 Wide	ening wive 136.	o - IVIIVI 141.8	Proposal Sched	Jule							
)	Activity Name	Original Duration	Start	Finish	202 Q		2022 202	202 2 Q Q	23 Q Q	2024 Q Q Q		202 2 Q
🔲 D1370	Submit Revised Noise Wall Report	10	12-28-21	01-11-22		1 Sı	ubmit Re	vised No	oise Wa	all;Repor	nt :	+ +
Environmental Permits		190	05-24-21	02-25-22			)2-25-22	2, Enviro	nmenta	al Permit	.s	
🔲 D1380	Pre-Application Meeting	10	05-24-21	06-07-21		Pre-Applic	ation M	eeting			: :	
D1390	Preparation of NWP 6 - Geotechnical Work	65	06-08-21	09-08-21		Prepar	ation of	NWP 6	- Geote	chnical '	Work	
D1400	Preparation of Joint Permit Application (JPA)	35	06-08-21	07-27-21	—  i	Preparat	ion of J	oint Perr	nit App	lication (	JPA)	
D1410	QA/QC Joint Permit Application (JPA)	10	07-28-21	08-10-21			Joint Pe	mit App	lication	(JPA)		
D1420	Agency Review and Permit Issuance (USACE/DEQ/VMRC)	135	08-11-21	02-25-22			Adency	Reviewa	and Per	mit Issu	ance (	USAC
Litility Relocation/Coor	dination	262	05-24-21	09-15-22	<u> </u>		<b>—</b>	9-15-22	. Utility	Relocati	on/Cor	ordina
D1430	Obtain Letter authorizing DB to coordinate utility relocations	5	05-24-21	05-28-21		Obtain Let	ter auth	orizina E	)B to cc	ordinate	e utility	
D1440	Preliminary Plans to I trilities	10	06-01-21	06-14-21		Preliminar	v Plans	to Utilitie	24			
D1450	VDOT Coordination Meeting	14	06-15-21	06-28-21		VDOT Co	ordinatic	on Meeti	ina			
D1460	Preliminary Review Meeting with Litility Owners	10	06-15-21	06-28-21		Prelimina	ny Revie	w Meetir	ngwith		where	
D1470	Litility and DB "Master Agreements" completed	30	06-20-21	08-10-21			nd DB "N	Apetor A	ardomic	onte" con	nolotor	d'
D1470	Dranor JEO Forma	30	00-29-21	07 07 01				nasiei Au	Jieenie		ihiered	u i
D1400	Prepare 019 Follins	20	00-29-21	07-27-21	_		019 F0	115				
D1490	Preliminary ouncy Status Report	80	00-01-21	09-22-21				iiiy อเลเบ	is Repo	<i>m</i>		
	Distribute UFI Mans	1	09-23-21	09-23-21		i Listridi	ute UFII	rians				
D1510	Hold UFI	10	09-24-21	10-07-21			JFI					
D1520	Utilities prepare and submits plan and estimate (P&E)	55	10-08-21	12-29-21		🔲 Util	ities pre	pare and	d subm	its plan a	andes	stima
D1530	Utility P&E approval	10	12-30-21	01-13-22		] Ut	ility P&E	approva	al			
D1540	Utility Relocation	170	01-14-22	09-15-22			<u></u> ι ι	Itility Rel	ocation			
Bridge Maintenance ar	nd Repair Plans	58	05-24-21	08-26-21	<u> </u>	▼ 08-26-2	1, Bridg	je Mainte	enance	and Re	pair Pl	lans
🔲 D1550	Bridge Maintenance and Repair Plans B682, B677, B678 and B 681	30	05-24-21	07-06-21		Bridge M	aintenar	nce and	Repair	Plans B	682, B	3677
🔲 D1560	QA/QC Bridge Maintenance and Repair Plans B682, B677, B678 and B 681	10	07-07-21	07-20-21	ſ	QA/QC F	3ridge M	laintenar	nce and	l Repair	Plans	; ₿68
🛑 D1570	Submit Bridge Maintenance and Repair Plans B682, B677, B678 and B 681	2	07-21-21	07-22-21		Submit F	3ridge M	laintenar	nce and	d Repair	Plans	; ₿68
🔲 D1580	VDOT Review Bridge Maintenance and Repair Plans B682, B677, B678 and B681	21	07-23-21	08-12-21		VDOT F	leview B	stidge Ma	aintena	nce and	Repa	air Pla
🔲 D1590	Revise and Resubmit Bridge Maintenance and Repair Plans B682, B677, B678 and B681	10	08-12-21	08-26-21		Revise	and Res	submit B	ridge IV	laintena	nce ar	nḋ R
Bridge Design		128	05-24-21	12-27-21		12	-27-21, I	Bridge D	esign			
🔲 D1600	Bridge Stage I (TS&L) B683, B688, B684, B685, B686, B687, B677 and B678	21	05-24-21	06-22-21		Bridge Str	age I (T	5&L) B68	83, B68	38, B684	I, B68	5, B6
🔲 D1610	QA/QC Bridge Stage I (TS&L) B683, B688, B684, B685, B686, B687, B677 and B678	1	06-23-21	06-23-21		QA/QC Br	idge Sta	age I (TS	3&L) B6	83, B68	8, B68	84, E
<b>D1620</b>	Submit Bridge Stage I (TS&L) B683, B688, B684, B685, B686, B687, B677 and B678	1	06-24-21	06-24-21	i	Submit B	ridge St	age I (TS	S&L) Br	383, B68	38, B68	84, E
D1630	VDOT Review Bridge Stage 1 (TS&L) B683, B688, B684, B685, B686, B687, B677 and B678	21	06-25-21	07-15-21		VDOT R	eview Br	idge Sta	ige 1 (T	S&L)BE	383, Br	688,
D1640	Revise and Resubmit Bridge Stage 1 (TS&L) B683, B688, B684, B685, B686, B687, B677 and E	10	07-15-21	07-29-21	— i i i	Revise a	and Res	ubmit Br	idde St	ade 1 (T	S&L) I	B68
D1650	VDOT Review and Approve Bridge Stage 1 (TS&L) B683, B688, B684, B685, B686, B687, B677	21	07-30-21	08-19-21			Review a	and Appr	ove Br	idae Sta	ude 1 (	TS&
<b>D</b> 1660	Bridge Stage II (Final) B683, B688, B684, B685, B686, B687, B677 and B678	60	06-22-21	09-15-21		Bridge	Stage I	l (Final)	B683	B688 B	684 B	3685
D1670	QA/QC Bridge Stage II (Final) B683, B688, B684, B685, B686, B687, B677 and B678	10	09-16-21	09-29-21	—  T		C Bridge	Stage	l (Final	) B683	B688	B68
D1680	Submit Bridge Stage II (Final) B683, B688, B684, B685, B686, B687, B677 and B678	10	09-30-21	10-14-21			nit Brida		II (Fina	) Beez	B688	Bee
D1690	V/DOT Review Bridge Stage 2 (Final) B683, B688, B684, B685, B686, B687, B677 and B678	21	10-15-21	11-04-21			IT Povio			2 (Final)	1'B683	
D1700	Povice and Deshmit Bridge Stage 2 (Final) 2003, 2006, 2004, 2003, 2006, 2007, 2017 and 2017	21	11 04 21	12.06.21			ico and	Pochmi			2 (Einc	
D1700	NDOT Device and Approve Dridge Stage 2 (Final) D003, D000, D004, D003, D000, D007, D077 and D0	20	104-21	12-00-21				Respini				al) Di
	VDOT Review and Approve Blidge Stage 2 (Final) Boos, B	21	12-07-21	12-27-21				ew and /	Appiov	e pildge	Slage	3'Z (
Snoulder Strengthenin	g work Package	67	05-24-21	09-10-21		- 09-10-2	21, Sho	ulder Str	engine	ning vvo	лк нас	скад
D1720	Design of Shoulder Strengthening	30	05-24-21	07-06-21	[	Design of	Should	er Stren	gthenin	ıg		
D1730	QAVQU Review of Shoulder Strengthening	10	07-07-21	07-20-21		QA/QC F	(eview o	T Should	ier Stre	ngthenir	ıg	
D1740	Prepare Shoulder Strengthening Plans for Submission	1	07-21-21	07-21-21		Prepare	Shoulde	r Streng	thening	) Plans f	or Sub	omis
D1750	VDOT Review Shoulder Strengthening Work Package	21	07-22-21	08-11-21		UDOT R	leview S	noulder	Streng	thening	Work F	Pack
D1760	Comment Resolution/Revise Shoulder Strengthening Plans	5	08-11-21	08-18-21		I Comme	nt Reso	lution/Re	evise S	noulder	Streng	jthei
D1770	Resubmit Shoulder Strengthening Plans for Approval	1	08-19-21	08-19-21		I Resubr	nit Shou	Ider Stre	ngther	ing Plan	is for A	۱ppr
🔲 D1780	VDOT Review and Approval - Shoulder Strengthening Plans	21	08-20-21	09-09-21			Review	and App	roval -	Shoulde	r Stren	nģth
🔲 D1790	AFC Shoulder Strengthening WP Released	1	09-09-21	09-10-21		I AFC S	noulder	Strength	iening '	WP Rele	ased	
MOT, Grading, Drainag	ge, ESC/SWM, Water, Sewer and ROW Work Package	108	05-24-21	11-16-21	<b>—</b>	<b></b> 11-1	6-21, M	QT, Grac	Jing, Þr	ainage,	ESC/S	SŴN
	Design of MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW	65	05-24-21	08-24-21	- i 👘	Design	of MOT	Grading	a. Drain	aģe, ES	C/SWI	M, V
🔲 D1950								, <u> </u>				

													03	8-01	1-2′	1 1(	):45	5
20	)26	_		20	27	-		20	28	-		20	29	_		20	30	
Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q	Q
		   					1 1 1											
	1										1				1			
/MF	kC)																	
	1	1																
	1	1					1								1			
	1																	
	1	1					1								1			
	1																	
	1	1																
d B	68	1																
B67	18 a	nd	B 6	81														
₿67	8 a	nd	В6	81														
B6	77.	B6	78 :	and	B6	81												
sВ	682	. В	677	. В	678	an	id B	68	1									
-				, _														
B	577	an	H R	679			1											
, D(	260	יוום ם ל	67	7 2	, d	- 	0											
р, ц с г		, с , с	07	7 0			0											
0, 0	boo	∦,⊏ ¦\	0/	/ a		סס דב	0		70									
85,	BO	вю,	80	87, 00	BO	//	ano	BC	0/8			h						
684	4, B	685	р, В	686	р, В	68	(, В	671	' ar	nd E	367	8						
368	8, E	368 <sup>,</sup> ¦	4, E	868	5, E	368 	6, E	368	7, E	367	7 ai	hd I	B67	8				
87	B6	77	and	d B	678		1											
368	6, E	868	7, E	867	7 ai	hd I	B67	8										
B68	36, I	B68	7, 1	B67	7 a	ind	B6	78										
B6	85,	B6	86,	B6	87,	B6	77 :	and	B6	78								
, В6	584	, ве	85	, B6	586	, В6	587	, B6	577	an	dВ	678	3					
3, E	\$68	8, E	684	4, E	68	5, E	\$68	6, E	68	7, E	67	7 ai	nd E	367	8			
	1																	
							1											
e e																		
0																		
					۸1													
ew	era	Ind	кO	vv	vvoi	κP	ack	age	þ									
/er a	and	RC	W															
		1					1 1											

C0011	6203DB108		I-81 Widening MM 136.6 - MM 141.8	Proposal Schedu	ule												03-01	-21 10:45
Activity II	D	Activity Name	Original Start Duration	Finish	2021			2023 Q Q Q C		QQ		2026 Q Q Q		027 2 Q Q (	2028 2 Q Q (	20 2 Q C	)29 ) Q Q	2030 Q Q Q
	D1960	QA/QC Review of MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans	10 08-25-21	09-08-21		QA/QC	Review	of MOT, Gra	ding, Draina	age, E	ESC/SWM, \	Water, Se	ewer and	ROW Pla	ns			
	 D1970	Prepare MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans for Submis	ssion 1 09-09-21	09-09-21	- I I	Prepare	MOT, C	Grading, Drai	inage, ESC/	/SWIV	л, Water, Se	wer and	ROW Pla	ins for Sut	mission			
	🔲 D1980	VDOT Review MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans	21 09-10-21	09-30-21		VDOT	Review	MOT, Gradin	ig, Drainage,	, ESC	C/SWM, Wat	ter, Sewe	er and RC	JW Plans				
	🔲 D1990	Comment Resolution/Revise MOT, Grading, Drainage, ESC/SWM, Water, Sewer and RC	DW Plans 10 09-30-21	10-15-21		Comm	ent Res	olution/Revis	se MOT, Gra	ading	, Drainage, I	E\$C/\$W	/M, Water	, Sewer ar	nd ROW P	'lans		
	D2000	Resubmit MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW Plans for Appro	val 2 10-15-21	10-19-21		Resub	mit MO	T, Grading, D	Drain'age, ES	SC/SV	WM, Water,	Sewer ar	nd ROW	Plans for A	\pproval			
	D2010	VDOT Review and Approval -MOT, Grading, Drainage, ESC/SWM, Water, Sewer and RC	DW Work 21 10-20-21	11-09-21			Reviev	v and Approv	/al -MOT, Gra	radinç	g, Drainage,	ESC/SV	VM, Wate	r, Sewer a	nd ROW \	Work Pa	ackage	
	D2020	AFC MOT, Grading, Drainage, ESC/SWM, Water, Sewer and ROW WP Released	5 11-09-21	11-16-21		I AFC	MOT, G	rading, Drain	age, E\$C/S	SWM,	, Water, Sew	ver and R	<b>NOW WP</b>	Released				
	Right of Way Acquisition	on	132 09-10-21	06-01-22			06-01	-22, Right of	f Way Acquis	sition								
	D2030	R/W Authroization, Appraisals/BARS	60 09-10-21	11-08-21	-	R/W	Authroiz	ation, Apprai	isals/BARS									
	<b>D2040</b>	Independent Appraisal Review	20 11-09-21	12-07-21		Inde	penden	t Appraisal R	Réview									
	D2050	Submit Appraisal/BARS Package to VDOT	2 12-08-21	12-09-21		I Sub	mit Appr	aisal/BARS I	Package to	VDO	π						111	
	<b>D</b> 2060	VDOT Review	21 12-10-21	12-30-21		VD	OT Revi	ew										
	D2070	Negotiations	30 12-30-21	02-14-22		N	egotiatio	ns		i								
	D2080	Final Negotiations Submission	30 02-14-22	03-29-22			Final Ne	gotiations Si	ubmission									
	D2090	VDOT Review and Funding	21 03-30-22	04-19-22			VDOT F	Review and F	unding									
	D2100	Closing/Condemnation	30 04-19-22	06-01-22			Closin	ıg/Ċondemn	ation									
	Noise Walls		179 05-24-21	04-22-22			04-22-2	2, Noise Wa	alls									
	D1055	Noise Analysis & Report Preparation	80 05-24-21	09-15-21		Noise A	nalysis	& Report Pre	paration									
	D1065	QA/QC Noise Report	15 09-16-21	10-06-21			Noise I	Report										
	 D1075	VDOT Review Noise Report	14 10-07-21	10-20-21			Review	Noise Repo	nt									
	 D1085	Incorporate Comments & Resubmit Noise Report	5 10-20-21	10-27-21		I Incom	orate C	omments &	Resubmit No	loise F	Report							
	D1095	FHWA Review & Approval	14 10-28-21	11-10-21		I FHW	A Review	v & Approval		}								
	 D1105	Public Comment Period	30 11-10-21	12-23-21		🔲 Pub	lic Comi	ment Period		į								
	D1115	Revise Noise Report	10 12-23-21	01-10-22		Re	vise Noi	se Report										
	 D1125	QA/QC & Submit Amended Noise Report	5 01-10-22	01-18-22		I Q/	VQC &	Submit Amer	nded Noise F	Repo	ort							
	 D1135	VDOT Review of Amended Noise Report	14 01-19-22	02-01-22		0 VI	OOT Rev	iew of Amen	nded Noise F	Repor	ort							
	D1145	Incorporate Comments & Final VDOT Approval	5 02-01-22	02-08-22		l In	corporat	e Comments	s & Final VD	) A TOC	Approval							
	 D1155	Prepare Final Noise Wall Plan Submittal	25 02-08-22	03-16-22			Prepare	Final Noise \	Wall Plan Su	ubmit	ttal							
	 D1165	QA/QC Final Noise Wall Plans	5 03-16-22	03-23-22			QA/QC	-inal Noise V	Vall Plans									
	 D1175	Submit Final Noise Wall Plans	2 03-23-22	03-25-22			Submit I	- inal Noise V	Vall Plans									
	 D1185	VDOT Review & Approve Final Noise Wall Plan Submittal	14 03-26-22	04-08-22		Ó		eview & App	prove Final N	Voise	Wall Plan S	ubmittal						
	D1195	AFC Noise Wall Plans	10 04-08-22	04-22-22		0	AFC No	oise Wall Pla	ns									
	Final Design		81 11-17-21	05-12-22			05-12-	22, Final Des	sign									
	D2110	Final Roadway/ITS/Lighting Plans Design	65 11-17-21	02-22-22		F	inal Roa	dway/ITS/Lic	ghting Plans	s Desi	sign							
	D2120	Design QA/QC Review of Final Roadway/ITS/Lighting Plans	10 02-23-22	03-08-22		. <b>D</b> C	esign C	A/QC Review	w of Final Ro	oadw	vay/ITS/Light	ting Plan	າຣ					
	D2130	Prepare Final Roadway/ITS/Lighting Plans for Submission	1 03-09-22	03-09-22		I F	repare	Final Roadwa	ay/ITS/Lighti	ting P	Plans for Sub	omission						
	D2140	VDOT Review Final Roadway/ITS/Lighting Plans	21 03-10-22	03-30-22			VDOT R	eview Final I	Roadway/ITS	S/Ligi	hting Plans	,						
	 D2150	Comment Resolution/Revise Final Roadway/ITS/Lighting Plans	10 03-30-22	04-13-22			Comme	nt Resolutio	n/Revise Fin	nal:Rc	oadway/ITS/	Lighting	Plans					
	D2160	Resubmit Final Roadway/ITS/Lighting Plans for Approval	1 04-14-22	04-14-22			Resubn	nit Final Road	dway/ITS/Lic	ghting	g Plans for A	Approval						
	 D2170	VDOT Review and Approval Final Roadway/ITS/Lighting Plans	21 04-15-22	05-05-22			VDOT	Review and <i>i</i>	Approval Fin	nal Rc	oadwav/ITS/	/Liahtina	Plans					
	D2180	AFC Final Roadway/ITS/Lighting Plans Released	5 05-05-22	05-12-22		Ī	AFC F	nal Roadway	v/ITS/Lightin	ng Pla	ans Release	d						
	Pavement Markings/Sig	inage Plans	58 05-13-22	08-23-22		V		-23-22. Pave	ement Marki	inas/s	Signage Plar	ns						
	D2190	Pavememnt Markings/Signage Plans Final Design	20 05-13-22	06-10-22			Pave	memnt Mark	ings/Signag	ae Pla	ans Final Der	sidn						
	D2200	Design QA/QC Review of Pavement Markings/Signage Plans	10 06-13-22	06-24-22			Desid	n QA/QC R	eview of Pav	veme	ent Markings	/Signage	e Plans					
	D2210	Prepare Pavement Markings/Signage Plans for Submission	1 06-27-22	06-27-22			l Prep	are Paverne	nt Markings/	s/Sian	age Plans fo	or Submi	ission					
	D2220	VDOT Review Pavement Markings/Signage Plans	21 06-28-22	07-18-22				DT Review Pa	avement Ma	arkinc	as/Signage F	Plans						
	D2230	Comment Resolution/Revise Pavement Markings/Signage Plans	5 07-18-22	07-25-22			- Con	nment Resol	lution/Revise	e Pav	vement Mark	kinas/Sia	unade Pla	ns				
	D2240	Resubmit Pavement Markings/Signage Plans for Approval	1 07-26-22	07-26-22			l Res	ubmit Paver	ment Marking	nas/Si	ionade Plan:	s for App	otoval					
	D2250	VDOT Review and Approval Pavement Markings/Signage Plans	21 07-27-22	08-16-22				OT Review a	and Approval	al Pav	vement Mark	kinas/Siar	inage Plai	ns				
	D2260	AFC Pavement Markings/Signage Plans Released	5 08-16-22	08-23-22				C Pavement	t Markinas/S	Signa	ide Plans Ro	aleased						
			00-10-22	00 20 22					, maninga/o	-ignat	90 mans 1.01	134304						
	Actual Level of Effort	Remaining Work <ul> <li>Milestone</li> <li>Critical Remaining Work</li> <li>summary</li> </ul>	Page 3 of 13					Branch-Or	ders Joint V	√entu	ıre							

1020300100		1-81 Widening MiN 136.6 - MiN 141	.8 Proposal Sched	aule 03-0
ID	Activity Name	Original Start Duration	Finish	2021         2022         2023         2024         2025         2026         2027         2028         2029
		97 09-23-21	04-05-22	
	Mohilization	20 09-23-21	10-22-21	
<b>1110</b>		10 02 28 22	02 16 22	
			04.05.22	
1120		15 03-08-22	04-05-22	
<b>1130</b>		10 02-28-22	03-16-22	
	NACTIVITIES	809 09-23-21	11-14-25	▼ 11-14-25, CONSTRUCTION ACTIVITIES
PHASE 1		166 09-23-21	08-11-22	08 <u>+</u> 11-22, PHASE 1
I-81 NB		166 09-23-21	08-11-22	₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩₩
AREA 1		119 09-23-21	05-20-22	
	Shoulder Strenghthening (1-81 NB) (Area 1) (Phase 1)	9 09-23-21	10-05-21	
<u> </u>	SWM Basin (147+50 - 149+50) (I-81 NB) (Area 1) (Phase 1)	5 05-11-22	05-20-22	SWM Basin (147+50 - 149+50) (I-81 NB) (Area 1) (Phase 1)
AREA 2	Chaudan Other stheming (1.04 ND) (Area O) (Dhace 4)	157 10-06-21	08-11-22	Charles Date at a shaking (D4 ND) (dea 2) (D4 has (d))
	Shoulder Strengthening (1-81 NB) (Area 2) (Phase 1)	16 10-06-21	11-01-21	Shoulder Strengthening (1-81 NB) (Area 2) (Phase 1)
<b>1920</b>	SWM Basin (161+00 - 165+00) (I-81 NB) (Area 2) (Phase 1)	3 05-23-22	05-25-22	T SWM Basin (161+00 - 165+00) (I-81 NB) (Area 2) (Phase 1)
<b>1930</b>	SWM Basin (Sta. 182+00 - 188+00) (I-81 NB) (Area 2) (Phase 1)	6 05-27-22	06-06-22	SWM Basin (Sta. 182+00 - 188+00) (I-81 NB) (Area 2) (Phase 1)
TE. 635 F		38 06-07-22	08-11-22	08-11-22, RTE. 635 ROADWAY RECONSTRUCTION
<b>—</b> 1940	Establish Temp. MOT (Detour) (Rte. 635) (Area 2) (Phase 1)	2 06-07-22	06-10-22	I Establish Temp. MOT (Detour) (Rte. 635) (Area 2) (Phase 1)
	Grading/Excavation (Rte. 635) (Area 2) (Phase 1)	17 06-13-22	07-11-22	Grading/Excavation (Rte. 635) (Area 2) (Phase 1)
1960	Install Storm Drainage (Rte. 635) (Area 2) (Phase 1)	13 06-27-22	07-18-22	Install Ștoim Drainage (Rte: 635) (Area 2) (Phase 1)
<u> </u>	Install Aggregate Base Course (Rte. 635) (Area 2) (Phase 1)	6 07-19-22	07-28-22	I Install Aggregate Base Course (Rte. 635) (Area 2) (Phase 1)
<u> </u>	Install Asphalt Paving (Rte. 635) (Area 2) (Phase 1)	5 07-25-22	08-01-22	I Install Asphalt Paving (Rte. 635) (Area 2) (Phase 1)
<b>—</b> 1990	Install Pavement Markings/Signage (Rte. 635) (Area 2) (Phase 1)	5 08-02-22	08-09-22	Install Pavement Markings/Signage (Rte. 635) (Area 2) (Phase 1)
<b>a</b> 2000	Remove Temp. MOT Measures (Rte. 635) (Area 2) (Phase 1)	2 08-10-22	08-11-22	I Remove Temp. MOT Measures (Rte, 635) (Area 2) (Phase 1)
AREA 3		50 10-25-21	02-08-22	02-08-22, AREA 3
<b>=</b> 2010	Shoulder Strengthening (I-81 NB) (Area 3) (Phase 1)	15 11-02-21	11-30-21	□ Shoulder Strengthening (I-81 NB) (Area 3) (Phase 1)
I-81 OVER	RTE. 311 BRIDGE	35 10-25-21	01-04-22	01-04-22, I-81 OVER RTE. 311 BRIDGE
2025	Substructure Surface Repairs/Anodes (I-81 Over Rte. 311) (Area 3) (Phase 1)	10 10-25-21	11-09-21	Substructure Surface Repairs/Anodes (I-81 Over Rte. 311) (Area 3) (Phase 1)
2030	Steel Crack Reapairs (Welding) (I-81 Over Rte. 311) (Area 3) (Phase 1)	10 11-11-21	11-30-21	Steel Crack Reapairs (Weldirig) (I-81 Over Rte. 311) (Area 3) (Phase 1)
<b>—</b> 2035	Jack/Block & Replace Existing Bearings (I-81 Over Rte. 311) (Area 3) (Phase 1)	15 12-01-21	01-04-22	Jack/Block & Replace Existing Bearings (I-81 Over Rte: 311) (Area 3) (Phase 1)
📲 RTE. 705 (	OVER I-81 BRIDGE	15 01-07-22	02-08-22	₩ 02-08-22, RTE. 705 OVER I-81 BRIDGE
2040	Substructure Surface Repairs/Anodes (Rte. 705 Over I-81) (Area 3) (Phase 1)	5 01-31-22	02-08-22	I Substructure Surface Repairs/Anodes (Rte. 705 Over I-81) (Area 3) (Phase 1)
2045	Concrete Surface Protection (Rte. 705 Over I-81) (Area 3) (Phase 1)	10 01-07-22	01-28-22	Concrete Surface Ptotection (Rte: 705 Over I-81) (Area 3) (Phase 1)
	Shoulder Strongthoning (1.81 NR) (Area 4) (Phase 1)	45 12-01-21	03-14-22	V 03-14-22, AREA 4
		14 12-01-21	02 14 22	
	Substructure Surface Papairs/Apadas /Pta 410 Quart 91) (Area 4) (Phase 1)	5 03 04 22	03-14-22	W 03-14-22, RIE: 419 OVER 1-01 DRIDGE     II. Substructure Surface Demain / Anodae / Pta 410 Quart 81/ (Area 4) (Phase 1)
2085	Substituture Suitace Repails Anotes (Rie. 419 Over 1-o1) (Area 4) (Phase 1)	5 03-04-22	03-14-22	I Substituctule Sulface Repails Alloces (Rig. 419 Over 1-51) (Alea 4) (Finase 1)
2095	Concrete Surface Protection (Rte. 419 Over 1-81) (Area 4) (Phase 1)	10 02-11-22	03-02-22	
		76 10.06.21	02 14 22	
ANEA 4	Shoulder Strengthening (L81 SB) (Area 4) (Phase 1)	11 10-06-21	10-22-21	J Should'er Strengthening (I-81 SB) (Area 4) (Phase 1)
		15 02-11-22	03-14-22	
2135	Substructure Surface Repairs/Anodes (Rte. 419 Over I-81) (Area 4) (Phase 1)	5 03-04-22	03-14-22	I: Substructure Surface Repairs/Anodes (Rte 419 Over I-81) (Area 4) (Phase 1)
2145	Concrete Surface Protection (Rtg. 419 Over L81) (Area 4) (Phase 1)	10 02-11-22	03-02-22	Concrete Surface Protection (Rie 4/19 Over L-81) (Area 4) (Phase 1)
		55 10-25-21	02-21-22	
AREA 3	Shoulder Strengthening (I-81 SB) (Area 3) (Phase 1)	15 10-25-21	11-18-21	□ Shoulder Strendthening (I-81, SB) (Area 3) (Phase 1)
		35 10-25-21	01-04-22	
	Substructure Surface Repairs/Anodes (I-81 SB Over Rte, 311) (Area 3) (Phase 1)	10 10-25-21	11-09-21	Substructure Sulface Repairs/Anodels (II:81:SB Over Rte, 311) (Area 3) (Phase 1)
2105	Steel Crack Respairs (Melding) (I-81 SB Over Rte 311) (Area 3) (Phase 1)	10 11-11-21	11-30-21	Steel (Track Respective (Welding) (1-81 SB Over Rts, 311) (Area 3) (Phase 1)
- 2195	Jack/Block & Replace Existing Rearings (L&1 SR Over Pte, 311) (Area 3) (Phase 1)	15 12_01_21	01_04_22	Jack/Block & Replace Evicting Regimes (Lat SR Over Rts 311) (Ards 3) (Dhase 1)
			02.24.22	
- RIE. 705 C	Substructure Surface Renaire/Anodes (L81 SR Over Ptel 705) (Area 3) (Phase 1)		02-21-22	V V(221-22, NIL. 100 OVER POT DRIDOE
= 2215	Steel Crack Reanairs (Welding) (I-81 SB Over Rte 705) (Area 3) (Phase 1)	5 01-31-22	07-08-22	L Steel Crack Reanairs (Welding) (1-81 SB Over Rte 705) (Area 3) (Phase 1)
		3 01-51-22	02 00 22	

6203DB108		I-81 Widening MM 136.6 - MM 141.8	Proposal Schedr	dule	03-01-21
5	Activity Name	Original Start Duration	Finish		
2235	Jack/Block & Replace Existing Bearings (I-81 SB Over Rte. 705) (Area 3) (Phase 1)	5 02-11-22	02-21-22	Jack/	Block & Replace Existing Bearings (I-81 \$B Over Rte. 705) (Area 3) (Phase 1)
AREA 2		100 11-19-21	06-20-22		06-20-22, ARE'A 2
2245	Shoulder Strengthening (I-81 SB) (Area 2) (Phase 1)	16 11-19-21	12-17-21	Shoulde	er Strengthening (I-81 SB) (Area 2) (Phase 1)
2275	SWM Basin (Sta. 574+00 - 576+75) (I-81 SB) (Area 2) (Phase 1)	3 06-07-22	06-13-22	IS	SWM Basin (Sta. 574+00 - 576+75) (I-81 SB) (Area 2) (Phase 1)
2285	SWM Basin (Sta. 599+00 - 602+50) (I-81 SB) (Area 2) (Phase 1)	4 06-14-22	06-20-22	18	SWM Basin (Sta. 599+00 - 602+50) (I-81 SB) (Area 2) (Phase 1)
AREA 1		87 12-20-21	06-24-22	<b>— — — —</b>	06-24-22, AREA 1
2295	Shoulder Strengthening (I-81 SB) (Area 1) (Phase 1)	9 12-20-21	01-17-22	🗍 Should	der \$trengthening (I-81 \$B) (Area 1) (Phase 1)
2325	SWM Basin (527+00 - 530+00) (I-81 SB) (Area 1) (Phase 1)	3 06-21-22	06-24-22		SWM Basin (527+00 - 530+00) (I-81 \$B) (Area 1) (Phase 1)
PHASE 2		370 03-15-22	02-01-24		▼ 02-01-24, PHASE 2
2355	Establish Temp. MOT/Shift Traffic I-81 SB	5 03-25-22	04-01-22	Esta	ablish Temp. MOT/Shift Traffic I-81 SB
2365	Establish Temp. MOT/Shift Traffic I-81 NB	5 03-15-22	03-22-22	l Esta	ablish Temp. MOT/Shift Traffic I-81 NB
🔚 I-81 NB		326 03-18-22	11-02-23		▼ 11-02-23, I-81 NB
AREA 1		243 06-27-22	09-11-23		99-11-23, AREA 1
<b>=</b> 2330	Install Temporary Concrete Barrier (I-81 NB) (Area1) (Phase 2)	8 06-27-22	07-08-22		Install Temporary Concrete Barrier (I-81 NB) (Area1) (Phase 2)
2340	Grading/Excavation (I-81 NB) (Area1) (Phase 2)	10 07-01-22	07-19-22		Grading/Excavation (I-81 NB) (Area1) (Phase 2)
<b>=</b> 2350	Install Storm Drainage (I-81 NB) (Area1) (Phase 2)	19 07-12-22	08-11-22		Install Storm Drainage (I-81 NB) (Area1) (Phase 2)
2360	Install Median Barrier (I-81 NB) (Area1) (Phase 2)	9 08-08-22	08-19-22		Install Median Barrier (I-81 NB) (Area1) (Phase 2)
2370	Install Aggregate Base Course (I-81 NB) (Area1) (Phase 2)	14 08-12-22	09-01-22		Install Aggregate Base Course (I-81 NB) (Area1) (Phase 2)
2380	Install Asphalt Base Course (I-81 NB) (Area1) (Phase 2)	11 08-24-22	09-08-22		Install Asphalt Base Course (I-81 NB) (Area1) (Phase 2)
2390	Install Asphalt Intermediate Course (I-81 NB) (Area1) (Phase 2)	3 09-09-22	09-13-22		Install Asphalt Intermediate Course (I-81 NB) (Area1) (Phase 2)
2400	Install Guardrail (I-81 NB) (Area1) (Phase 2)	6 09-12-22	09-20-22		Install Guardrail (I-81 NB) (Area1) (Phase 2)
2410	Remove Temporary Concrete Barrier (I-81 NB) (Area1) (Phase 2)	7 09-21-22	09-30-22		Remove Temporary Concrete Barrier (LS1 NB) (Area1) (Phase 2)
2410	Establish Temp, MOT/Shift Traffic (I-81 NB) (Area1) (Phase 2)	2 10-03-22	10-04-22		Establish Temp, MOT/Shift Traffic (L-81 NB) (Area1) (Phase 2)
		2 10-03-22	00 11 22		
	E. 112 DRIDGE Partial Structure Removal (L81 NB Over Rte, 112) (Area 1) (Phase 2)	16 07-11-22	09-11-23		Partial Structure Demoval /L81 NB Over Pte 112) (Area 1) (Phase 2)
2430	Support of Excavation/Structure Excavation Abutment A (I-81 NB Over Rte 112) (Area 1)	(Phase 10 08-08-22	08-22-22		Support of Everyotion/Structure Everyotion Abutment A/(L81 NB Quer Pte 112) (Area 1) (Phase 2)
2440	Drive Biles (Abutment A) // 81 NB Over Bto 112) (Area 1) (Drass 2)	6 09 22 22	08 20 22		Drive Pilde (Abutment A) (191 NP Over Pto 112) (Area 1) (Phase 2)
2450	Construct MSE Walls (Abuttagent A) (1.94 ND Over Dts. 112) (Area 1) (Phase 2)	0 00-23-22	10.07.00		
2460	Construct MSE Walls (Abuthent A) (For the Over Re. 112) (Area 1) (Phase 2)	24 00-31-22	10-07-22		
2470	FRP Abutment (Abutment A) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	10 10-10-22	10-24-22		
2480	Support of Excavation/Structure Excavation Pier (I-81 NB Over Rte. 112) (Area 1) (Phase 2	2) 10 10-25-22	11-08-22		U Support of Excavation/Structure Excavation Pier (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
2490	Install Micropiles at Pier (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	23 11-10-22	12-20-22		L; Install Micropiles at Prer (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
2500	FRP Pier Footer (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	10 12-22-22	01-20-23		FRP Pier Footer (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
2510	FRP Pier Stem/Cap (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	14 01-23-23	02-21-23		□ FRP Pier Stem/Cap (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
<b>2520</b>	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 112) (Area 1	) (Phas 10 02-24-23	03-13-23		I Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (
2530	Construct MSE Wall (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	24 03-14-23	05-01-23		Construct MSE Wall (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
<b>2540</b>	Drive Piles (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	6 05-02-23	05-11-23		I Drive Piles (Abutment B) (I-81 NB Over Rte, 112) (Area 1) (Phase 2)
<b>=</b> 2550	FRP Abutment (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	10 05-12-23	06-01-23		I FRP Abutment (Abutment B) (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
<b>=</b> 2560	Girder Erection (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	7 06-02-23	06-13-23		I. Girder Erection (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
<b>=</b> 2570	FRP Deck/Barrier (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	45 06-15-23	08-25-23		FRP Deck/Barrier (I-81 NB Over Rte, 112) (Area 1) (Phase 2)
<b>=</b> 2580	FRP Approach Slabs (I-81 NB Over Rte. 112) (Area 1) (Phase 2)	10 08-28-23	09-11-23		I FRP Approach Slabs (I-81 NB Over Rte. 112) (Area 1) (Phase 2)
AREA 2		257 03-18-22	07-14-23		🕂 🕂 材 07-14-23, ÅRĖA 2 🕴 👘 👘 👘 👘 👘 👘 👘 👘 👘 👘 👘
<b>=</b> 2590	Install Temporary Concrete Barrier (I-81 NB) (Area 2) (Phase 2)	5 10-06-22	10-13-22		Install Temporary Concrete Barrier (I-81 NB) (Area 2) (Phase 2)
<b>a</b> 2600	Grading/Excavation (I-81 NB) (Area 2) (Phase 2)	18 10-11-22	11-07-22		Grading/Excavation (I-81 NB) (Area 2) (Phase 2)
<b>a</b> 2610	Install Storm Drainage (I-81 NB) (Area 2) (Phase 2)	36 10-19-22	12-19-22		Install Storm Drainage (I-81 NB) (Area 2) (Phase 2)
<b>=</b> 2620	Install Median Barrier (I-81 NB) (Area 2) (Phase 2)	16 12-09-22	01-17-23		🗴 Install Median Barrier (I-81 NB) (Area 2) (Phase 2)
2630	Install Aggregate Base Course (I-81 NB) (Area 2) (Phase 2)	25 12-16-22	02-17-23		Install Aggregate Base Course (I-81 NB) (Area 2) (Phase 2)
2640	Install Asphalt Base Course (I-81 NB) (Area 2) (Phase 2)	20 01-09-23	02-21-23		Install Asphalt Base Course (I-81 NB) (Area 2) (Phase 2)
	Install Asphalt Intermediate Course (I-81 NB) (Area 2) (Phase 2)	6 02-24-23	03-06-23		I Instal Asphalt Intermediate Course (I-81 NB) (Area 2) (Phase 2)
2660	Install Guardrail (I-81 NB) (Area 2) (Phase 2)	15 01-23-23	02-24-23		□ Install Guardrail (I-81 NB) (Area 2) (Phase 2)
2670	Remove Temporary Concrete Barrier (I-81 NR) (Area 2) (Phase 2)	5 02-27-23	03-06-23		Remove Temporary Concrete Barrier (I-81 NR) (Area 2) (Phase 2)
2010	Establish Temp, MOT/Shift Traffic /L-81 NR) (Area 2) (Phase 2)	2 02 07 22	03-00-23		L Establish Tomn. MOT/Shift Traffic (1.81 NR) (Area. 2) (Dhasa 2)
	$\Box$ satisfies the particular transferred of the particular transferred (Fildse 2)	2 03-07-23	03-03-23		

203DB108	3	-i l	81 Widening MM 136.6 - MM 141.8	Proposal Sched	dule 03
		Activity Name	Original Start Duration	Finish	2021         2022         2023         2024         2025         2026         2027         2028         2029           Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q Q
	I-81 OVER RTE	E. 635 BRIDGE	178 08-12-22	07-14-23	07-14-23, I-81 OVER RTE. 635 BRIDGE
	2685	Partial Structure Removal (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	16 08-12-22	09-06-22	Partial Structure Removal (I-81 NB Over Rte. 635) (Area 2) (Phase 2)
	2695	Support of Excavation/Structure Excavation (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (P	has 12 09-07-22	09-26-22	I Support of Excavation/Structure Excavation (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (F
	2705	Drive Piles (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	6 09-27-22	10-04-22	Drivé Piles (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)
	2715	Construct MSE Walls (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	24 10-06-22	11-11-22	Construct MSE Walls (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)
	2725	FRP Abutment (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	10 11-14-22	12-01-22	FRP Abutment (Abutment A) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)
	2735	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 635) (Area 2) (F	<sup>2</sup> has 12 12-02-22	12-22-22	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 635) (Area
	2745	Construct MSE Walls (Abutment B) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	21 12-23-22	02-17-23	Construct MSE Walls (Abutment B) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)
	2755	Drive Piles (Abutment B) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	6 02-20-23	03-02-23	II. Drive Piles (Abutment B) (I-81 NB Over Rte, 635) (Area 2) (Phase 2)
	2765	FRP Abutment (Abutment B) (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	10 03-03-23	03-21-23	I: FRP Abutment (Abutment B) (I-81 NB Over Rte, 635) (Area 2) (Phase 2)
	2775	Girder Frection (I-81 NB Over Rte. 635) (Area 2) (Phase 2)	6 03-24-23	04-03-23	Girder Frection (I-81 NB Over Rte, 635) (Area 2) (Phase 2)
	2785	FRP Deck/Barrier Wall (I-81 NB Over Rte, 635) (Area 2) (Phase 2)	45 04-04-23	06-27-23	
	2705	ERP Approach Slahs (L-21 NB Over Pte, 635) (Area 2) (Phase 2)	10 06-29-23	07-14-23	FEP Approach Slabs (L&1 NB (Dver Pie 635) (Area 2) (Phase 2)
				02 21 22	
	2805	Partial Structure Removal (I-81 NB Over Rte, 619) (Area 2) (Phase 2)	13 03-18-22	04-12-22	Partial Structure Removal (1-81, NB Over Rts, 610) (Δrea 2) (Phase 2)
	2005	Support of Evolution/Structure Evolution (Abutmont A) // 81 NP Over Pto, 610) (Area 2) /P	2bas 10 04 13 22	05 02 22	I Subport of Exceptotion (Structure Exceptotion (Abuttmost A) (181 NB/Outer Eta (610) (Area 2) //Phase
	- 2825	Drive Piles (Abutment A) (1-81 NR Over Pile 610) (Area 2) (Phase 2)	7 05 02 22	05-16-22	I Drive Piles (Abutment A) (1,81, NR Over Pie 610) (Area 2) (Phase d)
	2020	Construct MCE Wolls (Abutment A) (194 ND Creat Dts. 640) (Area 2) (Dtses 0)	1 00-03-22	07.05.00	
	2035	EPD Abutment (Abutment A) (LS4 NP Crost Ptel (24) (Area 2) (Phase 2)	21 05-17-22	07-05-22	Construct IVISE Walls (Aputment A) (I-ST IVIS Over Rte. 619) (Area 2) (Phase 2)
	2845	FRP Abutment (Abutment A) (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	10 07-07-22	07-22-22	I FRP Adutment (Abutment A) (I-81 NB Over Rte; 6(9) (Area 2) (Phase 2)
	2855	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (F	'has 10 07-25-22	08-09-22	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (Pr
	2865	Construct MSE Walls (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	27 08-10-22	09-20-22	Construct MSE Walls (Abutment B) (I-81 NB Over Rte. 619) (Area 2):(Phase 2):
·	2875	Drive Piles (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	7 09-21-22	09-30-22	Drive Piles (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (Phase 2)
	2885	FRP Abutment (Abutment B) (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	10 10-03-22	10-18-22	1 FRP Abutment (Abutment B) (I-81 NB Over Rte: 619) (Area 2) (Phase 2)
	2895	Girder Erection (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	6 10-19-22	10-26-22	Girder Erection (I-81 NB Over Rte; 619) (Area 2) (Phase 2)
	2905	FRP Deck/Barrier Wall (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	45 10-27-22	01-30-23	FRP Deck/Barrier Wall (I-81 NB Over Rte. 619) (Area 2) (Phase 2)
	2915	FRP Approach Slabs (I-81 NB Over Rte. 619) (Area 2) (Phase 2)	10 01-31-23	02-21-23	FRP Approach Slabs (I-81 NB Over Rte: 619) (Area 2) (Phase 2)
A	REA 3		275 03-18-22	08-11-23	V 08-11-23, AREA 3
	2925	Install Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 2)	5 03-10-23	03-20-23	II, Install Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 2)
	2935	Grading/Excavation (I-81 NB) (Area 3) (Phase 2)	17 03-17-23	04-18-23	Grading/Excavation (I-81 NB) (Area 3) (Phase 2)
	2945	Install Storm Drainage (I-81 NB) (Area 3) (Phase 2)	38 03-28-23	06-08-23	Inistall Storm Drainage (I-81 NB) (Area 3) (Phase 2)
-	2955	Install Median Barrier (I-81 NB) (Area 3) (Phase 2)	15 05-15-23	06-12-23	Install Median Barrier (I-81 NB) (Area 3) (Phase 2)
	2965	Install Aggregate Base Course (I-81 NB) (Area 3) (Phase 2)	24 05-23-23	07-05-23	Install Aggregate Base Course (I-81 NB) (Area 3) (Phase 2)
	2975	Install Asphalt Base Course (I-81 NB) (Area 3) (Phase 2)	19 06-06-23	07-07-23	Install Asphalt Base Course (I-81 NB) (Area 3) (Phase 2)
	2985	Install Asphalt Intermediate Course (I-81 NB) (Area 3) (Phase 2)	6 07-10-23	07-18-23	I Install Asphalt Intermediate Course (I-81 NB) (Area 3) (Phase 2)
	2995	Install Guardrail (I-81 NB) (Area 3) (Phase 2)	14 07-11-23	08-01-23	Install Guardrail (I-81 NB) (Area 3) (Phase 2)
	3005	Remove Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 2)	5 08-02-23	08-08-23	Remove Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 2)
	3015	Establish Temp. MOT/Shift Traffic (I-81 NB) (Area 3) (Phase 2)	2 08-10-23	08-11-23	I Establish Temp. MOT/Shift Traffic (I-81 NB) (Area 3) (Phase 2)
-	I-81 OVER RTE	E. 311 BRIDGE	139 03-18-22	11-15-22	▼ 11-15-22, I-81 OVER RTE, 311 BRIDGE
	3025	Partial Structure Removal (I-81 NB Over Rte. 311) (Area 3) (Phase 2)	10 03-18-22	04-05-22	Partial Structure Removal (I-81 NB Over Rte. 311) (Area 3) (Phase 2)
	3035	Support of Excavation/Structure Excavation (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (P	'has 16 04-08-22	05-09-22	Support of Excavation/Structure Excavation (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase
	3045	Drive Piles (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase 2)	6 05-10-22	05-20-22	Drive Piles (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase 2)
	3065	FRP Abutment (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase 2)	18 05-23-22	06-22-22	FRP Abutment (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase 2)
	3075	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 311) (Area 3) (P	has 16 06-24-22	07-21-22	Support of Excavation/Structure Excavation (Abutment B) (I-81 NB Over Rte. 311) (Area 3) (Ph.
	3095	Drive Piles (Abutment B) (I-81 NB Over Rte, 311) (Area 3) (Phase 2)	6 07-22-22	08-01-22	Drive Piles (Abutment B) (I+81 NB;Over Rte :311) (Area 3) (Phase 2)
	3105	FRP Abutment (Abutment B) (I-81 NB Over Rte, 311) (Area 3) (Phase 2)	18 08-02-22	08-29-22	FRP Abutment (Abutment B) (I-81 NB Over Rte. 311) (Area 3) (Phase 2)
	3115	Girder Frection (I-81 NB Over Rte 311) (Area 3) (Phase 2)	4 08-30-22	09-02-22	Girdet Frection (I-8/1 NB Over Rts 311) (Area 3) (Phase 2)
	- 3125	ERD Deck/Ramer Wall (L&I NR Over Pto 211) (Area 2) (Phase 2)	25 00 06 22	10.29.22	EDD Deck/Barrier Wall // 91 NB Over Tite: 311/(Area 3) (Bhana 3)
	- 3120 - 2125	EDD Approach Slobe (1.91 NB Or or Dec. 211) (Alea 3) (Chase 2)	30 09-00-22	10-20-22	FINE DEUN/Damet Wall (1-01, IND Over File, 3 (1) (Alea 3) (Filase 2)
		TRE Apploauti Diaus (1-01 IND Over Rie. 311) (Area 3) (Priase 2)	10 10-31-22	11-15-22	
A	2145	Install Tomporphy Constants Parties (1.94 NP) (Area 4) (Phase 0)	51 08-14-23	08 48 02	
	3140	Install remporary Concrete Damer (I-81 NB) (Area 4) (Phase 2)	5 08-14-23	00-18-23	I Install temporary Concrete Barner (1-81 NB) (Area 4) (Phase 2)
	3155	Grading/Excavation (I-81 NB) (Area 4) (Phase 2)	15 08-17-23	09-08-23	II Grading/Excavation (I+81 NB) (Area 4) (Phase 2)

C00116	6203DB108		I-81 Wid	ening MM 136.6 - MM 141.8	Proposal Schedu	ule								03-	01-21 10:45
Activity ID	)	Activity Name		Original Start Duration	Finish	2021		2023	2024		2026			2029	
	3165	Install Storm Drainage (I-81 NB) (Area 4) (Phase 2)		18 08-25-23	09-21-23				Install Storr	m Drainage (I-	31 NB) (Area 4)	(Phase 2)			
	3175	Install Median Barrier (I-81 NB) (Area 4) (Phase 2)		14 09-06-23	09-26-23				Install Med	lian Barrier (I-8	1 NB) (Area 4)	(Phase 2)			
	3185	Install Aggregate Base Course (I-81 NB) (Area 4) (Phase 2)		22 09-12-23	10-17-23				Install Ago	pregate Base 0	Course (I-81 NE	3) (Area 4) (Pha	se 2)		
	3195	Install Asphalt Base Course (I-81 NB) (Area 4) (Phase 2)		18 09-21-23	10-20-23				Install Asp	halt Base Cou	rse (I-81 NB) (A	Area 4) (Phase	2)		
	3205	Install Asphalt Intermediate Course (I-81 NB) (Area 4) (Phase 2)		6 10-23-23	10-30-23				Install Asc	ohalt Intermed	ate Course (l-8	31 NB) (Area 4)	(Phase 2)		
	3215	Install Guardrail (I-81 NB) (Area 4) (Phase 2)		13 10-02-23	10-23-23				Install Gu	ardrail (I-81 NE	) (Area 4) (Pha	ase 2)	(,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		
	3225	Remove Temporary Concrete Barrier (I-81 NB) (Area 4) (Phase 2)		5 10-24-23	10-30-23				Remove	Temporary Cor	crete Barrier (I	-81 NB) (Area 4	I) (Phase 2)		
	3235	Establish Temp. MOT/Shift Traffic (I-81 NB) (Area 4) (Phase 2)		2 10-31-23	11-02-23				Establish	Temp. MOT/S	hift Traffic (I-81	NB) (Area 4) (F	Phase 2)		
	- I-81 SB			358 04-08-22	02-01-24		<b></b>		02-01	-24, I-81 SB					
	AREA 1			266 06-27-22	10-19-23		-		▼ 10-19-23,	AREA 1					
	<b>=</b> 3905	Install Temporary Concrete Barrier (I-81 SB) (Area 1) (Phase 2)		5 06-27-22	07-01-22		l Insta	all Tempor	ary Concrete	Barrier (I-81 S	B) (Area 1) (Ph	ase 2)			
	<b>=</b> 3915	Grading/Excavation (I-81 SB) (Area 1) (Phase 2)		10 07-21-22	08-05-22		🛛 Gra	ading/Exca	vation (I-81 S	\$B) (Aręa 1) (F	hase 2)				
	<b>=</b> 3925	Install Storm Drainage (I-81 SB) (Area 1) (Phase 2)		20 08-12-22	09-12-22		🛛 In	stall Stom	h Drainage (I-	-81 SB) (Area	1) (Phase 2)				
	<b>=</b> 3935	Install Median Barrier (I-81 SB) (Area 1) (Phase 2)		9 09-02-22	09-16-22		0 In	stall Medi	an Barrier (I-8	81 SB) (Area 1	) (Phase 2)				
	<b>=</b> 3945	Install Aggregate Base Course (I-81 SB) (Area 1) (Phase 2)		14 09-09-22	09-30-22		0 Ir	hstall Aggr	egate Base 0	Course (I-81 SI	3) (Area 1) (Ph	ase 2)			
	3955	Install Asphalt Base Course (I-81 SB) (Area 1) (Phase 2)		11 09-19-22	10-04-22		0 li	nstall Asph	halt Base Cou	urse (I-81 SB) i	(Area 1) (Phase	ə 2)			
	<b>=</b> 3965	Install Asphalt Intermediate Course (I-81 SB) (Area 1) (Phase 2)		3 10-06-22	10-10-22			nstall Aspl	halt Intermed	liate Course (I-	81 SB) (Area 1	) (Phase 2)			
	<b>=</b> 3975	Install Guardrail (I-81 SB) (Area 1) (Phase 2)		6 10-07-22	10-17-22		0 1	Install Gua	ardrail (I-81 SI	B) (Area 1) (Ph	ase 2)				
	3985	Remove Temporary Concrete Barrier (I-81 SB) (Area 1) (Phase 2)		5 10-18-22	10-24-22		11	Remove T	emporary Co	ncrete Barrier	(I-81 SB) (Area	1) (Phase 2)			
	3995	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 1) (Phase 2)		3 10-25-22	10-27-22		1	Establish	Temp. MOT/S	Shift Traffic (I-8	1 SB) (Area 1)	(Phase 2)			
	I-81 OVER RTE	. 112 BRIDGE		242 08-08-22	10-19-23		-		▼ 10-19-23,	I-81 OVER RT	E. 112 BRIDG	E			
	<u> </u>	Partial Structure Removal (I-81 SB Over Rte. 112) (Area 1) (Phase	2)	16 08-08-22	08-30-22		🛿 Pa	artial Struc	ture Remova	ll (I-81 SB Ove	r Rte. 112) (Are	a 1) (Phase 2)			
	<b>—</b> 4015	Support of Excavation/Structure Excavation (Abutment A) (I-81 SE	3 Over Rte. 112) (Area 1) (Phas	10 08-31-22	09-15-22		I S	upport of	Excavation/S	tructure Excav	ation (Abutmer	nt A) (I-81 SB O	ver Rte. 112)	(Area 1) (P	hase 2)
	<b>—</b> 4025	Drive Piles (Abutment A) (I-81 SB Over Rte. 112) (Area 1) (Phase	2)	6 09-16-22	09-26-22		ID	rive Piles	(Abutment A)	(I-81 SB Over	Rte. 112) (Are	a 1) (Phase 2)			
	<b>—</b> 4035	Construct MSE Walls (Abutment A) (I-81 SB Over Rte. 112) (Area	1) (Phase 2)	24 10-10-22	11-15-22			Construct	M\$E Walls (	(Abutment A) (	I-81 SB Over R	tte. 112) (Area 1	) (Phase 2)		
	<b>—</b> 4045	FRP Abutment (Abutment A) (I-81 SB Over Rte. 112) (Area 1) (Ph	ase 2)	10 11-17-22	12-05-22		0	FRP Abu	tment (Abutn	nent A) (I-81 S	B Over Rte. 11	2) (Area 1) (Ph	ase 2)		
	<b>—</b> 4055	Support of Excavation/Structure Excavation (Abutment B) (I-81 SE	B Over Rte. 112) (Area 1) (Phas	10 04-11-23	05-01-23			🛛 Sup	oport of Exca	vation/Structu	e Excavation (	Abutment B) (I-	81 SB Over R	tte. 112) (Ar	ea 1) (Phase 2
	<b>—</b> 4065	Construct MSE Walls (Abutment B) (I-81 SB Over Rte. 112) (Area	1) (Phase 2)	24 05-02-23	06-15-23			🗖 C	onstruct MSE	Walls (Abutn	ient B) (I-\$1 \$E	3 Over Rte. 112	) (Area 1) (Ph	ase 2)	
	<b>—</b> 4075	Drive Piles (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Phase	2)	6 06-16-23	06-26-23			<b>I</b> C	prive Piles (Ab	outment B) (I-8	1 SB Over Rte	. 112) (Area 1) (	Phase 2)		
	<b>4085</b>	FRP Abutment (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Ph	ase 2)	10 06-27-23	07-13-23			01	RP Abutmer	nt (Abutment E	3) (I-81 SB Ove	r Rte. 112) (Are	a 1) (Phase 2	)	
	<b>4</b> 095	Girder Erection (I-81 SB Over Rte. 112) (Area 1) (Phase 2)		7 07-14-23	07-24-23				Girder Erectio	on (I-81 SB Ov	er Rte. 112) (Ar	rea 1) (Phase 2	)		
	<b>—</b> 4105	FRP Deck/Barrier Wall (I-81 SB Over Rte. 112) (Area 1) (Phase 2)		45 07-25-23	10-03-23				FRP Deck	/Barrier Wall (I-	81 SB Over Rte	e. 112) (Area 1)	(Phase 2)		
	<b>—</b> 4115	FRP Approach Slabs (I-81 SB Over Rte. 112) (Area 1) (Phase 2)		9 10-05-23	10-19-23				FRP Appro	oach Slabs (I-8	1 SB Over Rte	. 112) (Area 1)	(Phase 2)		
	6015	Support Of Excavation/Structure Excavation (Pier) (I-81 SB Over F	Rte. 112) (Area 1) (Phase 2)	10 12-06-22	12-22-22		0	Support	Of Excavatio	on/Structure E	cavation (Pier)	, (I-81 SB Over I	Rte. 112) (Are	a 1) (Phase	∋ 2)
	6025	Install Micropiles at Pier (I-81 SB Over Rte. 112) (Area 1) (Phase 2	2)	23 12-23-22	02-21-23		[	🔲 🔤 Instal	Micropiles at	t Pier (I+81 SB	Over Rte. 112)	(Area 1) (Phas	e 2)		
	6035	FRP Pier Footer (I-81 SB Over Rte. 112) (Area 1) (Phase 2)		10 02-24-23	03-13-23			I FRP	Pier Footer (I	-81 SB Over R	tte. 112) (Åreå	1) (Phase 2)			
	6045	FRP Pier Stem/Cap (I-81 SB Over Rte. 112) (Area 1) (Phase 2)		14 03-14-23	04-10-23			🛛 FRF	Pier Stem/C	Cap (I-81 SB O	ver Rte. 112) (A	Area 1) (Phase i	2)		
	AREA 2			284 04-13-22	09-15-23			•	09-15-23, A	AREA 2					
	3565	Install Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 2)		5 10-28-22	11-04-22			Install Ten	nporary Conc	crete Barrier (I-	31 SB) (Area 2)	) (Phase 2)			
	3575	Grading/Excavation (I-81 SB) (Area 2) (Phase 2)		18 11-08-22	12-09-22			Grading/	Excavation (I	I-81 SB) (Area	2) (Phase 2)				
	<b>a</b> 3585	Install Storm Drainage (I-81 SB) (Area 2) (Phase 2)		37 12-20-22	03-17-23			lnsta	Il Storm Drair	nage (I-81 SB)	(Area 2) (Phas	e 2)			
	<b>=</b> 3595	Install Median Barrier (I-81 SB) (Area 2) (Phase 2)		16 02-24-23	03-27-23			📕 Insta	III Median Ba	urrier (I-81 SB)	Area 2) (Phase	∋2)			
	3605	Install Aggregate Base Course (I-81 SB) (Area 2) (Phase 2)		25 03-03-23	04-21-23			📕 Inst	all Aggregate	e Base Course	(I-81 SB) (Area	a 2) (Phase 2)			
	<b>a</b> 3615	Install Asphalt Base Course (I-81 SB) (Area 2) (Phase 2)		20 03-17-23	04-25-23			📕 Inst	all Asphalt Ba	ase Course (I-8	31 SB) (Area 2)	) (Phase 2)			
	3625	Install Asphalt Intermediate Course (I-81 SB) (Area 2) (Phase 2)		6 04-27-23	05-05-23			l Ins	tall Asphalt In	ntermediate Co	ourse (I-81 SB)	(Area 2) (Phase	e 2)		
	<b>—</b> 3635	Install Guardrail (I-81 SB) (Area 2) (Phase 2)		15 04-28-23	05-25-23			📕 Ins	stall Guardrail	l (I-81 SB) (Are	a 2) (Phase 2)				
	<b>a</b> 3645	Remove Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 2)		4 05-26-23	06-02-23			I Re	emove Temp	orary Concrete	Barrier (I+81 S	B) (Area 2) (Ph	ase 2)		
	3655	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 2) (Phase 2)		3 06-05-23	06-08-23			I E	stablish Temp	o. MOT/Shift T	affic (I-81 SB)	(Area 2) (Phase	2)		
	I-81 OVER RTE.	. 619 BRIDGE		209 04-13-22	05-11-23			▼ 05	-11-23, I-81 C	OVER RTE: 61	9 BRIDGE				
	3665	Partial Structure Removal (I-81 SB Over Route 619) (Area 2) (Pha	se 2)	13 04-13-22	05-09-22		Partial	Structure	Removal (I-8	31 SB Over Ro	ute 619) (Area	2) (Phase 2)			
	<b>a</b> 3675	Support of Excavation/Structure Excavation (Abutment A) (I-81 SE	3 Over Route 619) (Area 2) (Pha	10 05-10-22	05-27-22		Suppo	ort of Exca	avation/Struct	ture Excavatio	n (Abutment A)	(I-81 SB Over I	Route 619) (A	rea 2) (Pha	ise 2)
	Actual Level of Effort	Remaining Work    Critical Remaining Work      Vertical Remaining Work      Summary		Page 7 of 13				Branch-	Orders Joint	Venture					

1020300	108		I-81 Widening MM 136.6 - MM 141.8	Proposal Sched	lule									03-0	1-21 10:4
ID		Activity Name	Original Start Duration	Finish	2021	2022	2023	2024		2026	20	27	2028	2029	2030
	<b>—</b> 3685	Drive Piles (Abutment A) (I-81 SB Over Route 619) (Area 2) (Phase 2)	7 05-31-22	06-10-22				ent A) (1-81 S		2.619) (Area	2) (Phas				
	3695	Construct MSE Walls (Abutment A) (I-81 SB Over Route 619) (Area 2) (Phase 2)	27 07-07-22	08-19-22			onstruct MSF	Walls (Abutn	hent A) (I-81 S	B Over Rou	ute 619) (	Area 2) (P	hase 2)		
	3705	FRP Abutment (Abutment A) (I-81 SB Over Route 619) (Area 2) (Phase 2)	10 08-22-22	09-02-22		l F		(Abutment A	).(I-81 SB Ov	er Route 61	9) (Area 2	(Phase	2)		
	3715	Support of Excavation/Structure Excavation (Abutment B) (I-81 SB Over Route 619) (An	ea 2) (Ph; 10, 09-06-22	09-20-22		Π .		avation/Strue	ture Excavat	on (Abutme	ent B) (I-8	1 SB Ove	r Route 61	9) (Area 2) (F	hase 2
	3725	Construct MSE Walls (Abutment B) (I-81 SB Over Route 619) (Area 2) (Phase 2)	27 09-21-22	11-01-22			Construct M	SF Walls (Ab	utment B) (I-8	1 SB Over F	Route 619	) (Area 2)	(Phase 2)	·) (cu _) (.	
	3735	Drive Piles (Abutment B) (I-81 SB Over Route 619) (Area 2) (Phase 2)	7 11-03-22	11-14-22			Drive Piles (/	butment B)	(I-81 SB Over	Route 619)	) (Area 2)	(Phase 2)	)		
	3745	FRP Abutment (Abutment B) (I-81 SB Over Route 619) (Area 2) (Phase 2)	10 11-15-22	12-02-22			FRP Abutm	ant (Abiutmer	of B) (I-81 SB	Over Route	619) (Arr	(1 1 0 0 2)	/ (se 2)		
	3755	Girder Erection (I-81 SB Over Route 619) (Area 2) (Phase 2)	6 12-05-22	12-13-22			Girder Fred	tion (I-81 SB	Over Route 6	19) (Area 2)	) (Phase '	2)			
	3765	FRP Deck/Barrier Wall (I-81 SB Over Route 619) (Area 2) (Phase 2)	40 01-31-23	04-24-23				eck/Barrier M		ver Route 6	) (111000 2 (19) (Area	-/ 2) (Phase	a 2)		
	3775	FRP Approach Slabs (I-81 SB Over Route 619) (Area 2) (Phase 2)	10 04-25-23	05-11-23				borbach Slal	ns (I+81 SB O	ver Route 6	19) (Area	2) (Phase	2)		
			202 09-07-22	09-15-23				9-15-23 I-81			F				
	3785	Partial Structure Removal (I-81 SB Over Rte, 635) (Area 2) (Phase 2)	15 09-07-22	09-29-22			Partial Structu	re Removal (	I-81 SB Over	Rte. 635) (A	- Area 2) (P	hase 2)			
	3795	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte, 635) (Area	2) (Phas 12 09-30-22	10-19-22		n	Support of F	cavation/Str	icture Excava	tion (Abutm	100 - 1 (1-5		er Rte 635	) (Area 2) (Pl	1256 2)
	3805	Drive Piles (Abutment A) (I-81 SB Over Rte, 635) (Area 2) (Phase 2)	6 10-20-22	10-27-22			Drive Piles (A	butment A) (	-81 SB Over	Rte (635) (A	area 2) (Pl	hase 2)		/ (/ 100 2) (1 1	100 L)
	3815	Construct MSE Walls (Abutment A) (I-81 SB Over Rte, 635) (Area 2) (Phase 2)	21 11-14-22	12-20-22				ASE Walls (A	butment A) (I	81 SB Over	r Rte 635	i) (Area 2)	(Phase 2)		
	3825	FRP Abutment (Abutment A) (L81 SB Over Rtg. 635) (Area 2) (Phase 2)	10 12-22-22	01-20-23				hen't (Abutm		B Over Bte	635) (Arc	) (Aica 2)	(1 1123¢ Z)		
	<u> </u>	Support of Excavation/Structure Evcavation (Abutment R) (LS1 SR Over Pte 625) (Area	2) (Phas 12 01-22-22	07-20-23				of Exceluation	Structure Ev	cavation (Al	hutment	אין (ו <u>-</u> גזי רייומ: א) (ו <u>-</u> גזי פר		635) (Area '	) (Pho
		Construct MSE Wolls (Abutmont B) (1.81 SB Over Bto . 625) (Area 2) (Bhase 2)	22) (Filds 12 01-23-23	02-17-23	_							5) (1-01, 30		033) (Alea 2	) (Filas
	- 2955	Drive Biles (Abutment B) (181 SB Over Pto, 625) (Area 2) (Phase 2)	6 04 02 23	04 11 22	_			iloc'(Abutmo					a 2) (Filas	; 2)	
	3000	Drive Files (Abutment B) (161 SB Over Ric. 635) (Alea 2) (Filase 2)	04-03-23	04-11-23	_			hutmont (Abu				(Area 2) (			
	3805	Circles Exercises (I 04 CB Cruze Dts. C25) (Area 2) (Phase 2)	10 04-14-23	05-02-23								(Area 2) (F	nase 2)		
	3875	Girder Erection (I-81 SB Over Rte. 635) (Area 2) (Phase 2)	6 05-04-23	05-12-23				Erection (I-8		e. 635) (Are	a z) (Pnac				
	3885	FRP Deck/Barrier Wall (I-61 SB Over Rie, 035) (Alea 2) (Phase 2)	40 00-29-23	00-30-23	_						), 035) (Ar		ase 2)		
	3895	FRP Approach Slabs (I-81 SB Over Rte. 635) (Area 2) (Phase 2)	10 08-31-23	09-15-23				KP Approach	51aps (1-81 5	B Over Rte.	. 635) (Are	ea 2) (Pha	ase 2)		
	AREA 3	Install Temporary Constata Parties (1.91 SP) (Area 2) (Dhasa 2)	5 06 00 22	10-10-23				10-10-23, AR	EA 3	nor (1 01 SD	Aroa 2	Dhana G			
	3405 3475	Crading/Evenuation (L91 SP) (Area 2) (Phase 2)	17 06 15 22	07 12 22	_							(Fildse Z	-/		
	3475	Grading/Excavation (1-61 SB) (Area 3) (Phase 2)	17 00-15-23	07-13-23	_			ung/Excava			lase z)	5			
	3465	Install Stoff Dialinage (I-81 SB) (Area 3) (Phase 2)	38 00-23-23	08-22-23					ainage (i-o i		(Phase 2				
	3495	Install Median Barrier (I-81 SB) (Area 3) (Phase 2)	15 08-03-23	08-25-23	_			stall iviedian	Barner (I-81 S	B) (Area 3)	(Phase 2)				
	3505	Install Aggregate Base Course (I-81 SB) (Area 3) (Phase 2)	24 08-10-23	09-15-23				istali Aggrega	ate Base Cou	se (1-81 SB	) (Area 3)	(Phase 2)	)		
_	3515	Install Asphalt Base Course (I-81 SB) (Area 3) (Phase 2)	19 08-21-23	09-19-23				nstall Asphalt	Base Course	(I-81 SB) (A	Area 3) (Pi	nase 2)			
	3525	Install Asphalt Intermediate Course (I-81 SB) (Area 3) (Phase 2)	6 09-20-23	09-28-23				nstall Asphal		Course (I-8	1 SB) (Ar	ea 3) (Pha	ase 2)		
_	3535	Install Guardrail (I-81 SB) (Area 3) (Phase 2)	5 09-21-23	09-28-23	_			nstall Guardr	ail (I-81 SB) (/	Area 3) (Pha	ise 2)				
_	3545	Remove Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 2)	4 09-29-23	10-05-23				Remové Tem	porary Concre	ete Barrier (I	-81 SB) (/	Area 3) (Pl	hase 2)		
_	3555	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 3) (Phase 2)	3 10-06-23	10-10-23				Establish Ten	np. MOT/Shif	Traffic (I-81	SB) (Are:	a 3) (Phas	se 2)		
	I-81 OVER RTE	E. 311 BRIDGE	174 04-08-22	02-27-23			02-27-23	3, I-81 OVER	RTE. 311 BR	IDGE					
	3345	Partial Structure Removal (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	10 04-08-22	04-26-22		D Partia	Structure Re	moval (1-81 S	B Over Rte.	(Area 3)	) (Phase 2	2)			
	3355	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte. 311) (Area	13) (Phas 16 05-10-22	06-07-22		L Sup	port of Excava	ition/Structure	Excavation	(Abutment A	4) (I-81 SE	3 Over Rte	ə. 311) (Are	a 3) (Phase	2)
	3365	Drive Piles (Abutment A) (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	6 06-10-22	06-20-22		U Drive	e Piles (Abutn	nent A) (I-81 \$	SB Over Rte.	311) (Area :	3) (Phase	2)			
	3385	FRP Abutment (Abutment A) (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	18 06-24-22	07-25-22		FR	P Abutment (	Abutment A)	(I-81 SB Ove	Rte. 311) (/	Area 3) (P	hase 2)			
	3395	Support of Excavation/Structure Excavation (Abutment B) (I-81 SB Over Rte. 311) (Area	a 3) (Phas 16 07-26-22	08-19-22			upport of Exca	vation/Struct	ure Excavatio	n (Abutmer	nt B) (I-81	SB Over	Rte. 311) (	Area 3) (Pha	se 2)
	<b>—</b> 3415	Drive Piles (Abutment B) (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	6 08-22-22	08-29-22			rive Piles (Abı	itment B) (I-8	1 SB Over Rt	e. 311) (Are	a 3) (Pha	se 2)			
	<b>3</b> 425	FRP Abutment (Abutment B) (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	18 08-30-22	09-27-22			FRP Abutmen	t (Abutment I	3) (I-81 SB O	/er Rte. 311	) (Area 3)	(Phase 2)	)		
	<b>a</b> 3435	Girder Erection (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	4 09-28-22	10-03-22			Girder Erectio	n (I-81 SB O\	/er Rte. 311) (	Area 3) (Pha	ase 2)				
	<b>3</b> 445	FRP Deck/Barrier Wall (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	35 10-31-22	01-10-23			FRP Deck	Barrier Wall (	I-81 SB Over	Rte. 311) (A	vrea 3) (Pl	nase 2)			
	<b>—</b> 3455	FRP Approach Slabs (I-81 SB Over Rte. 311) (Area 3) (Phase 2)	20 01-13-23	02-27-23			FRP App	roach Slabs	(I-81 SB Ove	Rte. 311) (/	Area 3) (P	hase 2)			
5	AREA 4		56 10-12-23	02-01-24			-	🔽 02-01-24	, AREA 4						
	3245	Install Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2)	5 10-12-23	10-19-23				Install Tempo	orary Concrete	Barrier (I-8	1 SB) (Are	∋a 4) (Pha	ase 2)		
	3255	Grading/Excavation (I-81 SB) (Area 4) (Phase 2)	12 10-17-23	11-03-23				Grading/Exc	avation (I-81	SB) (Area 4)	) (Phase 2	2)			: : '
	3265	Install Storm Drainage (I-81 SB) (Area 4) (Phase 2)	16 10-25-23	11-20-23				Install Storn	n Drainage (I-	81 SB) (Area	a 4) (Pha	se 2)			
	3275	Install Median Barrier (I-81 SB) (Area 4) (Phase 2)	11 11-07-23	11-28-23				Install Medi	an Barrier (I-8	1 SB) (Area	ı 4) (Phas	e 2)			
	3285	Install Aggregate Base Course (I-81 SB) (Area 4) (Phase 2)	18 11-14-23	12-15-23				Install Agg	egate Base (	ourse (I-81	SB) (Area	a 4) (Phas	e 2)		

C00	116203DB	3108		I-81 Wide	ning MM 136.6 - MM 14	1.8 Proposal Sched	lule							03	3-01-21 10:45
Activity	' ID		Activity Name		Original Start	Finish	2021 2022	2023	2024	2025	2026	2027	2028	2029	2030
					Duration									QQQ	
		3295	Install Asphalt Base Course (I-81 SB) (Area 4) (Phase 2)		15 11-29-23	01-02-24			Install Asp	nalt Base Cou	urse (I-81 SB) (/	Area 4) (Phas	e 2)		
		<b>3</b> 305	Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 2)		5 01-03-24	01-15-24			Install Asp	halt Intermedi	iate Course (I-{	31 SB) (Area	4) (Phase 2)		
		3315	Install Guardrail (I-81 SB) (Area 4) (Phase 2)		6 01-08-24	01-17-24			Install Gua	ardrail (I-81, SE	3) (Area 4) (Pha	ase 2)			
		3325	Remove Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 2)		4 01-22-24	01-29-24			Remove	Temporary Co	ncrete Barrier (	(I-81 SB) (Are	a 4) (Phase 2	2)	
		<b>a</b> 3335	Establish Temp. MOT/Shift Traffic (I-81 SB) (Area 4) (Phase 2)		3 01-30-24	02-01-24			I Establish	Temp. MOT/S	Shift Traffic (I-8	1 SB) (Area 4	) (Phase 2)		
		ASE 3			329 10-20-23	07-18-25				<b>07-1</b>	18-25, PHASE	3			
		-81 NB			265 10-20-23	03-21-25				03-21-2	.5, I-81 NB				
		AREA 1	Justell Tennessen (Caronate Damian (LOA ND) (Area 4) (Dhaca 2)		243 10-20-23	01-28-25			La stall Tanan	▼ 01-28-25,	AREA 1		(Dhanar 0)		
		4125	Install Temporary Concrete Barrier (T-81 NB) (Area 1) (Phase 3)		9 11-03-23	11-17-23				orary Concrete	e Barrier (1 <del>1</del> 81 h	NB) (Area; 1) (	Phase 3)		
		4135	Grading/Excavation (I-81 NB) (Area 1) (Phase 3)		5 11-13-23	11-20-23				avation (I-81 I	NB) (Area T) (P	mase 3)			
		4145	Install Storm Drainage (I-81 NB) (Area 1) (Phase 3)		30 11-16-23	01-23-24			Install Sto	rm Drainage (	(I-81 NB) (Area	1) (Phase 3)	- 4) (5) (		
		4150	Install Site Lighting/TS Installation (I-81 NB) (Area 1) (Phase 3)		53 11-16-23	03-12-24			Install S	ite Lighting/11	5 Installation (I	I-81 INB) (Area	a 1) (Phase 3	9	
		4155	Install Median Barrier (I-81 NB) (Area 1) (Phase 3)		5 02-12-24	02-20-24				edian Barrier (	(I-81 NB) (Area	1) (Phase 3)			
		4165	Install Aggregate Base Course (I-81 NB) (Area 1) (Phase 3)		14 01-02-24	01-31-24			Install Ag	gregate Base	Course (I-81 N	IB) (Area 1) (F	hase 3)		
		4175	Install Asphalt Base Course (I-81 NB) (Area 1) (Phase 3)		11 01-17-24	02-08-24			Install As	phalt Base Co	ourse (I-81 NB)	(Area 1) (Pha	ISE 3)		
		4185	Install Asphalt Intermediate Course (I-81 NB) (Area 1) (Phase 3)		3 02-12-24	02-15-24			I Install As	phalt Intermed	diate Course (I-	-81 NB) (Area	1) (Phase 3)	2	
		4195	Install Guardrail (I-81 NB) (Area 1) (Phase 3)		5 02-13-24	02-22-24			I Install G	uardrail (I-81 N	VB) (Area 1) (PI	hase 3)			
		4205	Construct Noise Walls (Sta 134+50 - 156+00) (I-81 NB) (Area 1) (Phas	ie 3)	40 11-13-23	02-08-24				Noise Walls (	(Sta 134+50 - 1	156+00) (1-81	NB) (Area 1)	(Phase 3)	/
		4215	Restoration/Landscaping (I-81 NB) (Area 1) (Phase 3)		5 03-15-24	03-25-24			Restora	tion/Landscar		(Area 1) (Pha	se 3)		
		<b>1-81 OVER RTE</b> .	112 BRIDGE Destial Structure Removal /( 81 NR Quar Bts. 112) (Area 1) (Phase 2)		243 10-20-23	01-28-25			Dortiol Strug	▼ 01-28-25,		E. 112 BRID	.jE 00.4)(Dhaoo	2)	
		4225	Support of Exception/Structure Exception (Abutment A) (1.81 NB Ov	or Pto 112) (Area 1) (Phas	10 11 20 22	12 07 22			Support of	Evolution/St				B Over Pte	112) (Arbo 1)
		4235	Drive Biles (Abutment A) (1.81 NP Over Bto 112) (Area 1) (People 2)	er Rie. 112) (Alea I) (Filas	0 12 09 22	01 02 24									. 112) (Alea 1)
		4245	Drive Pries (Adulthent A) (1-61 NB Over Rie, 112) (Area 1) (Priase 3)		9 12-08-23	01-02-24								3)	20.2)
		4200	Construct MSE Walls (Abutment A) (1-61 NB Over Re. 112) (Area 1) (F	nase 3)	7 02 42 24	02-12-24					Abuimeni A) (I-		(Ale		se s)
		4200	FRP Adulthent (Adulthent A) (I-61 NB Over Rte. 112) (Alea 1) (Phase	3)	7 02-13-24	02-27-24				iment (Abum	ient A) (I-6 I NE		(Alea I)		
		4275	Support of Excavation/Structure Excavation (Abuthent B) (1-61 NB C	Phase 2)	18 07-08-24	08-02-24								) (I-0 I IND) 11 2) (Area	
		4285	Construct MSE wails (Abutment B) (1-61 NB Over Rte. 112) (Area 1) (1	-nase 3)	18 08-05-24	08-30-24								12) (Alea	1) (Priase 3)
		4295	Drive Piles (Abuthent B) (1-61 NB Over Rie. 112) (Alea 1) (Priase 3)	2)	9 09-03-24	09-16-24					Ulment D) (I-o I				3)
		4305	Circler Exerction (LS1 NB Over Rte. 112) (Area 1) (Phase	3)	7 09-17-24	09-26-24								(Pn	ase 3)
		4315	Girder Erection (I-81 NB Over Rte. 112) (Area 1) (Phase 3)		8 09-27-24	10-08-24						1 Rte. 112) (A	rea 1) (Phase	3)	
		4325	FRP Deck/Barrier Wall (1-81 NB Over Rte. 112) (Area 1) (Phase 3)		45 10-10-24	01-07-25					Bamer vvali (i-a			a T) (Phase	e 3)
		4335	FRP Approach Stabs (I-81 NB Over Rte. 112) (Area 1) (Phase 3)	(Area 4) (Dhaaa 2)	9 01-09-25	01-28-25					oach Slabs (I-8	1 NB Over R	.e. 112) (Area	11) (Phase	3)
		0075	Support of Excavation/Structure Excavation Pier (I-81 NB Over Rte. 1)	(Area 1) (Phase 3)	7 02-29-24	03-12-24			Support	or Excavation	1/Structure Exc	avation Pier		Rte. 112)	(Area T) (Phas
		6075	Install Micropiles at Pier (I-81 NB Over Rte. 112) (Area 1) (Phase 3)		32 03-15-24	05-16-24				Diad Diates (		Jver Rte. 112	) (Area 1) (Pr	lase 3)	
		6085	FRP Pier Footer (I-81 NB Over Rte. 112) (Area 1) (Phase 3)		10 05-17-24	06-04-24				Pier Footer (I-	81 NB Over Rt	.e. 112) (Area	1) (Phase 3)		
		6095	FRP Pier Stem/Cap (I-81 NB Over Rte. 112) (Area 1) (Phase 3)		18 06-06-24	07-05-24				Pier Stem/Ca	ap (I-81 NB OV	er Rte. 112) (	Area 1) (Pha	se 3)	
			Install Tomporany Concrete Barrier // 81 NB) (Area 2) (Phase 3)		205 11-03-23	03 04 24				11-19-24, AF	REA2	91 NIP) (//mod	2) (Phace 3)		
		5105	Grading/Execution (1.81 NP) (Area 2) (Phase 3)		0 02 05 24	03-04-24							2) (Flidse 3)		
		5195 5205	Install Storm Drainage (1.81 NB) (Area 2) (Phase 3)		55 02 12 24	05-25-24						2) (Fliase 3)	200 2)		
		<b>5205</b>	Install Stollin Dialitage (I-oT ND) (Area 2) (Filase 3)		05 03 12 24	08-29-24					laye (I-o I IND)		(Arch 2)	haab 2)	
		<b>5</b> 215	Install Site Lighting/115 Installation (1-81 NB) (Area 2) (Phase 3)		95 03-12-24	08-28-24				stall Sile Light	ung/115 Installa		(Area 2) (Pr	lase 3)	
		<b>5</b> 225	Install Median Baller (1-01 NB) (Alea 2) (Filase 3)		25 05 21 24	07 12 24								2)	
		<b>5235</b>	Install Aggregate Base Course (I-81 NB) (Area 2) (Phase 3)		25 05-31-24	07-12-24					base course (		a ∠) (Phase ;	)	
		<b>524</b> 5	Install Apphalt Intermediate Course (1.81 ND) (Area 2) (Phase 3)		6 07 17 24	07-16-24				all Asphalt In	ise course (i-o		) (Fildse 3) ) (Aroo 2) (Dt	200 2)	
		<b>5255</b>	Install Asphalt Intermediate Course (For TND) (Area 2) (Phase 3)		6 07-17-24	07-25-24							(Alea 2) (Pri	ase 3)	
		5265	Install Guardrall (I-81 NB) (Area 2) (Phase 3)		5 07-18-24	07-25-24			l ins	tall Guardrall (	(I-81 NB) (Area	2) (Phase 3)			
		<u>5275</u>	Construct Noise Walls (Sta 156+00 - 235+00) (I-81 NB) (Area 2) (Phas	ie 3)	130 03-26-24	10-31-24				Construct Noi	ise Walls (Sta	156+00 - 235	+00) (I-81 NE	3) (Area 2)	(Phase 3)
		5285	Restoration/Landscaping (I-81 NB) (Area 2) (Phase 3)		5 11-12-24	11-19-24				Restoration/I	Landscaping (I	-81 NB) (Area	1 2) (Phase 3	)	
		1-81 OVER RTE.	635 BRIDGE		158 11-03-23	09-04-24				9-04-24, I-81 (	OVERRIE. 63	35 BRIDGE			
		4345	Prantial Structure Removal (I-S1 NB Over Rte. 635) (Area 2) (Phase 3)		14 11-03-23	11-29-23			Panial Struc	iure Removal		RTE. 635) (Ar	ea∠) (Phase	3)	
		4355	Support of Excavation/Structure Excavation (Abutment A) (I-81 NB Ov	er Rie. 635) (Area 2) (Phas	10 11-30-23	12-15-23			Support of	Excavation/St	tructure Excava	ation (Abutme	int A) (I-81 N	3 Over Rte	. 635) (Area 2)
	Actua	al Level of Effort	Remaining Work    Critical Remaining Work      Summary		Page 9 of 13			Branch-Ord	ers Joint Ve	nture					

			11ng MIN 136.6 - MIN 141.8	Proposal Sched	luie					03-01-21 10:45
,	Activity Name		Original Start	Finish	2021 2022	2023 2024	2025 2	2026 2027	2028	2029 2030
426	E Drive Diles (Abutment A) (L94 ND Quer Dts. 625) (Area 3) (Dease	2)	10 10 10 00	01.16.24						
	5 Drive Files (Abutinent A) (1-61 ND Over Rte. 055) (Alea 2) (Filase 5 Construct MSE Walls (Abutmont A) (1.81 NB Over Bto, 635) (Area	2) (Phase 2)	14 01 17 24	02 15 24					(Aled 2) (Filds	(Dhaca b)
	5 EPD Abutment (Abutment A) (1.81 NB Over Pte, 625) (Area 2) (Pb		10 02 10 24	02-15-24	_				625) (Aroa 2)	
	5 Provide a support of Execution/Structure Execution (Abutment P) (1.81 NB	$R \cap r$	10 02-19-24	03-00-24			of Executation/Str		(Alea 2)	(Flidse J)
	5 Construct MSE Walls (Abutmont B) (191 NB Over Pto, 635) (Area	2) (Phase 2)	14 04 01 24	04.26.24				utmont P) (1 91 NP		(Arda 2) (Phase 3)
	5 Construct MSE Walls (Abutment B) (I-o1 NB Over Rte. 055) (Area 5 Drive Biles (Abutment B) (I-o1 NB Over Bte. 625) (Area 2) (Bease	2) (Fildse 3)	14 04-01-24	04-20-24						
	5 EPD Abutment (Abutment B) (191 NB Over Re. 055) (Alea 2) (Phase	3) 200 2)	10 04-29-24	06.04.24			hutmont (Abutmo		Dto 625) (Alea 2) (F	$(D_{P})$
442	5 FRF Abulthent (Abulthent B) (For NB Over Rie. 635) (Area 2) (Fit		10 05-17-24	06-04-24			r Fraction (1.91 NF		Rie. 033) (Alea	2) (Flidse 3)
	5 Gilder Election (I-or ND Over Rie, 055) (Alea 2) (Place 3) 5 EDD Dook/Parrier Wall (I 21 ND Over Pta, 625) (Area 2) (Phace 2)		27 06 24 24	08-20-24						(Dhace 2)
	5 FRF Deck/Dallier Wall (For TND Over Rie, 055) (Area 2) (Fridse 5)		0 00 22 24	00-20-24					(Area 2)	Phone 2)
	(FR PTE 640 PPIDCE		9 00-22-24	09-04-24					035) (Alea 2) (F	mase 5)
	5 Partial Structure Removal (L81 NB Over Rte, 610) (Area 2) (Phase	3)	14 11-03-23	11-29-23		Partial Struct	ura Removal (I-81		(Δrog 2) (Phase	13)
	5 Support of Excavation/Structure Excavation (Abutment A) /L81 NE	3 Over Pte 619) (Area 2) (Phas	10 11-30-23	12-15-23				re Excavation (Abur	(Aica 2) (I 11230	B Over Pte 619) (Area
	5 Drive Piles (Abutment A) (I-81 NB Over Pte, 610) (Area 2) (Phase	3)	10 12-18-23	01-16-24			(Abutment A) (L-81	NB Over Pte 610		
	5 Diver ries (Abutheni A) (For the Over file, 015) (Alea 2) (Filase 5 Construct MSE Walls (Abutmont A) (1.81 NR Over Bto, 610) (Area	2) (Phase 2)	14 01 17 24	02 15 24					(Alea 2) (1 has	
449	5 EPD Abutment (Abutment A) (1.81 NP Quer Pte, 610) (Area 2) (Pb		14 01-17-24	02-15-24					$e_1 (A = 0.00) (A = $	
450	5 FRF Abulthent (Abulthent A) (For ND Over Rie. 619) (Aled 2) (Fi	(Area 2)	10 02-19-24	03-00-24			of Execution/Str	vi (I-o I ND Uver Rie	(Alea 2)	
451	5 Support of Excavation//Structure Excavation (Abutment B) (1-61 No	2) (Phase 2)	10 03-11-24	03-29-24						Area 2) (Phase 2)
452	5 Construct MSE wails (Abutment B) (I-81 NB Over Rte. 619) (Area 5 Drive Biles (Abutment B) (I-81 NB Over Bte. 610) (Area 2) (Bease	2) (Phase 3)	14 04-01-24	04-20-24	_		CLIVISE Walls (AD			(Area 2) (Priase 3)
453	5 Drive Pries (Abutment B) (1-61 NB Over Rte. 619) (Alea 2) (Phase 5 EDD Abutment (Abutment B) (1-81 NB Over Bto, 610) (Area 2) (Phase	3)	10 04-29-24	05-16-24			hutment (Abutment B)		019) (Alea 2) (A	(Depage 2)
454	5 FRP Abutment (Abutment B) (For NB Over Rie. 619) (Alea 2) (Ph	ase 3)	10 05-17-24	06-04-24			r Erretien (Abutme			2) (Phase 3)
455	5 Gildel Election (I-o1 NB Over Rte. 019) (Alea 2) (Phase 3) 5 EBD Deek/Parrier Well (I 21 NB Over Bte. 610) (Area 2) (Phase 3)		25 06 24 24	08 16 24			Doolk/Porrior Wo		ea 2) (Phase 3)	Dhdoo '2)
450	5 FRF Deck/Dalliel Wall (For TND Over Rie, 019) (Alea 2) (Flase 3)		0 08 10 24	08-20-24					610) (Area 2) (	
	5 FRP Apploach Slabs (1-81 NB Over Rie. 619) (Alea 2) (Phase 3)		9 06-19-24	01 21 25			P Apploach Slaps		619) (Alea 2) (F	mase 3)
AREA 3	Install Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 3)		5 07-26-24	01-21-25		Linst	UI-21-25, AREA	1.3 Jorete Barrier (I-81.1	IB) (Area 3) (Pha	250 3)
5305	Grading/Excavation (L81 NB) (Area 3) (Phase 3)		9 07-30-24	08-12-24			ding/Excavation (			
5315	Install Storm Drainage (L81 NB) (Area 3) (Phase 3)		45 08-02-24	10-11-24			stall Storm Drains	-on (L-81 NB) (Area	3) (Phase 3)	
5325	Install Storin Dialinage (101 NB) (Area 3) (Phase 3)		80 08-02-24	01-09-25			Ibstall Site Light	ting/ITS Installation	(1-81 NR) (Area	3) (Phace 3)
5335	Install Median Barrier (I-81 NB) (Area 3) (Phase 3)		5 12-16-24	01-02-25			Install Median B	arrier (I-81 NR) (Are		
<b>5</b> 345	Install Magroacto Rose Course (191 ND) (Area 3) (Phase 3)		24 00 12 24	10 17 24	_					202
5355	Install Apphalt Base Course (L81 NB) (Area 3) (Phase 3)		10 00-23-24	10-21-24						30 9)
5365	Install Asphalt Intermediate Course (I-81 NB) (Area 3) (Phase 3)		6 10-22-24	10-20-24			nstall Asphalt Inte	rmediate Course (I-		(Phase 3)
5375	Install Augraria (I-81 NB) (Area 3) (Phase 3)		5 10-24-24	10-30-24			nstall Guardrail (L	81 NB) (Area 3) (Ph	are 3)	(111030-0)
5385	Construct Noise Walls (Sta 235±00 - 281±00) (L81 NB) (Area 3) (F	Phase 3)	75 08-13-24	12-13-24				Walls (Sta 235+00	281-00) (I-81	NB) (Area 3) (Phase 3)
5305	Bestaration/Landscaning (L81 NB) (Area 3) (Phase 3)		5 01-13-25	01-21-25			Bestoration/Lar	ndecaning (L-81 NB)	(Area 3) (Phase	
	/ED DTE 211 DDDGE		100 11 02 22	06 17 24					(Alea 3) (I Hase	, , , , , , , , , , , , , , , , , , , ,
458	5 Partial Structure Removal (I-81 NB Over Rte 311) (Area 3) (Phase	3)	12 11-03-23	11-27-23		Partial Struct	ure Removal (I-81	NB Over Rte 311	(Area 3) (Phase	43)
- 459	5 Support of Excavation/Structure Excavation (Abutment A) (I-81 NE	3 Over Rte. 311) (Area 3) (Phas	10 11-28-23	12-12-23		Support of F	xcavation/Structu	re Excavation (Abut	ment A) (I-81 NF	B Over Rte. 311) (Area :
	5 Drive Piles (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Phase	3)	6 12-14-23	01-02-24		Drive Piles	Abutment A) (I-81	NB Over Rte. 311)	(Area 3) (Phase	3)
- 462	5 FRP Abutment (Abutment A) (I-81 NB Over Rte. 311) (Area 3) (Ph	ase 3)	7 01-03-24	01-17-24		I FRP Abutn	ent (Abutment A)	(I-81 NB Over Rte	311) (Area 3) (P	hase 3)
463	5 Support of Excavation/Structure Excavation (Abutment B) (I-81 N	3 Over Rte. 311) (Area 3) (Phas	10 01-22-24	02-08-24		Support o	Excavation/Struc	ture Excavation (Ar	utment B) (I-81	NB Over Rte 311) (Are
- 465	5 Drive Piles (Abutment B) (I-81 NB Over Rte. 311) (Area 3) (Phase	3)	6 02-12-24	02-22-24		<b>I</b> Drive Pile	(Abutment B) (I-	81 NB Over Rte 31	1) (Area 3) (Pha	se 3)
466	5 FRP Abutment (Abutment B) (I-81 NB Over Rte, 311) (Area 3) (Ph	ase 3)	7 02-26-24	03-08-24		I FRP Abu	ment (Abutment I	B) (I-81 NB Over Rt	e. 311) (Area 3)	(Phase 3)
- 467	5 Girder Frection (I-81 NB Over Rte. 311) (Area 3) (Phase 3)		7 04-08-24	04-22-24		I Girder i	rection (I-81 NB (	Wer Rte 311) (Arec	3) (Phase 3)	
- 468	5 FRP Deck/Barrier Wall (I-81 NB Over Rte, 311) (Area 3) (Phase 3)		14 04-23-24	05-17-24		FRP D	eck/Barrier Wall (I-	81 NB Over Rte. 31	1) (Area 3) (Pha	ase 3)
	5 FRP Approach Slabs (I-81 NB Over Rte 311) (Area 3) (Phase 3)		8 05-20-24	06-03-24			pproach Slabs (I-	81 NB Over Rte 31	1) (Area 3) (Pha	se 3)
<b>—</b> 612	5 Backwall & Joint Reconstruction (J-81 NB Over Rte. 311) (Area 3) (	(Phase 3)	14 03-11-24	04-05-24		Rackwa	& loint Reconstr	uction (I-81 NB Ove	r Rte (311) (Area	$a_3$ (Phase 3)
	5 Prep Existing Deck & Install Latex Overlay (I-81 NB Over Rte. 311	(Area 3) (Phase 3)	8 06-04-24	06-17-24			Existing Deck & In	stall Latex Overlav	(I-81 NB Over R	te 311) (Area 3) (Phase
			62 10-31-24	03-21-25				FA 4		
5405	Install Temporary Concrete Barrier (I-81 NB) (Area 4) (Phase 3)		5 10-31-24	11-08-24		n n	Install Temporary	Concrete Barrier (I-{	31 NB) (Area 4) (	(Phase 3)
					1 : 1 : 1 : 1 : 1 : 1 : 1				1 1 1 1 1 1 1 1 1 1 1 1	

C00116	6203DB108	I-81 W	/idening MM 136.6 - MM 141.8	Proposal Schedu	ıle									03-01-21 10:4	45
Activity ID		Activity Name	Original Start	Finish	2021	2022	202	3 2	2024	2025	2026	2027	2028	2029 2030	
			Duration				QQQQ								۲Q
	5425	Install Storm Drainage (I-81 NB) (Area 4) (Phase 3)	41 11-12-24	02-14-25						Install Stor	m Drainage	) (I-81 NB) (Ar	ea 4) (Phase	3)	
	<b>5</b> 435	Install Site Lighting/ITS Installation (I-81 NB) (Area 4) (Phase 3)	50 11-11-24	03-04-25						I Install Site	Lighting/IT	S Installation	(I-81 NB) (Ar	ea 4) (Phase 3)	
	<b>5455</b>	Install Aggregate Base Course (I-81 NB) (Area 4) (Phase 3)	22 01-09-25	02-28-25						I Install Age	Jregate Bas	e Course (I-81	1 NB) (Area 4	) (Phase 3)	
	5465	Install Asphalt Base Course (I-81 NB) (Area 4) (Phase 3)	18 01-27-25	03-07-25						Install Asp	shalt Base C	Course (I-81 N	lB) (Area 4) (I	Phase 3)	
	5475	Install Asphalt Intermediate Course (I-81 NB) (Area 4) (Phase 3)	6 03-10-25	03-21-25						Install As	phalt Interm	iediate Course	e (I-81 NB) (A	rea 4) (Phase 3)	
	5485	Install Guardrail (I-81 NB) (Area 4) (Phase 3)	13 02-10-25	03-10-25					[	Install Gu	ardrail (I-81	NB) (Area 4) (	(Phase 3)		
	5505	Restoration/Landscaping (I-81 NB) (Area 4) (Phase 3)	2 03-11-25	03-14-25						Restoration	on/Landscar	ping (I-81 NB)	(Area 4) (Ph	ase 3)	
	I-81 SB		311 11-20-23	07-18-25							8-25, I-81 S	В			
	AREA 4	Install Temporary Concrete Barrier (L81 SB) (Area 4) (Phase 3)	79 02-05-24	07-08-24					nstall Temp	24, AREA 4	oto Barrior (	(L81 SB) (Aro:	(Dhace 3		
	5525	Grading/Excavation (I-81 SB) (Area 4) (Phase 3)	6 02-08-24	02-10-24					Grading/Ev	cavation (I-8		4) (Phase 3)			į
	5535	Install Storm Drainage (I-81 SB) (Area 4) (Phase 3)	36 02-15-24	02-20-24					I Install St	orm Drainad	ie (1-81 SB)	(Area 4) (Pha	90-3)		
	5545	Install Site Lighting/ITS Installation (I-81 SB) (Area 4) (Phase 3)	69 02-15-24	06-28-24					linstall	Site Lighting	v/ITS Install:	ation (I-81 SB)	(Area 4) (Ph	ase 3)	
	5555	Install Median Barrier (I-81, SB) (Area 4) (Phase 3)	5 03-11-24	03-19-24					Install Med	lian Barrier (	(I-81 SB) (A	rea 4) (Phase	3)		
	5565	Install Aggregate Base Course (I-81, SB) (Area 4) (Phase 3)	18 03-29-24	05-02-24					Install Ac	idredate Bas	se Course (I	-81 SB) (Area	4) (Phase 3)		
	5575	Install Asphalt Base Course (I-81 SB) (Area 4) (Phase 3)	15 05-03-24	05-31-24					<ul> <li>Install A</li> </ul>	shhalt Base	Course (I-8	1 SB) (Area 4	) (Phase 3)		
	5585	Install Asphalt Intermediate Course (I-81 SB) (Area 4) (Phase 3)	5 06-03-24	06-10-24						sphalt Inter	mediate Co	urse (I-81 SB)	(Area 4) (Ph	ase 3)	
	5595	Install Guardrail (I-81 SB) (Area 4) (Phase 3)	5 06-04-24	06-11-24					I Install (	Guardrail (I-8	1 SB) (Area	4) (Phase 3)	,		
	5605	Construct Retaining Wall (Sta 713+90 - 714+60) (I-81 SB) (Area 4) (Phase 3)	8 02-22-24	03-08-24				<b>n</b> 1	Construct F	Retaining Wa	all (Sta 713	+90 - 714+60	(I-81 SB) (A	rea 4) (Phase 3)	
	5615	Restoration/Landscaping (I-81 SB) (Area 4) (Phase 3)	5 07-01-24	07-08-24					Restor	ation/Lands	caping (1-81	I SB) (Area 4)	(Phase 3)		
	AREA 3		196 11-28-23	11-27-24					1	1-27-24: AR	EA3	02)(0.000.)	(		
	5625	Install Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 3)	5 06-13-24	06-20-24					Install	Temporary C	Concrete Ba	rrier (I-81 SB)	(Area 3) (Pha	ase 3)	
	5635	Grading/Excavation (I-81 SB) (Area 3) (Phase 3)	9 06-18-24	07-02-24					Gradin	g/Excavatio	n (I-81 SB)	(Area 3) (Pha:	se 3)		
	5645	Install Storm Drainage (I-81 SB) (Area 3) (Phase 3)	46 06-24-24	09-04-24					🔲 Insta	all Storm Dra	ainage (I-\$1	SB) (Area 3)	(Phase 3)		
	5655	Install Site Lighting/ITS Installation (I-81 SB) (Area 3) (Phase 3)	91 06-24-24	11-15-24					in In	stall Site Lig	hting/ITS Ir	nstallation (I-8	1 SB) (Area 3	3) (Phase 3)	
	5665	Install Median Barrier (I-81 SB) (Area 3) (Phase 3)	5 09-05-24	09-12-24					I Inst	all Median B	arrier (I-81 5	SB) (Area 3) (I	Phase 3)		
	5675	Install Aggregate Base Course (I-81 SB) (Area 3) (Phase 3)	24 09-13-24	10-18-24					📕 ins	stall Aggrega	ite Base Co	urse (I-81 SB)	(Area 3) (Ph	ase 3)	
	5685	Install Asphalt Base Course (I-81 SB) (Area 3) (Phase 3)	19 09-24-24	10-22-24					📕 ins	stall Asphalt	Base Cours	e (I-81 SB) (A	rea 3) (Phase	e 3)	
	5695	Install Asphalt Intermediate Course (I-81 SB) (Area 3) (Phase 3)	6 10-24-24	10-31-24					I In	stall Asphalt	Intermediat	te Course (l-8	1 SB) (Area 3	) (Phase 3)	
	5705	Install Guardrail (I-81 SB) (Area 3) (Phase 3)	5 10-25-24	10-31-24					l In	stall Guardra	ail (I-81 SB)	(Area 3) (Pha	se 3)		
	<b>5715</b>	Construct Retaining Wall (Sta. 660+50 - 664+50) (I-81 SB) (Area 3) (Phase 3)	15 07-03-24	07-26-24					Const	ruct Retainir	ng Wall (Sta	ı. 660+50 - 66	4+50) (l-81 S	SB) (Area 3) (Phase 3)	
	<b>5725</b>	Restoration/Landscaping (I-81 SB) (Area 3) (Phase 3)	5 11-18-24	11-27-24					0 F	Restoration/L	andscaping	I-81 SB) (Ar	ea 3) (Phase	3)	
	5735	Construct Retaining Wall (Sta. 669+25 - 670+00) (I-81 SB) (Area 3) (Phase 3)	5 07-29-24	08-02-24					I Cons	truct Retainir	ng Wall (\$ta	a. 669+25 - 67	/0+00) (I-81 S	SB) (Area 3) (Phase 3)	
	<b>=</b> 5745	Construct Retaining Wall (Sta. 691+00 - 701+50) (I-81 SB) (Area 3) (Phase 3)	20 08-05-24	09-04-24					📕 Con	struct Retain	ing Wall (St	ta. 691+00 - 7	'01+50) (I-81	\$B) (Area 3) (Phase 3)	
	I-81 OVER RTE	E. 311 BRIDGE	111 11-28-23	07-11-24					07-11-	24, I-81 OVI	ER RTE. 31'	1 BRIDGE			
	<u>4705</u>	Partial Structure Removal (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	12 11-28-23	12-15-23				🛿 Pai	rtial Structu	ire Removal	(I-81 SB Ov	/er Rte. 311) (/	Area 3) (Pha	se 3)	
	<b>4715</b>	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte. 311) (Area 3) (Phas	10 12-18-23	01-16-24				🚺 Sເ	upport of E	xcavation/St	ructure Exc	avation (Abutr	ment A) (I-81	\$B Over Rte. 311) (Are	a 3
	4725	Drive Piles (Abutment A) (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	6 01-17-24	01-30-24					Drive Piles (/	Abutment A)	(I-81 SB O	ver Rte. 311) (	(Area 3) (Pha	ise 3)	
	4745	FRP Abutment (Abutment A) (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	7 01-31-24	02-13-24				0 F	-RP Abutm	ent (Abutme	nt A) (I-81 S	3B Over Rte. 3	311) (Area 3)	(Phase 3)	
	4755	Support of Excavation/Structure Excavation (Abutment B) (I-81 SB Over Rte. 311) (Area 3) (Phas	10 02-15-24	03-05-24					Support of	Excavation/	Structure E>	xcavation (Abi	utment B) (I-8	31 SB Over Rte. 311) (A	rea
	4775	Drive Piles (Abutment B) (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	6 03-08-24	03-19-24				0	Drive Piles	(Abutment I	B) (I-81 SB (	Over Rte. 311	) (Area 3) (Pl	nase 3)	
	4785	FRP Abutment (Abutment B) (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	7 03-22-24	04-02-24					FRP Abuti	ment (Abutm	1ent B) (I-81	SB Over Rte	. 311) (Area 3	3) (Phase 3)	
	4795	Girder Erection (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	7 05-06-24	05-17-24					Girder E	rection (I-81	SB Over Rt	.e. 311) (Area	3) (Phase 3)		
	4805	FRP Deck/Barrier Wall (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	14 05-20-24	06-13-24					FRP De	eck/Barrier W	/all (I-81 SB	Over Rte. 31	1) (Area 3) (P	hase 3)	
	4815	FKP Approach Slabs (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	8 06-14-24	06-27-24					ц нкрар	oproach Slat	os (I-81 SB (	Over Rte. 311	) (Area 3) (Pl	nase 3)	
	6175	Backwall & Joint Reconstruction (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	14 04-08-24	05-03-24					Backwall	& Joint Rec	onstruction	(I-81 SB Over	r Rte. 311) (A	rea 3) (Phase 3)	
	6185	Prep Existing Deck & Install Latex Overlay (I-81 SB Over Rte. 311) (Area 3) (Phase 3)	8 06-28-24	07-11-24					II Prep E	xisting Deck	K Install La	atex Overlay (I	I <del>-</del> 81 SB Over	кте. 311) (Area 3) (Pha	se (
		Install Temporary Concrete Barrier /L&1 SB) (Area 2) (Phase 2)	<u>262</u> 11-30-23 5 11 01 24	04-28-25				V	1 1-	-▼ 04-28-2	o, AREA 2	to Barrior /I 01	SB) (Area 2)	(Phase 3)	
	576F	Grading/Evavation (L81 SB) (Area 2) (Phase 2)	0 11-01-24	11-11-24									(Phace's)	r nase s)	
	5775	Install Storm Drainage (I-81 SB) (Area 2) (Phase 3)	50 11-14-24	03-10-25						Inetal Sta	1valiulii (I-01		rea 2) (Phace	3)	
	<b>U</b> 5115		50 11-14-24	05-10-25						<ul> <li>mətati 310</li> </ul>		ο, (ι-φ Ι φ <b>D</b> );(Al	ipa 2) (FilaSt		
	Actual Level of Effort	Remaining Work    Milestone	Page 11 of 12				Branch	orders	Joint Venti	ure					
	Actual Work	Critical Remaining Work	i age i i ui is							-					

C0011620	03DB108		I-81 Widening MM 136.6 - MM 141.8	Proposal Schedu	ule									03-0´	1-21 10:4
ity ID		Activity Name	Original Start	Finish	2021	2022	2023	2024	2025	20	026	2027	2028	2029	2030
	5705			0.1.10.05											
	<b>5</b> 785	Install Site Lighting/TS Installation (I-81 SB) (Area 2) (Phase 3)	70 11-14-24	04-18-25					Insta	all Site Lig	ghting/11S	Installation	(I-81 SB) (/	Area 2) (Phase;	3)
	<b>5</b> 795	Install Median Barrier (I-81 SB) (Area 2) (Phase 3)	5 01-14-25	01-23-25						/ledian Bą	Samer (I-81	SB) (Area	2) (Phase 3	2	
	5805	Install Aggregate Base Course (I-81 SB) (Area 2) (Phase 3)	25 01-23-25	03-21-25					Instal	I Aggrega	ate Base (	Course (I-81	SB) (Area 1	2) (Phase 3)	
	5815	Install Asphalt Base Course (I-81 SB) (Area 2) (Phase 3)	20 02-10-25	03-25-25					Instal	Asphalt	Base Cou	urse (I-81 SI	3) (Area 2) (	(Phase 3)	
	<b>5825</b>	Install Asphalt Intermediate Course (I-81 SB) (Area 2) (Phase 3)	6 03-27-25	04-04-25					l Insta	II Asphalt	tIntermed	liate Course	(I-81 SB) (/	Area 2) (Phase	3)
	<b>5835</b>	Install Guardrail (I-81 SB) (Area 2) (Phase 3)	5 03-28-25	04-04-25					Insta	Il Guardra	rail (I-81 SI	B) (Area 2) (	Phase 3)		
	<b>5845</b>	Construct Retaining Wall (Sta. 555+50 - 569+00) (I-81 SB) (Area 2) (Phase 3)	) 20 11-27-24	01-13-25					Constru	ct Retaini	ning Wall (	Sta. 555+50	) - 569+00)	(I-81 SB) (Area	2) (Pha
	<b>5855</b>	Restoration/Landscaping (I-81 SB) (Area 2) (Phase 3)	5 04-21-25	04-28-25					I Res	toration/L	Landscapi	ng (I-81 SB	) (Area 2) (F	Phase 3)	
	I-81 OVER RTE	E. 619 BRIDGE	177 11-30-23	10-25-24			▼		10-25-24, 1	-81 OVEF	R RTE. 61	19 BRIDGE			
	<b>4825</b>	Partial Structure Removal (I-81 SB Over Rte. 619) (Area 2) (Phase 3)	14 11-30-23	01-02-24				Partial Stru	ucture Remo	oval (I-81	I SB Over	Rte. 619) (/	Area 2) (Pha	ase 3)	
	<b>4835</b>	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte.	619) (Area 2) (Phas 10 01-03-24	01-24-24				Support o	of Excavatio	n/Structu	ure Excava	ation (Abuth	nent A) (I-81	SB Over Rte.	619) (Ar
	<b>4845</b>	Drive Piles (Abutment A) (I-81 SB Over Rte. 619) (Area 2) (Phase 3)	10 01-29-24	02-15-24				Drive Pile	es (Abutmer	nt A) (I-81	1 SB Over	Rte. 619) (/	Area 2) (Ph	ase 3)	
	<b>—</b> 4855	Construct MSE Walls (Abutment A) (I-81 SB Over Rte. 619) (Area 2) (Phase 3	3) 14 02-19-24	03-18-24				Constru	ict MSE Wa	ılls (Abutn	ment A) (I	-81 \$B Ove	r Rte. 619) (	(Area 2) (Phase	<del>;</del> 3)
	<b>4865</b>	FRP Abutment (Abutment A) (I-81 SB Over Rte. 619) (Area 2) (Phase 3)	10 03-19-24	04-05-24				FRP At	outment (Ab	outment A	A) (I-81 SI	3 Over Rte.	619) (Area	2) (Phase 3)	
	4875	Support of Excavation/Structure Excavation (Abutment B) (I-81 SB Over Rte.	619) (Area 2) (Phas 10 04-08-24	04-26-24				Suppo	nt of Excav	ation/Stru	ucture Exc	avation (Ab	utment B) (	(I-81 SB Over F	te. 619)
	4885	Construct MSE Walls (Abutment B) (I-81 SB Over Rte. 619) (Area 2) (Phase 3	3) 14 04-29-24	05-23-24				Cons	truct MSE	Walls (Abi	utment B)	) (I-81 SB C	ver Rte. 61	9) (Area 2) (Phr	ase 3)
	4895	Drive Piles (Abutment B) (I-81 SB Over Rte. 619) (Area 2) (Phase 3)	10 05-24-24	06-11-24				Drive	Piles (Abu	tment B)	(I-81 SB (	Over Rte. 6	19) (Area 2)	) (Phase 3)	
	4905	FRP Abutment (Abutment B) (I-81 SB Over Rte. 619) (Area 2) (Phase 3)	10 06-13-24	06-28-24					Abutment	(Abutmer	ent B) (I-81	SB Over R	te. 619) (År	ea 2) (Phase 3	)
	4915	Girder Erection (I-81 SB Over Rte, 619) (Area 2) (Phase 3)	10 07-01-24	07-16-24				I Gire	der Erection	າ (I-81 SB	3 Over Rte	e. 619) (Area	a 2) (Phase	3)	
	4925	FRP Deck/Barrier Wall (I-81 SB Over Rte, 619) (Area 2) (Phase 3)	35 08-19-24	10-11-24					FRP Deck/F	Barrier Wa	all (1-81 SF	B Over Rte	619) (Area	2) (Phase 3)	
	4935	FRP Approach Slabs (I-81 SB Over Rte, 619) (Area 2) (Phase 3)	9 10-14-24	10-25-24	_				FRP Appro	ach Slab	s (I-81 SB	3 Over Rte	619) (Area :	2) (Phase 3)	
		E 635 BRIDGE	181 11-30-23	10-31-24			-		10-31-24	I-81 OVE		35 BRIDGE	,	-),(11466-0)	
	4945	Partial Structure Removal (I-81 SB Over Rte, 635) (Area 2) (Phase 3)	14 11-30-23	01-02-24	_			Partial Stru	ucture Remo	oval (1-81	I SB Over	Rte. 635) (	Area 2) (Ph	ase 3)	
	4955	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte.	635) (Area 2) (Phas 10 01-03-24	01-24-24				Support o	of Excavatio	on/Structu	ure Excava	ation (Abutr	nent A) (I-8	1 SB Over Rte	635) (År
	4965	Drive Piles (Abutment A) (I-81 SB Over Rte, 635) (Area 2) (Phase 3)	10 01-29-24	02-15-24					s (Abutmer	nt A) (I-81	1 SB Over	Rte 635) (	Δrea 2) (Ph	ase 3)	
	4900	Construct MSE Walk (Abutment A) (I-81 SB Over Pte, 635) (Area 2) (Phase 3)	3) 14 02-19-24	03-18-24						alle (Abutr			r Pto 635	(Area 2) (Phase	3)
	4975	ERP Abutment (Abutment A) (L81 SB Over Rte, 635) (Area 2) (Phase 3)		04-05-24	_				utmont (Ab				635) (Area	(2) (Phase 3)	, 0,
	4905	Support of Evoluation/Structure Evoluation (Abutmont P) (1.81 SP Quar Bto	625) (Area 2) (Phase 10 04 08 24	04-03-24						notion/@tr		over Ne.			Ho (625)
	4995	Support of Excavation/Structure Excavation (Abutthent B) (1-61 SB Over Rie.	0000 (Alea 2) (Filas 10 04-08-24	04-20-24	_										le. 039)
	5005	Drive Dilac (Abuttment D) (1.04 CD Cruze Dta, COS) (Area 2) (Phase 3)	5) 14 04-29-24	00-23-24										) (Alea 2) (File	ise 3)
	5015	Drive Pries (Abutthent B) (1-81 SB Over Rte. 635) (Area 2) (Priase 3)	10 05-24-24	06-11-24	_				Plies (ADU	(ment b)			ss) (Alea ∠)	(Phase 3)	
	5025	FRP Abutment (Abutment B) (I-81 SB Over Rte. 635) (Area 2) (Phase 3)	10 06-13-24	06-28-24	_				Abutment	(Abutmer	ent B) (1-81	SB Over R	(Ar	ea 2) (Phase 3)	1
	5035	Girder Erection (I-81 SB Over Rte. 635) (Area 2) (Phase 3)	10 07-01-24	07-16-24						i (I-81 SB	S Over Rte	. 635) (Area	12) (Phase	3)	
	5045	FRP Deck/Barrier Wall (I-81 SB Over Rte. 635) (Area 2) (Phase 3)	37 08-22-24	10-17-24					FRP Deck/L	Barner Wa	/all (I-81 SI	B Over Rte	635) (Area	2) (Phase 3)	
	5055	FRP Approach Slabs (I-81 SB Over Rte. 635) (Area 2) (Phase 3)	9 10-18-24	10-31-24				U	FRP Appro	ach Slabs	os (I-81 SE	3 Over Rte. (	535) (Area 2	2) (Phase 3)	
	AREA 1		311 11-20-23	07-18-25					0	7-18-25, /	AREA 1				
	5865	Install Temporary Concrete Barrier (I-81 SB) (Area 1) (Phase 3)	5 04-07-25	04-15-25					Insta	Il lempor	orary Conc	rete Barner	(I-81 SB) (A	rea 1) (Phase :	3)
	5875	Grading/Excavation (I-81 SB) (Area 1) (Phase 3)	5 04-14-25	04-21-25					Grac	ling/Exca	avation (I-8	31 SB) (Area	a 1) (Phase	3)	
	5885	Install Storm Drainage (I-81 SB) (Area 1) (Phase 3)	25 04-18-25	06-05-25					L Ins	stall Storm	m Drainag	e (I-81 SB)	(Area 1) (Ph	iase 3)	
	5895	Install Site Lighting/ITS Installation (I-81 SB) (Area 1) (Phase 3)	40 04-18-25	07-01-25					🔲 İn	istall Site	e Lighting/I	TS Installat	ion (I-81 \$E	3) (Area 1) (Pha	se 3)
	<u> </u>	Install Median Barrier (I-81 SB) (Area 1) (Phase 3)	5 06-02-25	06-09-25					l Ins	stall Media	lian Barrier	r (I-81 SB) (/	Area 1) (Ph	ase 3)	
	<b>5</b> 915	Install Aggregate Base Course (I-81 SB) (Area 1) (Phase 3)	14 05-19-25	06-12-25					🚺 Ins	stall Aggre	regate Bas	se Course ()	-81 SB) (Ar	ea 1) (Phase 3)	1 1
	<b>5925</b>	Install Asphalt Base Course (I-81 SB) (Area 1) (Phase 3)	11 06-10-25	06-27-25					🛛 In	stall Asph	halt Base	Course (I-8	1 SB) (Area	1) (Phase 3)	
	<b>5935</b>	Install Asphalt Intermediate Course (I-81 SB) (Area 1) (Phase 3)	3 06-30-25	07-02-25					l In	istall Asph	halt Intern	nediate Cou	ırse (I-81 SI	3) (Area 1) (Pha	ase 3)
	<b>5</b> 945	Install Guardrail (I-81 SB) (Area 1) (Phase 3)	6 07-01-25	07-10-25					l Ir	nstall Gua	ardrail (I-8 <sup>-</sup>	1 SB) (Area	1) (Phase :	3)	
	5955	Construct Retaining Wall (Sta. 537+00 - 555+50) (I-81 SB) (Area 1) (Phase 3)	20 04-22-25	05-30-25					Co	nstruct Re	Retaining V	Nall (Sta. 5	37+00 - 555	+50) (I-81 SB)	(Area 1)
	5965	Restoration/Landscaping (I-81 SB) (Area 1) (Phase 3)	5 07-11-25	07-18-25					IR	Restoration	on/Landsc	aping (I-81	SB) (Area 1	) (Phase 3)	
	I-81 OVER RTE	E. 112 BRIDGE	248 11-20-23	03-24-25				i i i	03-24	4-25, I-81		TE. 112 BR	IDGE		
	5065	Partial Structure Removal (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	18 11-20-23	12-21-23				Partial Stru	cture Remo	oval (I-81	SB Over	Rte. 112) (A	rea 1) (Pha	ise 3)	
	5075	Support of Excavation/Structure Excavation (Abutment A) (I-81 SB Over Rte.	112) (Area 1) (Phas 10 01-02-24	01-23-24				Support o	f Excavatio	on/Structu	ure Excava	ation (Abutr	nent A) (I-81	1 SB Over Rte.	
	5085	Drive Piles (Abutment A) (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	9 01-24-24	02-12-24				Drive Pile	s (Abutmer	nt A) (I-81	1 SB Over	Rte. 112) (	Area 1) (Ph	ase 3)	
	5095	Construct MSE Walls (Abutment A) (I-81 SB Over Rte 112) (Area 1) (Phase 3	) 18 02-13-24	03-22-24					ict MSF W∕⊧	alls (Abutr	ment AV (I	-81 SB Ove	r Rte. 112	(Area 1) (Phase	± 3)
	Actual Level of Effort [ Actual Work		Page 12 of 13	03-22-24			Branch-Ord	ers Joint Ve	enture		Inenit A) (I	-01 2D 0/6			· 3) <sub>1</sub>

C00116203DB	108	I-81	Widening MM 136	.6 - MM 141.	8 Proposal Schedu	ule												03-0	)1-21 10:45
Activity ID		Activity Name	Origina	Start	Finish	202		2022	20	23	2024	20	25	2026	20	27 2	2028	2029	2030
			Duration			QC				QQ	QQQ	QQQ	QQC		QQQ	QQQ			
	<b>=</b> 5105	FRP Abutment (Abutment A) (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	7	03-25-24	04-04-24						I FRP	Abutment	: (Abutme	ent A) (I <del>-</del> 8	31 SB Ov	er Rte. 112	) (Area 1) (	Phase 3)	
	<b>=</b> 5115	Support of Excavation/Structure Excavation (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Phase	s 18	08-13-24	09-09-24							Support	of Excav	ation/Stru	ucture Ex	cavation (A	butmentB	) (I-81 SB (	Over Rte. 112
	<b>=</b> 5125	Construct MSE Walls (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	18	09-10-24	10-07-24							l Constru	ct MSE V	Walls (Abu	utment E	8) (I-81 SB C	Over Rte. 1	12) (Area 1	i) (Phase 3)
	<b>=</b> 5135	Drive Piles (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	ç	10-08-24	10-21-24							Drive P	iles (Abu	tment B)	(I-81 SB	Over Rte. 1	12) (Area	1) (Phase 3	3)
	<b>5145</b>	FRP Abutment (Abutment B) (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	7	10-22-24	10-31-24							FRP AL	outment (	(Abutmen	nt B) (I-81	SB Over F	Rte. 112) (A	rea 1) (Pha	ase 3)
	<b>=</b> 5155	Girder Erection (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	8	11-01-24	11-15-24							Girder	Erection	(I-81 SB	Over Rte	e. 112) (Area	a 1) (Phas	e 3)	
	<b>=</b> 5165	FRP Deck/Barrier Wall (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	45	11-18-24	03-03-25					i i		FF	RP Deck/I	Barrier Wa	all (I-81 S	B Over Rte	. 112) (Are	a 1) (Phase	e 3)
	<b>5175</b>	FRP Approach Slabs (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	g	03-04-25	03-24-25							D F	RP Appro	ach Slab	os (I-81 S	B Over Rte	. 112) (Are	a 1) (Phase	ə 3)
	6215	Support of Excavation/Structure Excavation Pier (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	7	04-05-24	04-19-24						🛛 Şup	port of Ex	cavation/	Structure	Excavat	ion Pier (I-8	1 SB Over	Rte. 112) (	(Årea 1) (Phas
	6225	Install Micropiles at Pier (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	23	05-17-24	06-27-24						🗖 🗖 🗖	stall Micro	pilės at I	Pier (I-81	SB Over	Rte. 112) (/	Area 1) (Pł	iase 3)	
	6235	FRP Pier Footer (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	10	06-28-24	07-15-24						0	RP Pier F	ooter (I-8	1 SB Ove	er Rte. 1	12) (Area 1)	(Phase 3)		
	6245	FRP Pier Stem/Cap (I-81 SB Over Rte. 112) (Area 1) (Phase 3)	18	07-16-24	08-12-24							FRP Pier	Stem/Ca	p (I-81 \$E	B Over R	te. 112) (Ar	ea 1) (Pha	se 3)	
PH/	ASE 4		132	04-07-25	11-14-25					i i		-	1	1+14+25, F	PHASE 4				
	-81 NB		81	04-07-25	08-26-25							-	08-2	6-25, I-81	I NB				
	AREA 1		14	04-07-25	05-01-25							<b>•</b>	05-01-25	, AREA 1					
	<b>5180</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area 1) (Phase 4)	7	04-07-25	04-18-25							1	Remove	Temporar	y Concre	te Barrier (I	-81 NB) (A	rea 1) (Pha	use 4)
	<b>5190</b>	Install Asphalt Surface Course (I-81 NB) (Area 1) (Phase 4)	7	04-15-25	04-25-25							•	nstall As	phalt Surf	face Cou	rse (I-81 NE	3) (Area 1)	(Phase 4)	
	<b>5200</b>	Install Permanent Pavement Markings/Signage (I-81 NB) (Area 1) (Phase 4)	6	04-22-25	05-01-25								Install Pe	rmahent	Paveme	nt Markings	/Signage	1-81 NB) (A	Area 1) (Phase
	AREA 2		24	05-02-25	06-17-25					i i		-	06-17-2	25, AREA	2				
	<b>5210</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area 2) (Phase 4)	13	05-02-25	05-29-25								Remove	Tempora	ary Conc	rete Barrier	(I-81 NB) (	Area 2) (Ph	nase 4)
	<b>5220</b>	Install Asphalt Surface Course (I-81 NB) (Area 2) (Phase 4)	13	05-19-25	06-10-25								Install A	sphalt \$u	urface Co	ourse (l-81 l	NB) (Area 2	) (Phase 4	4)
	<b>5230</b>	Install Permanent Pavement Markings/Signage (I-81 NB) (Area 2) (Phase 4)	10	06-02-25	06-17-25								Install F	Permanen	nt Paven	ent Markin	gs/Signage	e (I-81 NB)	(Area 2) (Pha
	AREA 3		22	06-19-25	07-24-25							•	▼ 07-24	-25, AREA	А З				
	<b>5240</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area 3) (Phase 4)	12	06-19-25	07-08-25								Remo	ve Tempo	orary Cor	crete Barrie	er (I-81 NB)	(Area 3) (F	Phase 4)
	<b>5250</b>	Install Asphalt Surface Course (I-81 NB) (Area 3) (Phase 4)	12	06-30-25	07-18-25								Install	Asphalt S	Surface C	ourse (I-81	NB) (Area	3) (Phase	4)
	<b>5260</b>	Install Permanent Pavement Markings/Signage (I-81 NB) (Area 3) (Phase 4)	10	07-10-25	07-24-25								Install	Permane	ent Pave	ment Marki	ngs/Signa	ge (I-81 NB	s) (Area 3) (Ph
	AREA 4		21	07-25-25	08-26-25					i i			₩ 08-2	6-25, ARE	EA 4				
	<b>5270</b>	Remove Temporary Concrete Barrier (I-81 NB) (Area 4) (Phase 4)	11	07-25-25	08-11-25								Remo	ove Temp	orary Co	ncrete Barr	ier (I-81 NE	3) (Area 4) (	(Phase 4)
	5280	Install Asphalt Surface Course (I-81 NB) (Area 4) (Phase 4)	11	08-04-25	08-20-25								Insta	ll Asphalt	Surface	Course (I-8	1 NB) (Are	a 4) (Phase	e 4)
	5290	Install Permanent Pavement Markings/Signage (I-81 NB) (Area 4) (Phase 4)	g	08-14-25	08-26-25								I Insta	ll Perman	nent Pav	ement Marl	kings/Sigha	ge (I-81 N	B) (Area 4) (P
	81 SB		51	08-27-25	11-14-25					i i			1	1-14-25, I	-81 SB				
	AREA 4		17	08-27-25	09-23-25								₩ 09-2	23-25, AR	REA 4				
	<b>=</b> 5300	Remove Temporary Concrete Barrier (I-81 SB) (Area 4) (Phase 4)	ç	08-27-25	09-10-25					i i			Ren	nove Tem	nporary C	oncrete Ba	rrier (I-81 S	B) (Area 4)	) (Phase 4)
	<b>=</b> 5310	Install Asphalt Surface Course (I-81 SB) (Area 4) (Phase 4)	9	09-03-25	09-16-25								🛿 Inst	all Asphal	lt Surface	e Course (I-	81 SB) (Ar	ea 4) (Phas	se 4)
	<b>5320</b>	Install Permanent Pavement Markings/Signage (I-81 SB) (Area 4) (Phase 4)	8	09-11-25	09-23-25								l Inst	all Perma	anent Pa	vement Ma	rkings/Sigr	age (I-81 S	SB) (Area 4) (I
	AREA 3		22	09-11-25	10-14-25								👿 10	-14-25, AF	REA 3				
	<b>=</b> 5330	Remove Temporary Concrete Barrier (I-81 SB) (Area 3) (Phase 4)	12	09-11-25	09-29-25								Rer	nove Terr	nporary (	Concrete Ba	arrier (I-81	SB) (Area 3	3) (Phase 4)
	<b>= 5340</b>	Install Asphalt Surface Course (I-81 SB) (Area 3) (Phase 4)	12	09-22-25	10-08-25								l Ins	tall Aspha	alt Surfac	e Course (l	-81 SB) (A	ea 3) (Pha	ise 4)
	<b>=</b> 5350	Install Permanent Pavement Markings/Signage (I-81 SB) (Area 3) (Phase 4)	10	09-30-25	10-14-25								l Ins	tall Perma	anent Pa	avement Ma	arkings/Sig	nage (I-81	\$B) (Area 3) (
	AREA 2		22	09-30-25	10-31-25								<b>W</b> 10	)-31-25, A	REA 2				
	<b>5360</b>	Remove Temporary Concrete Barrier (I-81 SB) (Area 2) (Phase 4)	13	09-30-25	10-20-25								Re	move Ter	mporary	Concrete B	arrier (I-81	SB) (Area 2	2) (Phase 4)
	<b>5370</b>	Install Asphalt Surface Course (I-81 SB) (Area 2) (Phase 4)	13	10-09-25	10-28-25								📕 In:	stall Asph	alt Surfa	ce Course (	I-81 SB) (A	rea 2) (Pha	ase 4)
	<b>5</b> 380	Install Permanent Pavement Markings/Signage (I-81 SB) (Area 2) (Phase 4)	10	10-20-25	10-31-25								l Ins	stall Perm	nanent P	avement M	arkings/Sig	nage (I-81	SB) (Area 2)
5	AREA 1		17	10-21-25	11-14-25								<b>T</b> 11	1+14+25, A	AREA 1				
	5390	Remove Temporary Concrete Barrier (I-81 SB) (Area 1) (Phase 4)	7	10-21-25	10-29-25								I Re	emove Tei	mporary	Concrete B	arrier (I-81	SB) (Area	1) (Phase 4)
	<b>5</b> 400	Install Asphalt Surface Course (I-81 SB) (Area 1) (Phase 4)	7	10-27-25	11-04-25								l In	stall Asph	alt Surfa	ce Course (	(I-81 \$B) (/	Area 1) (Pha	ase 4)
	<b>=</b> 5410	Install Permanent Pavement Markings/Signage (I-81 SB) (Area 1) (Phase 4)	8	11-03-25	11-14-25								🛿 In	stall Pern	manent F	avement N	1arkings/Si	ghage (I-81	1 SB) (Area 1)
🗗 СОМ	PLETION ACT	TIVITIES	62	11-15-25	01-15-26								-	01-15-26	6, COMP	LETIONAC	TIVITIES		
	0	Cleanup - Punchlist	62	11-15-25	01-15-26									Cleanub	- Punch	ist			
	-				0.1020	i	; ;	<u>; ; ;</u>	;;;;	i i	1		í <b>–</b>	2.041100			<u>i i i</u>	<u>i i i</u>	<u>. ; ; ; ;</u>
	all evel of Effort	Remaining Work		ao 12 of 12					Brand	h-Ord	ars loint	Venture							
	al Work		Pa	เye เจบเ เจ								· ontaro							ſ