

DIVISION VI – ROADSIDE DEVELOPMENT

SPECIAL PROVISION COPIED NOTES (SPCNs), SPECIAL PROVISION (SPs) and SUPPLEMENTAL SPECIFICATIONS (SSs)

VDOT web file users ("pdf") may obtain more information and other resources by downloading the accompanying "zip" file (compressed WORD[®] files). <u>http://www.virginiadot.org/business/resources/const/07ImpRev.zip</u>

These sheets may also be found at the following locations: Global Web Access: <u>http://www.virginiadot.org/business/const/spec-default.asp</u>

VDOT Only Access: https://outsidevdot.cov.virginia.gov/P0JQP/2007_Standard_Specifications/Forms/AF.aspx

TABLE OF CONTENTS

STANDARD 600 SERIES SPCNs	s, SPs and SSs ———	- 6-1	
SS60301 - SUPP. SEC. 603—SEEDING	9-3-14	6-2	
SS60901 - SUPP. SEC. 609—TREE WEL	LS AND TREE WALLS	1-25-106-3	
CNSP SELECT USE 600 SERIES SPCNs and SPs			
NONE		6-5	

1-2-3-

4-

5-6-

GUIDELINES — FOR USE WHEN SEEDING IS REQUIRED.

SS60301-0914

September 3, 2014

VIRGINIA DEPARTMENT OF TRANSPORTATION 2007 ROAD AND BRIDGE SUPPLEMENTAL SPECIFICATIONS

SUPPLEMENTAL SECTION 603—SEEDING

SECTION 603—SEEDING of the Specifications is amended as follows:

Section 603.03(d) Applying Seed is amended to replace the third paragraph with the following:

Where temporary seeding is employed as a means of soil stabilization it shall consist of applying seed, fertilizer, and mulch in accordance with the rates specified in the plans or in Section 603.03 of the Specifications to stabilize areas on which grading operations are anticipated to be suspended for durations greater than 14 days. Where temporary seeding is required or directed by the Engineer, the cost for removal of vegetation once grading operations resume shall be included in the price of seeding.

^{*}These SPECIFICATIONS REVISIONS are subject to change on short notice.

GUIDELINES — FOR USE WHEN TREE WELLS AND TREE WALLS ARE REQUIRED.

SS60901-0310

January 25, 2010

VIRGINIA DEPARTMENT OF TRANSPORTATION 2007 ROAD AND BRIDGE SUPPLEMENTAL SPECIFICATIONS

SUPPLEMENTAL SECTION 609—TREE WELLS AND TREE WALLS

SECTION 609—TREE WELLS AND TREE WALLS of the Specifications is amended as follows:

Section 609.04—Measurement and Payment is amended to replace the first paragraph with the following:

Tree wells and tree walls will be measured in cubic yards of masonry, complete-in-place, and will be paid for at the contract unit price per cubic yard of masonry. This price shall include excavation; and furnishing and installing drain pipe, geotextile fabric and backfill, including aggregate.

– CNSP SELECT USE 600 SERIES SPCNs and SPs ——

The following are Select Use Special Provisions. None have been through the Department's complete Specifications Committee review/comment/acceptance process and are not part of the Standard Specifications. They are to be considered as project-specific and may be subject to modifications required to meet specific project conditions or requirements for Federal funding. Anyone making modifications is responsible for obtaining the appropriate expertise in the discipline applicable to the modification. If modifications are made the date <u>must</u> also be changed to reflect the current date. Please send a copy of the modified special provision with the new date and specific project number to <u>David.Gayle@VDOT.Virginia.gov</u> so it may be added to the <u>Specifications</u> <u>Stockpile</u>.

NONE

^{*}These SPECIFICATIONS REVISIONS are subject to change on short notice.